


MARTINUS RAIL





Document Control

| DOCUMENT TITLE: | Construction Biodiversity Management Plan – Stage C | | | |
|--------------------|--------------------------------------------------------------------|--|------------------------------------------------------|------------|
| DOCUMENT OWNER: | Chris Standing – Environment, Approvals and Sustainability Manager | | | |
| PREPARED BY: | Alison Kriegel TITLE: | | Environmental Approvals Lead | |
| SIGNATURE: | ausm Knegel | | DATE: | 23/09/2025 |
| REVIEWED BY: | Chris Standing TITLE: | | Environment, Approvals and Sustainability Manager | |
| SIGNATURE: | lSq | | DATE: | 23/09/2025 |

Approved by

| NAME | TITLE | SIGNATURE | DATE |
|---------------|------------------|-----------|------------|
| Andy Williams | Project Director | Alle | 23/09/2025 |

Revision History

| REVISION | REVISION DATE | AMENDMENT | DATE TO CLIENT |
|----------|---------------|---------------------|----------------|
| А | 17/09/2025 | To consider Stage C | 17/09/2025 |
| 0 | 23/09/2025 | For ER approval | 23/09/2025 |

Disclaimer: This document has been prepared by Martinus. Use of this document shall be subject to the terms of the relevant contract with Martinus. The electronic file of this current revision is the controlled copy. This file is stored on Martinus' server located at Head Office, Unit 1, 23-27 Waratah St, Kirrawee, NSW.

This document is the property of and contains proprietary information owned by Martinus. No permission is granted to publish, reproduce, transmit or disclose to another party, any information contained in this document, in whole or in part, without prior written permission from the issuing authority.

For the purpose of this document, Martinus refers to the Martinus Group of companies.

This document is uncontrolled when printed.



TABLE OF CONTENTS

| GLO | SSARY | |
|--------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|
| 1 | INTRODUCTION | ç |
| 1.1 | Project overview | |
| 1.2 | Planning context | |
| 1.3 | Statutory context and approval | |
| 1.4 | Scope of this Stage C Plan | 10 |
| 1.4.1 | 3 - 3 | 10 |
| 1.4.2 | | |
| 1.5 | Interactions with other management plans and strategies | |
| 1.6 | Consultation | |
| 1.6.1 | | |
| 1.6.2 | Ongoing consultation during construction | 15 |
| | PURPOSE AND OBJECTIVES | |
| 2.1 | Purpose | |
| 2.2 | Objectives | |
| 2.3 | Targets | |
| 2.4 | Performance outcomes | |
| 2.5 | SMART principles | 1 <i>i</i> |
| 3 | ENVIRONMENTAL REQUIREMENTS | |
| 3.1 | Legislation | |
| 3.2 | Guidelines and standards | |
| 3.3 | Minister's Conditions of Approval | |
| 3.4 | Updated Mitigation Measures | |
| 3.5 | Infrastructure Sustainability Council requirements | 28 |
| | EXISTING ENVIRONMENT | |
| 4.1 | Environmental aspects | |
| 4.1.1 | 9 | |
| 4.1.2 | | |
| 4.1.3 | | |
| 4.1.4 | | |
| 4.1.5 | | |
| 4.2 4.2.1 | Weeds and biosecurity | |
| 4.2.1 | Matters of National Environmental Significance | |
| 4.3.1 | The state of the s | |
| 4.3.2 | | |
| 4.3.3 | | |
| 4.3.4 | · · · · · · · · · · · · · · · · · · · | |
| 5 | ENVIRONMENTAL ASPECTS AND IMPACTS | 20 |
| 5 .1 | Construction activities. | |
| 5.2 | Ecological impacts | |
| 5.2.1 | | |
| 5.2.2 | | |
| 5.2.3 | | |
| 5.2.4 | | |
| 5.2.5 | Injury and mortality of fauna | 42 |
| 5.2.6 | | |
| 5.2.7 | | |
| 5.2.8 | | |
| 5.2.9 | Noise, vibration, dust, light and contaminants | 43 |
| 6 | MANAGEMENT AND MITIGATION | 44 |
| 6.1 | Vegetation clearing process | |
| 6.1.1 | | |
| 6.1.2 | Management of fauna during pre-clearing | 45 |





| 6.1.3 | Pre-clearing survey report | 47 |
|--------|---------------------------------------------------------|-----|
| 6.1.4 | Staged or non-staged clearing | 47 |
| 6.1.5 | 5 Post-clearing report | 48 |
| 6.1.6 | | |
| 6.1.7 | | |
| 6.2 | Re-use of woody debris and landscape features | |
| 6.2.1 | | |
| 6.3 | Aquatic and riparian habitat | |
| | | |
| 6.3.1 | 1 7 7 3 | |
| 6.4 | Weed, pest and pathogen control | |
| 6.4.1 | , | |
| 6.5 | Unexpected threatened species finds | |
| 6.6 | Fauna rescue and release procedure | 52 |
| 6.7 | Vegetation rehabilitation | |
| 6.8 | Biodiversity offsets | 53 |
| 6.9 | Sloane's Froglet Surveys | 53 |
| 6.10 | Fauna Connectivity Strategy | 53 |
| 6.11 | Management and mitigation measures | |
| | | |
| 7 | COMPLIANCE MANAGEMENT | |
| 7.1 | Roles and responsibilities | 66 |
| 7.2 | Training | 66 |
| 7.3 | Monitoring | 66 |
| 7.4 | Inspections | 66 |
| 7.5 | Auditing | |
| 7.6 | Reporting and identified records | |
| | | |
| 8 | REVIEW AND IMPROVEMENT | 68 |
| 8.1 | Continuous improvement | 68 |
| 8.2 | Update and amendment | 68 |
| | | |
| APP | PENDICES | 69 |
| | | |
| | PENDIX A | |
| Unex | xpected Threatened Species Finds Procedure | 70 |
| A DD | PENDIX B | 74 |
| | na Handling and Rescue Procedure | |
| raun | na Handling and Rescue Procedure | |
| ۸ DD | PENDIX C | 72 |
| | sitive Area Mapping - Biodiversity | |
| OCIIS | silive Area Mapping - Diodiversity | 12 |
| APP | PENDIX D | 94 |
| | ne's Froglet Survey | |
| Oloui | 110 0 1 10 glot 0 al 10 g | |
| APP | ENDIX E | 95 |
| | Rating | |
| | | |
| | ENDIX F | |
| PSR | and CEMF Requirements | 100 |
| | | |
| | ENDIX G | |
| Cons | struction Biodiversity Monitoring Program | 105 |
| A D.D. | ENDIV II | 400 |
| APP | PENDIX H | 106 |
| Ihrea | atened Species Identification | 106 |
| | | |
| | | |
| | | |
| LIS | ST OF TABLES | |
| | e 1: Consultation summary | 10 |
| | e 2: Performance objectives (construction biodiversity) | |
| | | |
| rable | e 3: CoA relevant to this Plan | 19 |



A2I | ALBURY TO ILLABO

CONSTRUCTION BIODIVERSITY MANAGEMENT PLAN - STAGE C

| Table 4: UMMs relevant to this Plan | 25 |
|------------------------------------------------------------------------------------------------------------------------------|------|
| Table 5: IS ECO-1 Ecological value targets | 28 |
| Table 6: IS ECO-2 habitat connectivity targets | 29 |
| Table 7: Extent of White Box – Yellow Box – Blakely's Red Gum Grassy Woodland and Derived Native Grassland threatened | |
| ecological community within the study area | 30 |
| Table 8: Species with suitable habitat within the project site | 31 |
| Table 9: Threatened fauna recorded in the study area | 32 |
| Table 10: Priority weeds and weeds of National Significance | 33 |
| Table 11: Mapped TEC and endangered species | 36 |
| Table 12: direct impacts on non-native vegetation within the inland slopes ibra subregion and the corresponding precinct and | |
| enhancement sites | 39 |
| Table 13: Direct impacts on native vegetation within the Lower Slopes IBRA subregion and the corresponding precinct and | |
| enhancement sites | 39 |
| Table 14: Direct impacts on native vegetation within the Inland Slopes IBRA subregion and the corresponding precinct and | |
| enhancement sites | . 39 |
| Table 15: Direct impacts on TEC due to the Project | |
| Table 16: Direct impacts on threatened species credit species within the Project | .41 |
| Table 17: Potential microbat roosting habitat | |
| Table 18: Plant community types clearing limits | . 48 |
| Table 19: Clearing limits for threatened fauna species | . 49 |
| Table 20: Biodiversity management and mitigation measures | . 54 |



GLOSSARY

| TERM | DEFINITION |
|---------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| A2I | Albury to Illabo section of the Inland Rail project |
| A2P CEMF | Albury to Parkes Construction Environmental Management Framework (0-0000-900-EEC-00-SP-0002_2); |
| ARTC | Australian Rail Track Corporation |
| BAM | Biodiversity Assessment Method |
| BC Act | Biodiversity Conservation Act 2016 (NSW) |
| BCS | Biodiversity, Conservation and Science Directorate of DCCEEW (former) |
| BDAR, Revised | Biodiversity Development Assessment Report that comprises Part 1 and Part 2 of the Revised Technical Paper 8: Biodiversity Development Assessment Report (WSP, February 2024) |
| CAMBA | China-Australia Migratory Bird Agreement |
| CBMP | Construction Biodiversity Management Plan – Stage C (this Plan) |
| CCS | Community Communications Strategy |
| CEMF | Construction Environmental Management Framework |
| CEMP | Construction Environmental Management Plan |
| ССНМР | Construction Heritage Management Plan |
| CIZ | Construction Impact Zone |
| CMP | Construction Monitoring Plan |
| CMS | Complaints Management System |
| CoA | Conditions of Approval |
| Construction | Includes work required to construct the CSSI as defined in the Project Description described in the documents listed in Condition A1 including commissioning trials of equipment and temporary use of any part of the CSSI but excluding Low Impact Work which is carried out or completed prior to approval of the CEMP. |
| CPESC | Certified Professional in Erosion and Sediment Control |
| CPHR | Conservation Programs, Heritage and Regulation Group of the NSW Department of Climate Change, Energy, the Environment and Water (formerly BCS) |
| CSSI | Critical State Significant Infrastructure |
| CSWMP | Construction Soil and Water Management Plan |
| CWMS | Construction Work Method Statement |



| TERM | DEFINITION | |
|--------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|
| CWCHMMP | Construction Waste, Contamination and Hazardous Materials Management Plan | |
| DAWE | Department of Agriculture, Water and Environment | |
| DCCEEW | Department of Climate Change, Energy, the Environment and Water | |
| DCCEEW (Cth) | Commonwealth Department of Climate Change, Energy, the Environment and Water | |
| DEC | Department of Environment and Conservation | |
| DIPNR | Department of Infrastructure, Planning and Natural Resources | |
| DPE | NSW Department of Planning and Environment | |
| DPHI | Department of Planning, Housing and Infrastructure | |
| DPI | Department of Primary Industries | |
| DPIE | Department of Planning, Industry and Environment | |
| EAD | Environmental Assessment Documentation that includes: Inland Rail – Albury to Illabo Environmental Impact Statement (ARTC, August 2022); Albury to Illabo Response to Submissions (ARTC, November 2023); Albury to Illabo Preferred Infrastructure Report (ARTC, November 2023); Albury to Illabo Preferred Infrastructure Report Response to Submissions (ARTC, February 2024); Inland Rail – Albury to Illabo (SSI-10055) Response to request for additional information – Air Quality Assessment (letter dated 1 May 2024); Part 1 - Revised Technical Paper 8: Biodiversity Development Assessment Report (WSP, February 2024); Part 2 - Revised Technical Paper 8: Biodiversity Development Assessment Report (WSP, February 2024); Albury to Illabo Kemp Street Bridge Enhancement Site Modification (Inland Rail, Jun 2025); Albury to Illabo Kemp Street Bridge Enhancement Site Modification Clarification (Inland Rail, July 2025); Albury to Illabo Kemp Street Bridge Modification Noise and Vibration Impact Assessment (August 2025). | |
| EHG | Environment and Heritage Group | |
| EIS | Environmental Impact Statement | |
| EMS | Environmental Management System | |
| Environmental Representative (ER) | The Environmental Representative(s) for the CSSI approved by the Planning Secretary | |
| EPA | Environmental Protection Authority (NSW) | |
| EP&A Act | Environmental Planning and Assessment Act 1979 (NSW) | |
| EPBC Act | Environment Protection and Biodiversity Conservation Act 1999 (Federal) | |



| TERM | DEFINITION |
|---------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| EPL | Environmental Protection License |
| ESCP | Erosion and Sediment Control Plan |
| ESR | Environmental Site Representative |
| EWMS | Environmental Work Method Statement |
| GPS | Global Positioning System |
| На | Hectare |
| IBRA | Interim Biogeographic Regionalisation for Australia |
| IRPL | Inland Rail Pty Ltd |
| ISC | The Infrastructure Sustainability Council |
| JAMBA | Japan Australia Migratory Bird Agreement |
| KFH | Key Fish Habitat |
| km | Kilometre |
| LEP | Local Environmental Plan |
| LGA | Local Government Area |
| LLS | Local Land Services |
| Local road | Any road that is not defined as a classified road under the Roads Act 1993 |
| m | Metre |
| MNES | Matters of National Environmental Significance |
| Modification Report | Modification Report that includes the following: Albury to Illabo Kemp Street Bridge Enhancement Site Modification (June 2025); Albury to Illabo Kemp Street Bridge Enhancement Site Modification Clarification (July 2025); Albury to Illabo Kemp Street Bridge Modification Noise and Vibration Impact Assessment (August 2025). |
| MR | Martinus Rail |
| MR ESM | Martinus Rail Environment, Approvals and Sustainability Manager |
| NPWS | National Parks and Wildlife Service |
| NSW | New South Wales |
| OEH | Office of Environment and Heritage |
| PCT | Plant Community Type |



| TERM | DEFINITION |
|--------------------|--------------------------------------------------------------------------------------------------------------------------|
| PDCA | Plan-Do-Check-Act |
| PIR | Preferred Infrastructure Report |
| Planning Secretary | Secretary of the NSW Department of Infrastructure, Housing and Infrastructure, or delegate |
| PMST | Protected Matters Search Tool |
| POEO Act | Protection of the Environment Operations Act 1997 |
| Primary CoA/UMM | CoA and/or UMMs that are specific to the development of this Plan |
| Project ecologist | Suitably qualified and experienced ecologist engaged by MR |
| Project, the | Albury to Illabo section of the Inland Rail project |
| RoKAMBA | Republic of Korea–Australia Migratory Bird Agreement |
| RtS | Response to Submissions |
| SAP | Sensitive Area Plans |
| SAII | Serious and Irreversible Impact |
| SEARs | Secretary's Environmental Assessment Requirements |
| SEM | Site Environmental Maps |
| SEMP | Site Establishment Management Plan |
| SIMP | Social Impact Management Plan |
| SMART | Specific, measurable, achievable, relevant and timely |
| SSI | State Significant Infrastructure |
| SuMP | Sustainability Management Plan |
| TEC | Threatened Ecological Community |
| TSC Ac | Threatened Species Conservation Act 1995 (NSW), repealed in 2017 |
| TfNSW | Transport for New South Wales (formerly Roads and Maritime Services) |
| UDLP | Urban Design and Landscape Plan |
| UMM | Updated Mitigation Measures, as amended in Albury to Illabo Kemp Street Bridge Enhancement Site Modification (June 2025) |
| WoNS | Weeds of National Significance |



1 INTRODUCTION

1.1 Project overview

Inland Rail is an approximate 1,600 kilometres (km) freight rail network that will connect Melbourne and Brisbane via regional Victoria, New South Wales (NSW) and Queensland. The Inland Rail route would involve using approximately 1,000 km of existing track (with enhancements and upgrades where necessary) and 600 km of new track, passing through 30 local government areas (LGAs). Inland Rail will accommodate double-stacked freight trains up to 1,800 metres (m) long and 6.5 m high.

The Australian Government has confirmed that Inland Rail is an important project to meet Australia's growing freight task, improve road safety and help decarbonise the economy. Inland Rail will enhance our national freight and supply chain capabilities, connecting existing freight routes through rail, roads and ports, and supporting Australia's growth. Inland Rail is being delivered by Australian Rail Track Corporation (ARTC) and Inland Rail Pty Ltd (IRPL).

Comprising 12 sections, a staged approach is being undertaken to deliver Inland Rail. Each of these projects can be delivered and operated independently with tie-in points to the existing railway. Work south of Parkes has been prioritised, which will enable Inland Rail to initially connect to existing rail networks between Melbourne, Sydney, Perth and Adelaide via Parkes and Narromine. The Parkes to Narromine and Narrabri to North Star Phase 1 sections are complete.

The Inland Rail program will enable enhancement works to structures and sections of track along 185 km of the existing operational standard-gauge railway in the Albury to Illabo (A2I) section (the project). Enhancement works are required to provide the increased vertical and horizontal clearances required for double-stacked freight trains. Works would include track realignment, lowering and/or modification within the existing rail corridor, modification, removal or replacement of bridge structures (rail, road and/or pedestrian bridges), raising or replacing signal gantries, level-crossing modifications and other associated works.

A detailed Project description is provided in Section 4 of the Construction Environmental Management Plan (CEMP).

1.2 Planning context

The Inland Rail – Albury to Illabo Project (the Project) is declared State significant infrastructure (SSI) and critical State significant infrastructure (CSSI) under Division 5.2 of the *Environmental Planning and Assessment Act 1979* (NSW) (EP&A Act). The Project is permissible without development consent and is subject to assessment and approval by the NSW Minister for Planning and Public Spaces.

An environmental impact statement (EIS) was prepared to support ARTC's application for approval of the Project in accordance with the requirements of the EP&A Act and the environmental assessment requirements of the Secretary of the (then) NSW Department of Planning, Industry and Environment (the SEARs) (now the Department of Planning, Housing and Infrastructure (DPHI)).

The EIS was placed on public exhibition from 17 August 2022 to 28 September 2022. During the exhibition period, interested stakeholders and members of the community were able to review the EIS online, participate in consultation and engagement activities held by ARTC, and make a written submission to the DPE for consideration in its assessment of the Project.

In accordance with section 5.17 (6) (b) of the EP&A Act, on 13 April 2023 the Planning Secretary directed ARTC to submit a Preferred Infrastructure Report (PIR) that provides a further assessment of traffic and transport, noise and vibration, and air quality impacts. The PIR was also prepared to consider changes to the exhibited Project that have arisen as a consequence of these further assessments and related submissions.

As a result of the potential for impacts on protected matters, the project was referred to the then Australian Government Minister for the Environment on 2 June 2020 (EPBC Referral No 2020/8670). On 29 June 2020, the Australian Government Department of Agriculture, Water and Environment (DAWE) notified that the proposal is a not controlled action, and hence approval under the EPBC Act is not required. In July 2022, the department changed its name to become the Department of Climate Change, Energy, the Environment and Water (DCCEEW).

A modification report (Kemp Street Bridge Enhancement Site Modification, Inland Rail June 2025) was prepared to revise the replacement road and pedestrian bridge arrangement over the railway line at the Kemp Street bridge enhancement site in Junee to now provide a combined single structure. The Modification was approved by the delegate of the NSW Minister for Planning and Public Spaces on 13 August 2025.

1.3 Statutory context and approval

The Inland Rail – Albury to Illabo project (the project) was assessed as part of the following documents:

CONSTRUCTION BIODIVERSITY MANAGEMENT PLAN - STAGE C



- Inland Rail Albury to Illabo Environmental Impact Statement (ARTC, August 2022);
- Albury to Illabo Response to Submissions (ARTC, November 2023);
- Albury to Illabo Preferred Infrastructure Report (ARTC, November 2023);
- Albury to Illabo Preferred Infrastructure Report Response to Submissions (ARTC, February 2024);
- Inland Rail Albury to Illabo (SSI-10055) Response to request for additional information Air Quality Assessment (letter dated 1 May 2024);
- Part 1 Revised Technical Paper 8: Biodiversity Development Assessment Report (WSP, February 2024);
- Part 2 Revised Technical Paper 8: Biodiversity Development Assessment Report (WSP, February 2024);
- Albury to Illabo Kemp Street Bridge Enhancement Site Modification (Inland Rail, June 2025);
- Albury to Illabo Kemp Street Bridge Enhancement Site Modification Clarification (Inland Rail, July 2025);
- Albury to Illabo Kemp Street Bridge Modification Noise and Vibration Impact Assessment (August 2025).

Together these documents are referred to as the Environmental Assessment Documentation (EAD). Part 1 and Part 2 of the Revised Technical Paper 8: Biodiversity Development Assessment Report (WSP, February 2024) are collectively referred to as the Revised Biodiversity Development Assessment Report (Revised BDAR).

The original approval for the project under the EP&A Act was granted by the Minister for Planning on 8 October 2024. The Modification was approved by the delegate of the NSW Minister for Planning and Public Spaces on 13 August 2025.

1.4 Scope of this Stage C Plan

The scope of this Construction Biodiversity Management Plan (this Plan or this CBMP) is to describe how potential biodiversity impacts will be managed during Stage C construction of the project.

This Plan addresses the requirements of the EAD that related to construction activities including incorporating the relevant updated mitigation measures (UMMs), and Conditions of Approval (CoAs). SMART (Specific, Measurable, Achievable, Realistic and Timely) principles, as required by CoA C7(d), have been considered and applied during the preparation of this Plan which will be implemented for the duration of construction.

All Martinus Rail staff and sub-contractors are required to comply with and operate fully under the requirements of this Plan and related environmental management plans, over the full duration of the construction program.

1.4.1 Staging

The Staging Report describes how the construction and operation of the project will be staged in accordance with CoA A9, A10 and A11. A staged approach has been primarily adopted for the project to prioritise critical activities that are reliant upon infrequent and fixed rail possessions. It overall de-risks the construction program for the project, ensuring that the project is operational within the timeframe committed to by the NSW Government.

As required by CoA A14 and C16, a Construction Environmental Management Framework (CEMF) has been prepared to be consistent with the Staging Report. The CEMF has been prepared to facilitate the preparation and approval of CEMPs, Sub-plans, and construction monitoring plans (CMPs) during the construction phase of the project. It includes a guide to the general environmental, stakeholder and community management requirements which will be implemented during construction and provides a road map for environmental management documentation.

In accordance with CoA C16, the CEMF must be endorsed by the Environmental Representative (ER) and then submitted to the Planning Secretary (for approval) no later than one (1) month before the lodgement of any CEMP, CEMP Sub-plan, or Construction Monitoring Program (CMP).

This Plan has been prepared to be consistent with the Staging Report and the CEMF, as required by CoA A11 and A12, as well as C16. This Plan has therefore been prepared to address how Martinus Rail will manage potential biodiversity impacts during construction of Stage C of the Project.

Stage C, as described in Section 2.1.4 of the Staging Report will include traffic mitigation measures identified in the Wagga Wagga Construction Traffic, Transport and Access Mitigation Report and demolition of the existing Edmondson Street bridge and construction of the new Edmondson Street bridge. Construction in Stage C will also comprise a continuation of activities started in Stage A and/or Stage B and therefore works will be occurring at all enhancement sites during Stage C:

- Murray River bridge;
- Albury Station pedestrian bridge;
- Albury Yard clearances;
- Riverina Highway bridge;



- Billy Hughes bridge;
- Table Top Yard clearances
- Culcairn pedestrian bridge;
- Culcairn Yard clearances;
- Henty Yard clearances;
- Yerong Creek Yard clearances;
- The Rock Yard clearances:
- Uranguinty Yard clearances;
- Pearson Street bridge;
- Cassidy Parade pedestrian bridge;
- Edmondson Street bridge;
- Wagga Wagga Station pedestrian bridge;
- Wagga Wagga Yard clearances;
- Bomen Yard clearances;
- Harefield Yard clearances
- Kemp Street bridge;
- Junee pedestrian bridge;
- Junee Yard clearances;
- Olympic Highway underbridge;
- Junee to Illabo clearances.

This plan applies to the entirety of Stage C.

Staging is described further in Section 2 of the CEMP and in the CEMF and Staging Report. Stage C construction activities include:

- Pre-construction activities that have not commenced before the approval of the CEMP;
- Utility works and drainage works;
- Site establishment and operation;
- Traffic management and access, including material haulage;
- Clearing, grubbing and topsoil strip;
- Earthworks including preparation of pads and stockpiling;
- Track work including realignment and lowering;
- Rail bridge works;
- Road and pedestrian bridge works, including demolition;
- Pedestrian bridge works;
- Level crossing works;
- Gantry and signalling works;
- Finishing works.

1.4.2 Preparation of this Plan

This CBMP and relevant appendices were prepared in collaboration with and reviewed by Alex Graham, Principal Ecologist at East Coast Ecology, a suitably qualified professional.

1.5 Interactions with other management plans and strategies

This Plan has the following interrelationships with other management plans and documents:

- Albury to Parkes (A2I) Construction Environmental Management Framework (CEMF) (A2P CEMF) (0-0000-900-EEC-00-SP-0002 2);
- Sensitive Area Plans (SAPs) detailed in Appendix A8 of the CEMP which highlight sensitive environmental areas
 to be managed during construction, including mapped native vegetation adjacent to the project alignment and
 highlight 'exclusion zones' where vegetation is to be retained on site;



- The Construction Waste, Contamination and Hazardous Materials Management Plan (CWCHMMP) provides a framework for waste management including the disposal of weeds;
- Community Communication Strategy (CCS) which details procedures and processes for community notification, consultation and complaints management;
- The Sustainability Management Plan (SuMP) which outlines the required sustainability goals and deliverables of the project, and how the Contractor intends to achieve these outputs during design, delivery and operation of the project under the Infrastructure Sustainability Council (ISC) rating system.

A Biodiversity Assessment Method (BAM) Biodiversity Credit Report has been prepared and will be implemented by IRPL in accordance with CoA E21. E23 and E24.

Where a reference to another document is made, this is assumed to be the most recent version, unless otherwise stated.

1.6 Consultation

1.6.1 Consultation for this Plan

As described in Section 1.4.1, the CEMP is being developed in a two-step process.

The project's CEMP and Sub-plans are subject to the consultation requirements as identified in CoA C6. In accordance with CoA C6, this CBMP has been prepared in consultation with Department of Primary Industries – Fisheries (DPI Fisheries), Department of Climate Change, Energy, the Environment and Water (DCCEEW) – Conservation Programs, Heritage and Regulation (CPHR) (former Biodiversity, Conservation and Science Directorate (BCS)) and relevant councils:

- Albury City Council;
- Great Hume Shire Council:
- Lockhart Shire Council;
- Wagga Wagga City Council;
- Junee Shire Council.

Consultation with stakeholders was undertaken during the development of the Stage A Plan. Feedback was provided during the Stage A consultation period from BCS (now CPHR) and Junee Shire Council. The feedback provided was primarily around pre-clearing and the vegetation clearing process, weeds and pests, the unexpected finds protocol, the Sloane's Froglet survey, habitat fragmentation, fish passage and water pollution. The feedback was reviewed, the plan was updated and responses were issued to the stakeholders to close out the consultation process.

Consultation was also undertaken during the development of the Stage B CBMP. The CBMP was provided to stakeholders and councils on 20/03/2025 and 21/03/2025 and closed on 09/04/2025. Reminders were provided through emails and regular meetings with councils. Consultation received to date has been summarised in Table 1. Any further feedback from stakeholders will be accepted and incorporated into subsequent revisions of the plan.

No further consultation was undertaken during the development of the Stage C CBMP as the demolition of the Edmondson Street bridge was originally included in the scope of the Stage B CBMP when the plan was provided to stakeholders.

The consultation report prepared for the Stage B CBMP in accordance with CoA C6 will outline what feedback was provided (if any), and where stakeholders' responses have been addressed in this Plan. Table 1 summarises consultation undertaken and outlines how stakeholders' responses have been addressed.

TABLE 1: CONSULTATION SUMMARY

| STAKEHOLDER | DATES | FEEDBACK PROVIDED | HOW ADDRESSED |
|-------------|--------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| CPHR | 09/04/2025 23/05/2025 | Document markup and letter received 09/04/2025. Follow up phone call on 23/05/2025. A summary of feedback received: Inclusion in the BMP of all mitigation measures and actions committed to in the final revised BDAR and Environmental Impact Statement (EIS). This includes those commitments that are not identified with a relevant | • All UMMs relating to Biodiversity from the PIR Response to Submissions report, which were informed by the Revised BDAR are outlined in Table 4, with a separate column detailing where they are addressed in this Plan. Additional discussion has been included with respect to Superb Parrot nest trees in Section 6.1. Stop works during the Superb Parrot breeding season is not |



| STAKEHOLDER | DATES | FEEDBACK PROVIDED | HOW ADDRESSED |
|------------------------|------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | | reference number in the updated mitigation measures. Consistency and accuracy in referencing biodiversity exclusion zones, sensitive areas plans and no go zones and providing separate map layers for each (where relevant). Ensuring all updated feedback from RD regarding mitigation and management actions for Sloane's Froglet is included in the BMP. Appending the Fauna Connectivity Strategy, when finalised, to the BMP and referencing it in Section 6.10 of the BMP. | considered appropriate due to the brownfield nature of the site, the intermittent timing of work and the works being undertaken in a live rail setting where construction programming is dictated by existing train schedule and possession periods (as discussed with CPHR on 23/05/25) in Section 6.1 and CB-11 has been updated. Text referring to a 'biodiversity exclusion zone' or 'no-go zone' has been updated to 'exclusion zone' throughout for consistency with the term featured on sensitive area plans for the Project, as shown in Appendix A8 of the CEMP. Feedback received from CPHR during the preparation of the Stage A CBMP identifying that frog fencing is not recommended as a mitigation for Sloane's Froglet is reflected in Table 20 of this Plan. The mitigation measures outlined in Table 20 have been updated in line with recommendations made by CPHR and will assist in the mitigation and management of potential impacts to Sloane's Froglet, and will implemented in conjunction with the Sloane's Froglet Management Plan required for Billy Hughes Bridge as described in Section 6.9. The requirements of the Fauna Connectivity Strategy required by CoA E31 are discussed in Section 6.10. To specifically address CoA E29, E30 and E32 for Fauna Connectivity Strategy is being developed independently of this CBMP. |
| DPI Fisheries | 16/04/2025 | DPI Fisheries confirmed they have no comments on the CBMP. | N/A |
| Albury City Council | 10/03/2025 | No specific comments have been received on the CBMP, however one comment on the Construction Flood and Bushfire Emergency Management Plan has been considered in this Plan. Highlight Part 7.5 Development on river front areas, within our LEP 2010, specifically | As CSSI, environmental planning instruments (including local environmental plans) do not apply to or in respect of the project. The Project will have regard to the following guidelines that have similar objectives to the Part 7.5 of the Albury LEP: |



| 7.5.2.b. Please address this clause and how will the works adhere to the LEP? Guidelines for controlled activities on waterfront land (Department of Primary Industries (DPI), 2012b); Guidelines for developments adjoining land and water (OEH, 2013b). | STAKEHOLDER | DATES | FEEDBACK PROVIDED | HOW ADDRESSED |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Shire Council Junee Shire Council 19/05/2025 21/05/2025 21/05/2025 21/05/2025 A summary of feedback received: Council has not received return comments on this request from Stage A. Timing of works is not clear. Stages and commencement dates should be provided for Stage B. Evidence of consultation should be returned prior to the reports being issued. Where vegetation is to be impacted investigation of whether this vegetation supports fauna habitat and/or connectivity should be undertaken, and provision should be allowed for equivalent replacement of native vegetation and habitat links within Junee Shire. Fauna Handling and Rescue Procedure does not include pre-clearing activities to protect wildlife prior to the being discovered, such as 'tree-knocking', waiting 24 hours being activities are undertaken, etc. Erosion and sediment control plans must be incorporated into this plan. Refuelling should be completed on a hard surface or bunded area. 'so far as practicable' should be removed. Design drawings for fish passages and erosion and sediment control must be | | | 7.5.2.b. Please address this clause and how | Guidelines for controlled activities on waterfront land (Department of Primary Industries (DPI), 2012b); Guidelines for developments adjoining land and water (OEH, |
| Follow up meeting held on 21/05/2025. A summary of feedback received: Council has not received return comments on this request from Stage A. Timing of works is not clear. Stages and commencement dates should be provided for Stage B. Evidence of consultation should be returned prior to the reports being issued. Where vegetation is to be impacted investigation of whether this vegetation supports fauna habitat and/or connectivity should be undertaken, and provision should be allowed for equivalent replacement of native vegetation and habitat links within Junee Shire. Fauna Handling and Rescue Procedure does not include pre-clearing activities to protect wildlife prior to the being discovered, such as 'tree-knocking', waiting 24 hours being activities are undertaken, etc. Erosion and sediment control plans must be incorporated into this plan. Refuelling should be completed on a hard surface or bunded area. 'so far as practicable' should be removed. Design drawings for fish passages and erosion and sediment control must be | | 23/04/2025 | | N/A |
| and movement corridors above | Junee Shire | | Comments received 19/05/2025. Follow up meeting held on 21/05/2025. A summary of feedback received: Council has not received return comments on this request from Stage A. Timing of works is not clear. Stages and commencement dates should be provided for Stage B. Evidence of consultation should be returned prior to the reports being issued. Where vegetation is to be impacted investigation of whether this vegetation supports fauna habitat and/or connectivity should be undertaken, and provision should be allowed for equivalent replacement of native vegetation and habitat links within Junee Shire. Fauna Handling and Rescue Procedure does not include pre-clearing activities to protect wildlife prior to the being discovered, such as 'tree-knocking', waiting 24 hours being activities are undertaken, etc. Erosion and sediment control plans must be incorporated into this plan. Refuelling should be completed on a hard surface or bunded area. 'so far as practicable' should be removed. | Council comments raised on the Stage A BMP were provided to Council on 29/11/24, with follow-up on 17/12/24. Stage B is expected to commence in the first quarter of FY2526. An indicative program will be provided to Council. Responses to Junee Shire Council comments raised on the Stage B BMP were presented to Council on 21/05/25. Impact to vegetation has been assessed in the Revised BDAR. Pre-clearing surveys will also be carried out to determine fauna presence. Offsetting of vegetation forms part of the Project obligations in the Infrastructure Approval in accordance with CoA E21. Any additional replanting would be subject to urban design planning through the Urban Design and Landscape Plan (UDLP) required in accordance with CoA E108 of the Infrastructure Approval. The Revised BDAR concludes the project is considered unlikely to result in a large increase to landscape scale fragmentation and to further limit connectivity and movement corridors above what already exists in the project site as stated in Section 5.2.4. Harefield Yard has not been identified as an area that would be impacted by habitat fragmentation in the EAD. In accordance with CoA E31, the project is required to prepare a fauna connectivity strategy as discussed in Section 6.10, though this relates specifically to the Billy Hughes Bridge and |



| STAKEHOLDER | DATES | FEEDBACK PROVIDED | HOW ADDRESSED |
|-----------------------------|------------|------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | | | of Harefield Yard is not a requirement of this CoA. Section 6.1.2 updated to include additional activities which may be undertaken to encourage fauna to escape prior to clearing. Overarching ESCP will be incorporated into the next revision of the CSWMP. Original CB-30 wording is from UMM BD-15. CB-30 wording updated as requested. Instream works will be undertaken in dry conditions, as far as practicable. Progressive ESCPs will be developed prior to works and are not included within this plan. Current design (23/05/25) at Jeralgambeth Creek (main crossing) identifies that the existing culvert is to be retained. |
| Wagga Wagga City Council | N/A | Not yet received | N/A |
| Lockhart Shire Council | 14/04/2025 | Council confirmed they have no comments on the CBMP. | N/A |

1.6.2 Ongoing consultation during construction

Ongoing consultation between Martinus Rail, IRPL, other construction projects, stakeholders, the community and relevant agencies regarding the management of biodiversity impacts on the environment will be undertaken during the construction of the project as required.

The process for consultation is described in the Community Communication Strategy (CCS).

Biodiversity management information where required will be communicated to the community and stakeholders in accordance with the principles and procedures outlined in the CCS. The project will provide timely, accurate, relevant and accessible information about construction activities that may have biodiversity impacts, with provision for feedback through a complaints line during construction.



2 PURPOSE AND OBJECTIVES

2.1 Purpose

The purpose of this Plan is to describe how potential biodiversity impacts will be managed during Stage C construction of the project.

2.2 Objectives

The key objective of this CBMP is to minimise impacts from construction of the project on terrestrial and aquatic biodiversity. To aid in achieving this objective, this CBMP incorporates the relevant biodiversity management measures from the following sources:

- The project EAD;
- Inland Rail Albury to Illabo Infrastructure Approval CoA (SSI-10055);
- All relevant legislation and other requirements described in Section 3 of this Plan.

As discussed further in Section 3.5, sustainability is integral to the project. The Sustainability Management Plan (SuMP) (5-0052-210-PMA-00-PL-0001) includes environment and biodiversity theme targets. In relation to biodiversity, the relevant target is that ecological values across the Project will be improved by 5%.

In addition to the above, a Social Impact Management Plan (SIMP) has been developed for the project. The SIMP identifies desired outcomes for the project, including 'the project adequately manages and enhances aesthetic values in the social locality'. This CBMP will support the desired outcomes identified in the SIMP through the targets in Section 2.3 and the implementation of the CBMP supports this outcome through the implementation of management measures described in Section 6.11 including seed collection, and establishing the framework for rehabilitation in later phases of the project.

2.3 Targets

Targets for the management of biodiversity impacts during the project include:

- Full compliance with the relevant legislative requirements (CoAs);
- Adherence to clearing allowances as per CoA C20;
- Be generally in accordance with the UMMs;
- Ensure controls and procedures are implemented during construction activities to avoid, minimise or manage potential adverse impacts to biodiversity within and adjacent to the project corridor;
- No increase in the distribution of weeds currently existing within the project areas;
- No new weeds introduced to the project areas or transferred from project areas;
- No transfer of plant diseases or pathogens to or from the project work areas;
- All fauna species encountered during construction are handled humanely in accordance with industry standards;
- No pollution or siltation of aquatic ecosystems, wetlands, endangered ecological communities or threatened species habitat;
- Ecological values will be enhanced by a minimum of 5% (sustainability target for construction biodiversity).

2.4 Performance outcomes

Performance outcomes identified in Section 27.4 of the EIS that are relevant to the management of biodiversity during construction of the project are identified in Table 2.

TABLE 2: PERFORMANCE OBJECTIVES (CONSTRUCTION BIODIVERSITY)

| PERFORMANCE OUTCOMES | HOW PERFORMANCE OUTCOME WILL BE ACHIEVED |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------|
| Avoids and minimises, as far as practicable, impacts to terrestrial and aquatic biodiversity, including clearing of native vegetation | Implement this CBMP, particularly the management measures in Section 6, which have been developed to consider the |
| Offsets biodiversity impacts in accordance with the <i>Biodiversity Conservation Act 2016</i> (NSW) (BC Act) and the offset strategy for the Inland Rail program. | requirements in Section 3. |



| PERFORMANCE OUTCOMES | HOW PERFORMANCE OUTCOME WILL BE ACHIEVED |
|-------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------|
| Does not contribute to key threatening processes associated with weeds and pathogens. | Undertake training, monitoring and inspections as summarised in Section 7.3 and Section 7.4, respectively. |
| Incorporates best-practice principles into the design of waterway crossings. | Retirement of biodiversity credits required under the relevant Conditions of Approval. |
| Minimises, as far as practicable, significant impacts to flow regimes in receiving waterways. | |
| Integrates mitigation measures in design, where practicable, to maintain or enhance ecological connectivity | |
| Manages impacts on biodiversity in accordance with relevant legislation. | |

2.5 SMART principles

This Plan has been developed with the consideration of SMART principles. This was achieved as follows:

- **Specific**: The measures listed in Section 6.11 of this Plan are specific to flora and fauna management during construction. They include the development and implementation of plans and procedures tailored to address flora and fauna impacts, identification, and management of specific issues like unexpected finds of threatened species and threatened ecological communities and weed and pathogen control;
- **Measurable**: The document provides specific measures, requirements, and references that enable the evaluation and measurement of the effectiveness of each control measure. Monitoring program and reporting requirements are outlined, allowing for the assessment of impacts to flora and fauna;
- Achievable: The control measures outlined in the document are practical and achievable within the construction context. They involve the implementation of plans, investigations, and management strategies that can be feasibly executed during the construction phase;
- **Relevant**: The measures are directly relevant to flora and fauna management during construction. They address potential impacts, such as those associated with vegetation clearing, fauna encounters and impacts to aquatic habitats. These measures are designed to mitigate or prevent these impacts on flora and fauna;
- Time-bound: The document specifies when each measure should be implemented, such as prior to and during
 construction. It also assigns responsibilities to specific roles, indicating the timeline and accountability associated
 with each measure.



3 ENVIRONMENTAL REQUIREMENTS

3.1 Legislation

Legislation and regulations relevant to biodiversity management include:

- Environmental Planning and Assessment Act 1979 (EP&A Act);
- Protection of the Environment Operations Act 1997 (POEO Act);
- National Parks and Wildlife Act 1974;
- BC Act 2016:
- Biosecurity Act 2015;
- Local Land Services Act 2013;
- Pesticides Act 1999; and
- Fisheries Management Act 1994.

A register of legal requirements for the project is contained in Appendix A1 of the CEMP.

3.2 Guidelines and standards

The main guidelines, specifications, and policy documents relevant to this Plan include:

- Environmental Management Plan Guideline Guideline for Infrastructure Projects (DPIE, April 2020);
- Department of Primary Industries 'Policy and Guidelines for Fish Habitat Conservation and Management (DPI, 2013);
- Hygiene protocol for the control of disease in frogs (DECCW, 2008);
- Australian Standard AS 4373 Pruning of Amenity Trees;
- Biodiversity Assessment Method (Department of Planning, Industry and Environment (DPIE), 2020a) (the Biodiversity Assessment Method);
- Threatened Biodiversity Survey and Assessment: Guidelines for Developments and Activities (Department of Environment and Conservation (DEC), 2004);
- NSW Guide to Surveying Threatened Plants (Office of Environment and Heritage (OEH), 2016b), 'Species credit' threatened bats and their habitats (OEH, 2018);
- Australian Department of Agriculture, Water and the Environment's survey guidelines for threatened species under the EPBC Act;
- Risk assessment guidelines for groundwater-dependent ecosystems (Serov, et al., 2012);
- Matters of National Environmental Significance—significant impact guidelines 1.1 (Department of the Environment, 2013);
- Draft Referral guideline for 14 birds listed as migratory species under the EPBC Act (Department of the Environment, 2015b);
- EPBC Act Condition-setting Policy (Department of Agriculture, Water and Environment (DAWE), 2020);
- Policy and guidelines for fish habitat conservation and management (Department of Primary Industries (DPI), 2013c);
- Why do fish need to cross the road? Fish passage requirements for waterway crossings (Fairfull and Witheridge, 2003):
- Aguatic ecology in Environmental Impact Assessment EIA Guideline (Department of Planning, 2003);
- Guideline for controlled activities on waterfront land (DPI, 2012b);
- NSW Sustainable Design Guidelines (Transport for NSW (TfNSW), 2017b);
- Freshwater threatened species distribution maps (DPI, 2016–2021);
- Sloane's Froglet Stormwater Wetland Design Guidelines (OEH, 2017);
- Inland Rail Sustainability Strategy (0-0000-900-ESS-00-RP-0003); and
- Inland Rail Sustainability Requirements Albury to Parkes, sustainability requirements specified in 3-0000-210-ESS-00-SP-0001.



3.3 Minister's Conditions of Approval

The requirements of the CoA relevant to the development of this CBMP are shown in Table 3. These are defined as primary CoA and are specifically related to the development of this Plan.

A cross-reference is also included to indicate where the CoA is addressed in this Plan or other project management document.

TABLE 3: COA RELEVANT TO THIS PLAN

| NO. | REQUIREMENT | | | WHERE ADDRESSED |
|-----|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|------------------------------------------------------------------------------|---------------------------------------------------|
| C5 | CEMP(s) (and relevant CEMP sub-plans) not requiring the Planning Secretary's approval, but requiring ER endorsement, must be submitted to the ER no later than one (1) month before the commencement of construction or where construction is staged no later than one (1) month before the commencement of that stage. The CEMPs (and relevant CEMP sub-plans) must be endorsed by the ER as being consistent with the conditions of this approval and all undertakings made in the documents listed in Condition A1. | | | This CBMP |
| C6 | Except as provided by Condition C16 the following CEMP Sub-plans must be prepared in consultation with the relevant government agencies identified for each CEMP Sub-plan. Details of all information requested by an agency during consultation must be provided to the Planning Secretary as part of any submission of the relevant CEMP Sub-plan, including copies of all correspondence from those agencies as required by Condition A8. | | | This CBMP Section 1.6 |
| | | Required CEMP Sub- plan | Relevant government agencies to be consulted for each CEMP Sub-plan | |
| | (d) | Biodiversity | DPI Fisheries, BCS**, and relevant councils | |
| C7 | The CEMP Sub-plans mus | st state how: | | - |
| | (a) the environmental per Condition A1 will be a | Section 2.4 Section 1.3 | | |
| | (b) the mitigation measure implemented; | Section 6 | | |
| | (c) the relevant terms of this approval will be complied with; and (d) issues requiring management during construction (including cumulative impacts), as identified through ongoing environmental risk analysis, will be managed through SMART principles. | | | Section 2 Section 6 Section 7 Appendix A |
| | | | | |
| C10 | The Biodiversity Management Sub-plan must include, but not limited to details of the: | | | - |
| | (a) measures to avoid an aquatic threatened spe | | and impacts to terrestrial and | Section 6.11 |



| NO. | REQUIREMENT | | | WHERE ADDRESSED |
|-----|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------|--------------------------------------------------------------------|
| | (b) Measures to protect riparian corridors and erosion and sediment control measures to be implemented identified in accordance with Condition E173 and E174 and | | | |
| | (c) Riparian and watercon accordance with Condit | | res to be implemented in | Section 6.7 Section 5.2.3 |
| C15 | Construction must not common have been approved by the applicable and as identified CEMP and CEMP Sub-plansing minor amendments approve construction. Where the CSC commence until the relevant and approved by the Planning | rsed by the ER, (as er Condition C16). The ing Secretary, including any mented for the duration of tion of that stage is not to | Section 1.4 | |
| C26 | Except as provided by Cond Programs must be prepared identified for each to compa against the performance pre CEMP: | in consultation with the rele re actual performance of co | evant government agencies nstruction of the CSSI | Section 7.3 |
| | | Required Construction Monitoring Programs | Relevant government agencies to be consulted for each Construction Monitoring Program | |
| C27 | c) Each Construction Monitorin | Biodiversity | BCS** (NSW DCCEEW) | _ |
| 021 | principles and provide: | _ | | |
| | (a) details of baseline data a | Section 4 Appendix G: Construction Biodiversity Monitoring Plan | | |
| | (b) details of baseline data to be obtained and when; | | | Section 7.3 Appendix G: Construction Biodiversity Monitoring Plan |
| | (c) details of all monitoring of the project to be undertaken; | | | Section 7.3 Appendix G: Construction Biodiversity Monitoring Plan |
| | (d) the parameters of the pro | oject to be monitored; | | Section 7.3 Appendix G: Construction |



| NO. | REQUIREMENT | WHERE ADDRESSED |
|-----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------|
| | | Biodiversity Monitoring Plan |
| | (e) the frequency of monitoring to be undertaken; | Section 7.3 Appendix G: Construction Biodiversity Monitoring Plan |
| | (f) the location and justification of monitoring locations. | Section 7.3 Appendix G: Construction Biodiversity Monitoring Plan |
| | (g) the reporting of monitoring results and analysis results against relevant criteria | Section 7.3 Appendix G: Construction Biodiversity Monitoring Plan |
| | (h) details of the methods that will be used to analyse the monitoring data; | Appendix G: Construction Biodiversity Monitoring Plan |
| | (i) procedures to identify and implement additional mitigation measures where the results of the monitoring indicate unacceptable project impacts; and | Section 8.1 Appendix G: Construction Biodiversity Monitoring Plan |
| | (j) any consultation to be undertaken in relation to the monitoring programs. | Section 1.6 Appendix G: Construction Biodiversity Monitoring Plan |
| C34 | The results of the CMP(s) must be submitted to the Planning Secretary, and relevant regulatory agencies, for information in the form of a Construction Monitoring Report at the frequency identified in the relevant CMP. | Section 7.6 Appendix G: Construction Biodiversity Monitoring Plan |
| E19 | The clearing of native vegetation must be minimised to the greatest extent practicable with the objective of reducing impacts to threatened ecological communities, threatened species and their habitat. | Section 6.1 Section 6.11 |
| E20 | Impacts to plant community types and threatened species habitat must not exceed the impacts specified in Table 6 and Table 7 below: Table 6 Plant community type impacts and ecosystem credit requirements | Section 6.1 Section 6.1.6 Section 6.8 |
| | Name of Plant Community Type/ID Area of Ecosystem credits impact to be retired | |



| NO. | REQUIREMENT | | | | WHERE ADDRESSED |
|-----|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------|-------------------------------|--------------------|
| | 277 – moderate – Blakely's Red Gum – Yellow Box grassy tall woodland of the NSW South Western Slopes Bioregion | 0.5 | | 22 | |
| | 277 – poor - Blakely's Red Gum – Yellow Box grassy tall woodland of the NSW South Western Slopes Bioregion | 1.44 | | 30 | |
| | 277 – derived - Blakely's Red Gum – Yellow Box grassy tall woodland of the NSW South Western Slopes Bioregion | 2.3 | | 78 | |
| | 277 – Native plantings - Blakely's Red Gum – Yellow Box grassy tall woodland of the NSW South Western Slopes Bioregion | 0.26 | | 7 | |
| | 277 – Non-native - Blakely's Red Gum – Yellow Box grassy tall woodland of the NSW South Western Slopes Bioregion | 30.5 | | 0 | |
| | 5 - River Red Gum herbaceous-grassy very tall open forest wetland on inner floodplains in the lower slopes sub-region of the NSW South- Western Slopes Bioregion and the eastern Riverina Bioregion | 0.04 | | 2 | |
| | Total | | | 139 | |
| | Table 7 Threatened species habitat impacts and | species cr | edit requir | rements | |
| | Fauna Species | | Area (ha) | Credits to be retired | |
| | Lower Slopes IBRA Subregion | | | | |
| | Sloane's Froglet (Crinia sloanei) | | 0.03 | 2 | |
| | Squirrel Glider (Petaurus norfolcensis) | | 0.16 | 3 | |
| | Superb Parrot (Polytelis swainsonii) | | 0.16 | 3 | |
| | Inland Slopes IBRA Subregion | | | | 1 |
| | Sloane's Froglet (Crinia sloanei) | | 0.23 | 5 | |
| | Key's Matchstick Grasshopper (Keyacris scu | ırra) | 0.21 | 4 | |
| | Squirrel Glider (Petaurus norfolcensis) | | 1.82 | 41 | |
| | Superb Parrot (Polytelis swainsonii) | | 1.82 | 41 | |
| | Total | | | 99 | |
| E21 | Prior to impacts on the biodiversity values of the ecosystem credits and species credits (like-for-lik Biodiversity Credit Report which forms part of the retired. The number of biodiversity offset species retired (prior to impacting the biodiversity values) Table 6 and Table 7. | (e) as set on BDAR Recorded to the contract of | out in the levision M, ligations t | BAM must be hat must be | Section 6.8 |
| E22 | On the discovery of potential or actual impacts to species not listed in Condition E20, all work which | | | | Section 6.1.6 |



| NO. | REQUIREMENT | WHERE ADDRESSED |
|-----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|
| | or community must stop to prevent further impact and the Planning Secretary and DCCEEW (NSW) (and DCCEEW (Cth) where relevant) notified in writing. Work must not recommence until the relevant agencies have been consulted and any required approvals have been obtained. | Section 6.5 Section 6.8 |
| E23 | The retirement of the credits must be carried out in accordance with the <i>Biodiversity Conservation Act 2016</i> , and can be achieved by: (a) acquiring and retiring "biodiversity credits" within the meaning of the BC Act; and / or (b) making a payment into the Biodiversity Conservation Fund of an amount equivalent to the class and number of ecosystem and species credits, as calculated by the Biodiversity Conservation Fund (BCF) Charge System; and/or (c) funding a biodiversity conservation action that benefits the entity impacted and is listed in the ancillary rules of the Biodiversity Offset Scheme. (d) Where evidence of compliance with the Ancillary rules: Reasonable steps to seek like-for-like biodiversity credits for the purpose of applying the variation rules has been provided to, and approved by the Planning Secretary, the variation rules may be applied to retire the relevant ecosystem credits and species credits as set out in the BAM Biodiversity Credit Report (Variation). The variation rule does not apply to biodiversity credits for threatened species or threatened ecological communities that are listed as critically endangered under the <i>Biodiversity Conservation Act 2016</i> or listed in any capacity under the <i>Environment Protection and Biodiversity Conservation Act 1999</i> . **Note: "Impacted site" in the application of the like-for-like offset rules is taken to be the subject land described in the Biodiversity Development Assessment Report referred to in Condition A1. The subject land is the disturbance footprint subject to assessment under the Biodiversity Assessment Method. | Section 6.8 |
| E24 | Evidence of the retirement of credits in satisfaction of Condition E23 must be provided to the Planning Secretary prior to impacts to the biodiversity values | Section 6.8 |
| E25 | Prior to the commencement of works, the Proponent must complete targeted surveys during July and/ or August for Sloane's Froglet (<i>Crinia sloanei</i>) in all areas where that species was assumed present in the documents listed in Condition A1. The results of the targeted surveys are to be provided to DCCEEW and the Planning Secretary for information. | Section 6.9 |
| E26 | In all locations where the Sloane's Froglet is recorded, a site-specific Sloane's Froglet Management Plan(s) must be prepared and implemented in consultation with DCCEEW and landowners to manage work within and adjacent to Sloane's Froglet habitat. The Sloane's Froglet Management Plan must include: (a) details of proposed detention basins to manage stormwater consistent with the Sloane's Froglet Stormwater Wetland Design Guidelines (Spire, 2017); (b) measures to prevent Sloane's Froglet habitat from being impacted by sediment; and (c) regular monitoring. | Section 6.9 |
| E27 | The Sloane's Froglet Management Plan must be submitted to and approved by the Planning Secretary. No work that could impact the areas identified with Sloane's Froglet (<i>Crinia sloanei</i>) are to be carried out prior to: (a) the completion of the targeted surveys required in Condition E29; and | Section 6.9 |



| NO. | REQUIREMENT | WHERE ADDRESSED |
|-----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------|
| | (b) the implementation of the approved Sloane's Froglet Management Plan required by Condition E26. | |
| E28 | In all remaining areas that assumed the presence of Sloane's Froglet (<i>Crinia sloanei</i>), erosion and sediment control measures and protection of riparian areas must be installed in accordance with Conditions C10, E173 and E174 prior to work in these areas. | Section 5.2.2 Section 6.3 Section 6.9 Section 6.11 |
| E29 | Prior to construction, at Billy Hughes Bridge and Uranquinty Creek*, existing fauna movement corridors, pathways and connectivity for the Squirrel Glider at Billy Hughes Bridge and Uranquinty Creek* must be determined by a suitably qualified and experienced expert in consultation with DCCEEW including evidence of existing fauna movement corridors, pathways and connectivity including analysis of existing studies or baseline monitoring. | Section 6.10 |
| E30 | The design of fauna connectivity measures must have regard to: (a) existing fauna movement corridors, pathways and connectivity identified in accordance with Condition E29; (b) the Sloane's Froglet Stormwater Wetland Design Guidelines (Spire, 2017), relevant threatened species guidelines, species biology and the results of on-ground surveys; (c) Fauna Sensitive Road Design Manual Volume 2 (Queensland Government, 2010); (d) Fauna Sensitive Road Design Guidelines (VicRoads, 2012); and (e) industry best practice measures. | Section 6.10 |
| E31 | The Proponent must prepare and implement a Fauna Connectivity Strategy for the Squirrel Glider and Sloane's Froglet for Billy Hughes Bridge and Uranquinty Creek* prior to the commencement of Work that has the potential to impact on the Squirrel Glider and Sloane's Froglet. The strategy must: (a) include details of existing fauna movement corridors, pathways and connectivity informed by Condition E29; (b) be consistent with the Sloane's Froglet Stormwater Wetland Design Guidelines (Spire, 2017); (c) justify the design, location and spacing of fauna connectivity structures and measures; (d) demonstrate the effectiveness of connectivity structures and measures for the targeted species to maintain or improve connectivity and movement pathways of species within regional, local and riparian corridors; and (e) a map showing the location and design of all fauna connectivity measures to be implemented (f) the maintenance activities for all connectivity structures and measures for the life of the impact of the CSSI, including timing and frequency of maintenance actions, including after flood and bushfire events; (g) include the Operational Fauna Connectivity Monitoring and Adaptive Mitigation Program required by Condition D12. | Section 6.10 |
| E32 | The Fauna Connectivity Strategy must be prepared by a suitably qualified and experienced person(s) who has expertise in the relevant targeted species, in consultation with, BCS**, DPI Fisheries and approved by the Planning Secretary. | Section 6.10 Fauna Connectivity Strategy |



| NO. | REQUIREMENT | WHERE ADDRESSED |
|-----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------|
| E33 | There are to be no works to the substructure of the Murray River Bridge or instream works in the Murray River or Oddies Creek. | Section 6.3 Section 6.11 |
| E34 | Riparian land and watercourses disturbed during construction must be rehabilitated and revegetated with native species of local provenance from the relevant native vegetation community on completion of Work impacting the riparian land in accordance with the Controlled activities – Guidelines for riparian corridors on waterfront land (DPE 2022) and A Rehabilitation Manual of Australian Streams (Rutherfurd et al. 2000). | Section 6.3 Section 6.7 |
| E35 | An exclusion zone must be established to protect riparian vegetation adjoining Billy Hughes Bridge (the eastern compound and track lowering works) and Murray River Bridge adjacent to the surface road works before construction commences in this area. The exclusion zone must be maintained until construction is completed in the area. | Section 6.3 Section 6.11 |
| E36 | Seed from native plants to be removed must be collected before clearing and used in revegetation and rehabilitation across the Project area. Plant propagation must ensure that native species of local provenance from the relevant native vegetation community are available for successful revegetation and landscaping. | Section 6.1.1 Section 6.7 Section 6.11 |
| E37 | Cleared native vegetation and other landscape features must be reused as part of the CSSI. If reuse is not practicable, consultation with the relevant council(s), land-care groups and relevant government agencies must be undertaken to determine if: (a) hollows, tree trunks, mulch, bush rock and root balls; and (b) collected plant material, seeds and/or propagated plants, can be used by others in habitat enhancement, beneficial re-use and rehabilitation work, before pursuing other disposal options. | Section 6.2 Section 6.11 |

^{*}Uranquinty Creek refers to Sandy Creek which flows along the western extent of the Uranquinty township and intersects the Uranquinty Yard enhancement site.

3.4 Updated Mitigation Measures

Relevant Updated Mitigation Measures (UMMs), as amended in Albury to Illabo Kemp Street Bridge Enhancement Site Modification (June 2025), are listed in Table 4 below. A cross-reference is also included to indicate where and how the conditions are addressed in this CBMP or other project management documents.

TABLE 4: UMMS RELEVANT TO THIS PLAN

| REF. | ISSUE/IMPACT | MITIGATION MEASURE | WHERE ADDRESSED |
|------|--------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------|
| BD1 | Avoiding impacts on biodiversity | Detailed design and construction planning will seek to identify refinements that further avoid or minimise the need to further impact or disturb native vegetation, fauna habitat and riparian habitat. | This Plan Section 6.11 |
| BD2 | Connectivity and fauna passage | During detailed design, provision of one glider pole on each side of the rail corridor will be further investigated to enhance habitat connection between patches of remnant vegetation for squirrel glider at the Billy Hughes bridge enhancement site. | Table 20: Fauna Connectivity Strategy. |

^{**} BCS has changed names and is now CPHR.



| REF. | ISSUE/IMPACT | MITIGATION MEASURE | WHERE ADDRESSED |
|------|---------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------|
| BD3 | Connectivity and fauna passage | A Project connectivity strategy will be prepared and implemented with reference to the Fauna Design Guidelines for the Inland Rail Project (2022) to consider further enhancements, including beyond the proposal site. | Fauna Connectivity Strategy. |
| BD4 | Fish passage | Fish passage will be maintained at Jeralgambeth Creek (Junee to Illabo clearances) during construction. | Section 6.3.1 Section 6.11 |
| BD5 | Avoidance of fauna impacts | Pre-clearance surveys will be carried out prior to construction by a suitability qualified ecologist in accordance with the biodiversity management sub-plan. This would include: inspections of structures that provide potential microbat habitat. If bats are identified roosting in these structures, individuals will be excluded from this habitat (meaning bats can exit the habitat unharmed during their nocturnal activity period but not re-enter) native aquatic fauna salvage in watercourses of residual pools directly impacted by construction, including but not limited to Sloane's Froglet mapped habitat areas. All salvaged aquatic fauna will be relocated to similar habitat nearby. | Section 6.1 Section 6.11 |
| BD6 | Managing the potential for biodiversity impacts during construction | Exclusion areas will be established and maintained around native vegetation and riparian vegetation identified for retention and protection, particularly areas of biodiversity value adjoining the proposal site that are located in close proximity to work areas and identified on the Sensitive Areas Map (refer to Appendix E-4) for consideration. Additional exclusion areas within the proposal site will be identified through mitigation measure BD1. | Section 6.1 Section 6.11 |
| BD7 | Managing the potential for biodiversity impacts during construction | Construction workforce will be supplied with sensitive area maps (showing clearing boundaries and exclusion zones), including updates as required (refer Appendix E-4 for guidance on sensitive areas to be considered when outside of the construction area). | Section 6.11 Appendix C – Sensitive Area Mapping- Biodiversity |
| BD8 | Riparian vegetation and aquatic habitats | Activities within vegetated riparian zones will be managed to minimise impacts to aquatic environments as far as practicable. Riparian areas subject to disturbance will be progressively stabilised and rehabilitated. | Section 6.3 Section 6.7 Section 6.11 |
| BD9 | Sloane's froglet | Temporary frog exclusion fencing will be considered where construction compounds/laydown areas occur adjacent to mapped potential Sloane's froglet breeding habitat. | Section 6.11 |
| BD10 | Managing the potential for biodiversity impacts during construction | Prior to construction commencing, pre-clearance seasonal surveys will be undertaken for Sloane's Froglet at locations where prescribed impacts are shown in Appendix C5 of Appendix G: Revised Technical Paper 8: Biodiversity Development Assessment Report. Should the pre-clearance seasonal surveys identify the Sloane's Froglet is present, the following measures will be undertaken as necessary: Implementation of suitable erosion and sediment controls (with reference to Appendix E of the Sloane's Froglet stormwater wetland design guidelines (Albury City Council and NSW Office of Environment and Heritage, 2017)) | Section 4.1.3 Section 6.9 Appendix C: Sensitive Area Mapping – Biodiversity Appendix D: Sloane's Froglet Survey |



| REF. | ISSUE/IMPACT | MITIGATION MEASURE | WHERE ADDRESSED |
|------|------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------|
| | | implementation of the exclusion zone as indicated in Map 3 of Appendix C5 of Appendix G: Revised Technical Paper 8: Biodiversity Development Assessment Report. | |
| BD11 | Managing the potential for biodiversity impacts during operation | Mitigation measures will be implemented to address impacts on habitat connectivity for squirrel gliders. This would include the addition of connectivity structures (i.e. glider poles, canopy bridges) and vegetation rehabilitation. The final locations of connectivity structures and enhancement measures will be developed as part of post approval Flora and Fauna Management Plan. Potential indicative locations for implementation of glider poles include: Sandy Creek Eight Mile Creek/Billy Hughes Bridge Oddies Creek Murray River Bridge. Canopy bridges may also be used as an alternative measure particularly where gaps in vegetation are larger such as Reedy Creek. Final locations for fauna connectivity measures will account for the height of remaining trees, gap between trees and the gliding angle of squirrel gliders to enable successful corridor movements. | Section 5.2.4 Section 6.10 |
| BD12 | Instream impacts | Instream works at Sandy Creek (Uranquinty Yard clearances) and Jeralgambeth Creek (Junee to Illabo clearances) will be undertaken in dry conditions as far as practicable. Where works cannot be conducted in the dry, appropriate erosion and sediment control would be installed (i.e. a silt curtain or sediment boom around the work area and attached to the same side of the bank to maintain fish passage). Appropriate erosion and sediment control will be installed and maintained. Aquatic habitat will be returned to pre-works condition (or better) in accordance with the rehabilitation strategy. | Section 6.1 Section 6.3 Section 6.7 Section 6.11 |
| BD13 | Instream impacts | Any instream habitat features (woody debris, large rocks and boulders) at the temporary creek crossing location at Sandy Creek (Uranquinty Yard clearances) is to be removed and placed up or downstream of the construction area in consultation with a suitably qualified aquatic ecologist. Any such aquatic features will be reinstated within the watercourse at the completion of construction. | Section 6.1 Section 6.3 Section 6.11 |
| BD14 | Unexpected finds (biodiversity) | A species UFP will be implemented if TECs, flora and fauna species, not assessed in the biodiversity assessment, are identified in the proposal site. This will include stop work orders in the immediate area and notifying DPHI. Measures to ensure construction crews can identify Regent Honeyeaters at the Billy Hughes Bridge site will be implemented and DPHI and BCS* would be notified and a stop work order implemented if necessary. Site and species specific measures will be included in the CEMP Biodiversity Sub-plan to assist construction crews to identify species atrisk of construction impacts and adopt suitable responses. The measures will include notification requirements and be consistent with stop-work and restart protocols. An example species and location is the Regent Honeyeater potentially present at the Billy Hughes Bridge site. | Section 6.1.7 Appendix A: Unexpected Threatened Species Finds Procedure Appendix H: Threatened species Identification |
| BD15 | Instream impacts | Refuelling will be conducted outside of waterfront land, so far as it practicable, with appropriate measures in place to avoid impacts to waterways, aquatic habitats and groundwater. This includes spill kits | Section 6.11 |



| REF. | ISSUE/IMPACT | MITIGATION MEASURE | WHERE ADDRESSED |
|------|----------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------|
| | | always kept with maintenance vehicles and or machinery within 100 m of a watercourse. | |
| BD16 | Fish-passage impacts | Instream structures (bridges and culverts) that provide for the flow of watercourses will be inspected and maintained to address any issues that may contribute to the blockage of fish passage. | Section 6.11 |

^{*} BCS has changed names and is now CPHR.

3.5 Infrastructure Sustainability Council requirements

Both Martinus Rail and Inland Rail are firmly committed to ensuring the projects are designed and constructed with high levels of sustainability integrated throughout the projects. Martinus Rail has developed and will implement a Sustainability Management Plan (SuMP) that is compliant with:

- Project Approvals
- Inland Rail Sustainability Strategy (0-0000-900-ESS-00-RP-0003)
- Specification Inland Rail Sustainability Requirements Albury to Parkes (3-0000-210-ESS-00-SP-0001)
- A2P Enhancement Projects Incentivised Target Cost Deed (ARTC Contract No. 2140-0001)

Martinus Rail will aim to achieve a certified minimum rating of 'Excellent' under the Infrastructure Sustainability Council (ISC) IS Technical Manual version 1.2. For further information, please refer to the SuMP.

Detailed management of biodiversity impact targets are outlined in Section 2.3. Table 5 below lists the relevant IS credits and indicates where they are addressed in this plan or references external documents that fulfill the ISC credit criteria. Further information on compliance with the ISC credits is provided in Appendix E. For Eco 2 – Habitat Connectivity, the approach to this credit is still being developed, as such all levels and benchmarks are considered in this management plan and will be updated if required.

TABLE 5: IS ECO-1 ECOLOGICAL VALUE TARGETS

| COMMITMENT | DOCUMENT REFERENCE |
|-----------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| The ecological value of the infrastructure site is maintained. | Section 3.4; Section 6.9; Section 6.11; Environmental Work Method Statements; Fauna Connectivity Strategy; Fauna Handling and Rescue Procedure; Sensitive Area Plans; Pre and post clearing reports; Unexpected Threatened Species Finds Procedure. |
| The ecological value of infrastructure site is enhanced by 0 to 20%. Fractions of Levels may be achieved on a sliding scale up to 20% for Level 3. | Section 6.7; Landscape Design Reports; Urban Design and Landscape Plan; Site-specific Rehabilitation Strategy; Inland Rail Landscape and Rehabilitation Framework; Inland Rail Landscape and Rehabilitation Strategy; Inland Rail Landscape Specification. |



TABLE 6: IS ECO-2 HABITAT CONNECTIVITY TARGETS

| LEVEL 1 | | |
|-----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Benchmark | There is a low or moderate degree of existing habitat connectivity identified. | Section 5.2.4Fauna Connectivity Strategy. |
| Benchmark | The existing degree of habitat connectivity is enhanced (offsetting allowed). | Section 6.8 Section 6.10 Biodiversity Credit Report. Fauna Connectivity Strategy. Urban Design and Landscape Plan. Detailed Design Drawings showing Flora and Fauna No Go Zones, clearance areas, and construction impact zones. |
| LEVEL 2 | | |
| Benchmark | There is a low or moderate degree of existing habitat connectivity identified. AND The existing degree of habitat connectivity is enhanced (offsetting allowed). | Section 4. Section 5.2.4 Section 6.8 Section 6.10 Biodiversity Credit Report. Detailed Design Drawings showing Flora and Fauna No Go Zones, clearance areas, construction impact zones, native vegetation and environmental aspects. Fauna Connectivity Strategy. Urban Design and Landscaping Plan |

| COMMITMENT | DOCUMENT REFERENCE |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| There is a low or moderate degree of existing habitat connectivity identified. | Section 4; Section 5.2.4; Environmental Impact Statement; Detailed Design Drawings showing native vegetation and environmental aspects. |
| The existing degree of habitat connectivity is maintained (offsetting allowed) OR The existing degree of habitat connectivity is enhanced (with no offsetting). | Section 6.8; Section 6.10; Biodiversity Credit Report; Clearing Permit; Fauna Connectivity Strategy; Urban Design and Landscape Plan; Weekly environmental inspection checklist; Detailed Design Drawings showing Flora and Fauna No Go Zones, clearance areas, and construction impact zones. |
| There is a high degree of existing habitat connectivity identified. | Section 4; Section 5.2.4; Environmental Impact Statement; Detailed Design Drawings showing native vegetation and environmental aspects. |



4 EXISTING ENVIRONMENT

4.1 Environmental aspects

This section summarises the existing biodiversity within and adjacent to the whole project. The key reference documents include Chapter 16 of the EIS and the Revised BDAR.

A screening assessment of the Kemp Street bridge modification's potential impact on biodiversity values was undertaken in the Kemp Street Bridge Enhancement Site Modification Report (Inland Rail, June 2025). This assessment considered the environmental values present in the changed project footprint and the information in the approved BDAR. The assessment concluded that preparation of a BDAR is not required as the modification would have no impact to biodiversity values.

Appendix C provides mapping indicating the location of the enhancement sites and indicative work areas as well as location of PCTs and Sloanes Froglet assumed habitat.

4.1.1 Threatened ecological communities

Native vegetation recorded within the study area is considered to meet the final determination of one threatened ecological community (TEC) listed under the BC Act:

 White Box – Yellow Box – Blakely's Red Gum Grassy Woodland and Derived Native Grassland in the NSW North Coast, New England Tableland, Nandewar, Brigalow Belt South, Sydney Basin, South Eastern Highlands, NSW South Western Slopes, South East Corner and Riverina Bioregions.

White Box – Yellow Box – Blakely's Red Gum Grassy Woodland and Derived Native Grassland is listed as Critically Endangered under the BC Act. A summary of the extent of White Box – Yellow Box – Blakely's Red Gum Grassy Woodland and Derived Native Grassland threatened ecological community within the study area is provided in Table 7.

TABLE 7: EXTENT OF WHITE BOX – YELLOW BOX – BLAKELY'S RED GUM GRASSY WOODLAND AND DERIVED NATIVE GRASSLAND THREATENED ECOLOGICAL COMMUNITY WITHIN THE STUDY AREA

| THREATENED | VEGETATION TYPE AND ZONE | BC ACT | IBRA SUBRE | EGION | STUDY AREA EXTENT (HA) | PROJECT SITE EXTENT (HA) | |
|----------------------------------------------|------------------------------|--------------------------|-----------------|------------------|---------------------------------|-----------------------------------|--|
| ECOLOGICAL COMMUNITY | | | LOWER SLOPES | INLAND SLOPES | | | |
| White Box – Yellow Box – Blakely's Red | PCT 277 – Moderate condition | | 0 | 3.22 | 3.22 | 0.50 | |
| Gum grassy woodlands | PCT 277 – Poor condition* | Critically Endangered | 1.26 | 12.54 | 13.8 | 1.43 | |
| | PCT 277 – Derived condition | | 0 | 4.08 | 4.08 | 2.34 | |
| Total extent of | 21.1 | 4.27 | | | | | |

^{*}PCT 277 in poor condition has conservatively been included as the BC Act listed White Box – Yellow Box – Blakely's Red Gum grassy woodlands TEC threshold in discussion with CPHR, as per Table 4.12 of the Revised BDAR.

4.1.2 Threatened or otherwise significant flora species

A total of nine threatened flora species were considered to have potential associated habitats within the study area and were the subject of targeted surveys. No threatened flora species were recorded during targeted surveys.

A table detailing threatened flora species specified by the Revised BDAR that are known or predicted to occur in the Revised BDAR study area, and which have a moderate, high or known likelihood of occurrence is provided in Appendix H. The table includes scientific and common names, BC Act and EPBC Act listings, a written description and an example image for each species.

4.1.3 Fauna habitat

Section 5 of the Revised BDAR assessed the habitat suitability for threatened species in accordance with Chapter 5 of the BAM and has been prepared in accordance with Part 3 of the BAM 2020 Operational Manual – Stage 1 (EES 2020a).





Likelihood of occurrence assessments were undertaken for all threatened species, populations and migratory species identified through database searches.

Ecosystem credit threatened species were assessed using information about site context, PCTs and vegetation integrity attributes collected during the field surveys, and data from the Threatened Biodiversity Data Collection (EES, 2021) as required by subsections 5.2.1 and 5.2.2 of the BAM and Part 3 of the BAM 2020 Operational Manual – Stage 1 (EES 2020a). Initial desktop assessment to determine ecosystem (predicted) and species (candidate) credit species involved entering the identified vegetation types and zones into BAM-C. This allowed predicted and candidate species reports to be generated for the associated PCTs within the study area.

Fauna habitat assessments were undertaken to assess the likelihood of threatened species of animal (candidate species identified in desktop review) occurring within the study area.

Table 8 outlines the habitat features suitable for a species credit species within the Project site (BAM s. 5.2.5). Detailed figures for threatened fauna recorded and candidate species polygons are presented in Appendix C-4, Appendix C-6 and Appendix C-7 of the Revised BDAR (PIR 2024).

TABLE 8: SPECIES WITH SUITABLE HABITAT WITHIN THE PROJECT SITE

| | | | | | IBRA SUBREGION | | |
|--------------------------|---------------------------------|------------------------------------------|-----------------|---------------------------------------------------------------------------------------------|-------------------------|--------------------------|--|
| SCIENTIFIC NAME | COMMON NAME | BC ACT ¹ SAII ² | | ASSOCIATED NATIVE VEGETATION TYPES | LOWER SLOPES (HA) | INLAND SLOPES (HA) | |
| Crinia sloanei | Sloane's Froglet | V | No ³ | PCT 5 (poor condition) and PCT 277 (poor condition and native plantings) ⁴ | 0.03 | 0.23 | |
| Keyacris scurra | Key's Matchstick Grasshopper | Е | No | PCT 5 (poor) and PCT 277 (poor, moderate, derived and native plantings) ⁴ | - | 0.21 | |
| Polytelis swainsonii | Superb Parrot | V | No | PCT 5 (poor) and PCT 277 (poor and moderate) | 0.16 | 1.82 | |
| Petaurus norfolcensis | Squirrel Glider | V | No | PCT 5 (poor) and PCT 277 (poor and moderate) | 0.16 | 1.82 | |

⁽¹⁾ Threat status under the BC Act: V = Vulnerable, E = Endangered.

It was determined that the Sloane's Froglet (*Crinia sloanei*) potential species habitat will occur in the Project site, where the mapped potential habitat (including a 15-metre buffer) occurs in association with a native vegetation community (PCT) and is not dissected by a road, rail corridor or urban development. Targeted surveys were undertaken by NGH during July and/or August 2024 for Sloane's Froglet in all areas where that species was assumed present. Sloane's Froglet (*Crinia sloanei*) was not detected aurally or visually at any site. The survey is discussed further in Section 6.9.

The Matchstick Grasshopper (*Keyacris scurra*) species is predicted to occur within the Inland Slopes IBRA subregion. Targeted surveys for this species were completed in December 2022 and the species was not recorded. In areas that have not been surveyed due to access limitations this species was conservatively assumed to be present within potential habitats at the Junee to Illabo dual track clearances area in PCT 277 Blakely's Red Gum – Yellow Box grassy tall woodland (poor and moderate).

The Superb Parrot (*Polytelis swainsonii*) and Squirrel Glider (*Petaurus norfolcensis*) potential species habitat has been mapped using a precautionary principle where all available habitats for this species have been used to map species polygons, being all PCT 5 and 277 patches with the exception of derived and native plantings.

The presence of existing fauna fencing is not discussed in the EAD. Where existing fauna fencing is identified, it will be retained where it does not impact construction of the Project.

⁽²⁾ SAII = serious and irreversible impact.

⁽³⁾ Sloane's Froglet (Crinia sloanei) is a candidate SAII species however the Revised BDAR states the Project is not at risk of having a SAII on the species

⁽⁴⁾ The assessment relies on assumed presence for Sloane's Froglet and Key's Matchstick Grasshopper



4.1.4 Threatened fauna

In accordance with the BAM threatened species have been assessed as predicted or ecosystem credit species and species credit species. Threatened fauna surveys completed within the Revised BDAR study area were carried out as described in Section 5.5.3 of the Revised BDAR.

A total of six threatened fauna species identified as predicted or ecosystem credit species and species credit species were recorded during surveys. These are presented in Table 9.

TABLE 9: THREATENED FAUNA RECORDED IN THE STUDY AREA

| SCIENTIFIC NAME | COMMON NAME | BC ACT | CREDIT TYPE | OUTCOME OF TARGETED SURVEYS |
|---------------------------|-------------------------------|------------|------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Circus assimilis | Spotted Harrier | Vulnerable | Predicted ecosystem credit species | One individual was observed in grasslands adjacent to the study area at Marinna. Likely to occur seasonally in low numbers across open landscapes associated with the study area. Study area habitats are not considered to represent important foraging habitats, but may provide trees for breeding purposes |
| Hieraaetus morphnoides | Little Eagle | Vulnerable | Dual credit species | Although potential breeding habitat was recorded during habitat assessments and one individual was recorded during the breeding season adjacent to Billy Hughes bridge, no breeding activity or nest trees were observed in the study area. Given that targeted survey did not locate breeding activity or nest trees, breeding habitat for the Little Eagle is unlikely to be affected by the Project, and as such, this species was not considered further. |
| Petaurus norfolcensis | Squirrel Glider | Vulnerable | Candidate species credit | Species was recorded during field surveys within the study area. Study area provides habitat features (i.e. hollow-bearing trees) that the species is likely to use. The study area will be utilised for both foraging and breeding purposes. |
| Polytelis swainsonii | Superb Parrot | Vulnerable | Dual credit species | Species was recorded during field surveys within the study area. Study area provides habitat features (i.e. hollow-bearing trees) that the species is likely to use. The study area will be utilised for both foraging and breeding purposes. |
| Pteropus poliocephalus | Grey- headed Flying-fox | Vulnerable | Dual credit species ¹ | Species recorded foraging on blossom resources within the study area vegetation. There are no known Flying-fox camps associated with the study area. Due to the lack of the important breeding habitat features the species is not considered to be a candidate species. |
| Stagonopleura guttata | Diamond Firetail | Vulnerable | Predicted ecosystem credit species | Species recorded in the study area. May occasionally occur in the study area where more suitable habitat adjoins. The study area habitats are considered of generally poor quality to support this species over much of its length. |

⁽¹⁾ Grey-headed Flying-fox (*Pteropus poliocephalus*) is a dual credit species however for the purpose of the Project, the Revised BDAR states this is a 'predicted ecosystem credit species' due to the lack of the important breeding habitat features (breeding camps)

A table detailing threatened flora species specified by the Revised BDAR that are known or predicted to occur in the Revised BDAR study area, and which have a moderate, high or known likelihood of occurrence is provided in Appendix H. The table includes scientific and common names, BC Act and EPBC Act listings, a written description and an example image for each species.



4.1.5 Aquatic habitat

The study area includes 26 watercourses and three (3) waterbodies, of which 12 were ranked as medium to high priority watercourses and were subject to field survey and habitat assessment. The ranking of watercourses was based on Key Fish Habitat (KFH) mapping (DPI, 2007a), threatened species distribution mapping (DPI, 2016) and Strahler stream order (Strahler, 1952).

Aquatic habitat assessment in the field found that except for the Murray River, all other watercourses were ephemeral with only four (4) sites containing small, shallow remnant pools:

- Oddies Creek:
- Eight Mile Creek;
- Buckaringah Creek;
- Jeralgambeth Creek.

The remaining watercourses were completely dry within the Project site at the time of surveys.

The Murray River (which is perennial and contains moderate flows) and Oddies Creek both contain habitat features such as woody debris, instream macrophytes, riparian vegetation and bank overhang. Eight Mile Creek contained instream macrophytes and Buckaringah Creek contained large woody debris. The remaining watercourses lacked important fish habitat features. First and second-order drainage lines and tributaries that were visited usually lacked riparian or aquatic vegetation and were dry. All watercourses and riparian zones were significantly modified by agricultural land practices.

Targeted threatened fauna surveys were undertaken using bait traps in medium to high-priority watercourses where water and/or remnant pools were present. Pelagic species and/or larger-bodied fish species were not targeted in the Murray River and were assumed present and considered further in a likelihood of occurrence assessment.

Targeted surveys did not result in the capture of any threatened species and only the exotic Mosquitofish were captured.

4.2 Weeds and biosecurity

4.2.1 Weeds

Two exotic flora species recorded within the study area during field surveys were listed under the Biosecurity Act as priority weeds for the Murray and Riverina region (Department of Planning, Industry and Environment, 2020).

These two species are also listed as Weeds of National Significance (WONS) (Australian Weeds Committee, 2020). All priority weeds and weeds of National Significance are outlined below in Table 10.

TABLE 10: PRIORITY WEEDS AND WEEDS OF NATIONAL SIGNIFICANCE

| SPECIES NAME | PRIORITY WEEDS | WONS |
|-----------------------------------------|------------------------------------------------------------------------|------|
| Asparagus asparagoides (Bridal Creeper) | Prohibition on dealings. Must not be imported into the State or sold. | Yes |
| Rubus fruticosus agg. (Blackberry) | Prohibition on dealings Must not be imported into the State or sold. | Yes |

In addition to priority weeds and weeds of National Significance the following high-threat weeds were also recorded:

- Acer negundo (Box-elder Maple);
- Agrostis capillaris (Browntop Bent);
- Alternanthera pungens (Khaki Weed);
- Bromus diandrus (Great Brome);
- Cyperus eragrostis (Umbrella Sedge);
- Eragrostis curvula (African Love Grass);
- Fraxinus angustifolia (Narrow-leaved Ash);
- Hypericum perforatum (St. John's Wort);
- Ligustrum lucidum (Large-leaved Privet);
- Ligustrum sinense (Small-leaved Privet);



- Paspalum dilatatum (Paspalum);
- Romulea rosea (Onion Grass);
- Vinca major (Greater Periwinkle).

4.3 Matters of National Environmental Significance

4.3.1 Threatened species and ecological communities

Ecological communities

Based on broad-scale state vegetation mapping and database searches, a total of one candidate threatened ecological community listed under the *Commonwealth Environment Protection and Biodiversity Conservation Act 1999* (EPBC Act) was considered likely to occur, being:

White Box – Yellow Box – Blakely's Red Gum Grassy Woodland and Derived Native Grasslands.

A comparative assessment of native vegetation recorded within the Project site against this EPBC Act listed threatened ecological community was completed as part of the Revised BDAR. The assessment concluded that only patches of moderate condition PCT 277 meet the criteria of the EPBC Act listing for White Box – Yellow Box – Blakely's Red Gum Grassy Woodlands and Derived Native Grasslands.

Threatened flora species

A total of 18 EPBC Act listed threatened flora species are known to occur or are predicted to occur within the locality of the study area. Of these, four were identified as having a moderate likelihood of occurrence based on previous records and availability of potential habitat.

No individuals of these species were recorded during targeted surveys undertaken as part of the Revised BDAR.

Threatened fauna species

Thirty-one EPBC Act listed threatened fauna species are known to occur or are predicted to occur within the locality of the study area. This comprised three species of amphibians, 12 birds, eight mammals, two reptiles, two invertebrates and four fish (Appendix C-2 of the Revised BDAR). Of these, six were identified to have a moderate or higher likelihood of occurrence based on previous records and the availability of potential habitat.

Two threatened fauna species listed under the EPBC Act, including Superb Parrot and Grey-headed Flying-fox, were recorded in the study area during targeted surveys.

4.3.2 Migratory species

Migratory species are protected under international agreements, to which Australia is a signatory, including Japan-Australia Migratory Bird Agreement (JAMBA), China Australia Migratory Bird Agreement (CAMBA), Republic of Korea Australia Migratory Bird Agreement (RoKAMBA) and the Bonn Convention on the Conservation of Migratory Species of Wild Animals. Migratory species are considered Matters of National Environmental Significance (MNES) and are protected under the EPBC Act.

A total of 14 EPBC Act listed migratory species are known or predicted to occur within the locality of the study area based on the results of database searches completed. One species, the White-throated Needletail, is considered to have a moderate likelihood of occurrence within the study area. As the White-throated Needletail is listed as migratory and threatened under the EPBC Act, an assessment of significance was carried out for the Revised BDAR using the threatened species criteria.

4.3.3 Wetlands of national and international importance

Nationally important wetlands

One nationally important wetland was identified by the Protected Matters Search Tool (PMST) as occurring in proximity to the study area; being Doodle Comer Swamp. This wetland is located approximately 1 kilometre southwest of the enhancement site. The wetland is located 2.3 kilometres downstream of Buckaringah Creek, which is located about 150 metres north of the Henty Yard clearance enhancement site.

Wetlands of international importance (Ramsar Wetlands)

Seven Ramsar wetlands or Wetlands of International importance were identified by database searches completed within a 20-kilometre buffer of the project. These include:

CONSTRUCTION BIODIVERSITY MANAGEMENT PLAN - STAGE C



- Banrock station wetland complex located 600–700 kilometres upstream of the Murray River bridge enhancement site;
- Barmah forest located approximately 100–150 kilometres upstream of the Murray River enhancement site;
- Gumbower forest located approximately 150–200 kilometres upstream of the Murray River enhancement site;
- Hattah-kulkyne lakes located approximately 400–500 kilometres upstream of the Murray River enhancement site:
- NSW central Murray state forests located approximately 100 kilometres upstream of the Murray River enhancement site;
- Riverland located 500–600 kilometres upstream of the Murray River enhancement site;
- The Coorong, and Lakes Alexandra and Albert wetland located 500–600 kilometres from the Murray River enhancement site.

All these Wetlands of International Significance are located more than 100 kilometres from the study area and are unlikely to be directly or indirectly impacted by the project.

4.3.4 World and National heritage

Based on the Protected Matters Search Tool (PMST), no World Heritage Properties are located within or near the study area and therefore will not be impacted by the project. One listed National Heritage property was identified in the PMST which included:

Bonegilla Migrant Camp – Block 19.

Bonegilla Migrant Camp does not occur within the study area (located about 10km east of the Murray River bridge enhancement site) and as such will not be impacted by the project.



5 ENVIRONMENTAL ASPECTS AND IMPACTS

5.1 Construction activities

Key activities associated with Stage C of the project that could result in impacts to terrestrial and aquatic flora and fauna include:

- Clearing of native vegetation (including habitat);
- Works around watercourses within the riparian zone (including clearing of riparian vegetation);
- Dewatering of dams;
- Noise, vibration, and light impacts from ancillary facilities and construction works;
- Fencing and property boundary adjustment work;
- General earthworks near vegetation, resulting in disturbance of soils, consequential erosion and the mobilisation of sediment;
- Instream works including culvert works and bridge alterations;
- Establishment of ancillary facilities and access tracks (potential temporary habitat fragmentation);
- Heavy and light vehicle movements;
- Earthworks, including stockpiling of material;
- Utility and drainage works;
- Use of chemicals/fuels (potential for spills).

5.2 Ecological impacts

This section summarises the impacts to biodiversity within and adjacent to the project.

The Revised BDAR provides information on how impacts to biodiversity values were avoided and minimised through the planning and design phase of the project. In accordance with Section 7.1.1 of the BAM, efforts to avoid and minimise direct impact on native vegetation and habitat through project design are addressed in Table 8.1 of the Revised BDAR.

In accordance with CoA E22, in the event that potential or actual impacts to any threatened communities or species not listed in CoA E20 are discovered, all work that may impact the identified species or community will stop to prevent further impact and the Planning Secretary and DCCEEW (NSW) (and DCCEEW (Cth) where relevant) will be notified in writing. Work will not recommence until the relevant agencies have been consulted and any required approvals have been obtained.

In the event that potential or actual impacts to threatened species habitat or vegetation would exceed the area of impact stated in CoA E20, all work that may impact the identified species habitat or community will stop to prevent further impact. Work will not recommence until it is confirmed that clearing limits will not be exceeded or any required approvals have been obtained.

Table 11 identifies Threatened Ecological Communities and threatened species polygons mapped within each enhancement site.

TABLE 11: MAPPED TEC AND ENDANGERED SPECIES

| ENHANCEMENT SITE | THREATENED ECOLOGICAL COMMUNITIES | THREATENED FAUNA / FLORA POLYGONS PRESENT |
|-------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------|
| Murray River bridge | None | Superb Parrot Squirrel Glider Sloane's Froglet (Sloane's Froglet Survey identified none present) |
| Albury Station Pedestrian bridge | None | None |
| Albury Yard | BC Act - White Box - Yellow Box -Blakely's Red Gum Grassy Woodland and Derived Native Grassland in the NSW North Coast, New England Tableland, Nandewar, Brigalow Belt South, Sydney | Sloane's Froglet (Sloane's Froglet Survey identified none present) |



| ENHANCEMENT SITE | THREATENED ECOLOGICAL COMMUNITIES | THREATENED FAUNA / FLORA POLYGONS PRESENT |
|----------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | Basin, South Eastern Highlands, NSW South Western Slopes, South East Corner and Riverina Bioregions – Critically Endangered. | |
| Riverina Highway bridge | None | Sloane's Froglet (Sloane's Froglet Survey identified none present) |
| Billy Hughes bridge | BC Act - White Box - Yellow Box -Blakely's Red Gum Grassy Woodland and Derived Native Grassland in the NSW North Coast, New England Tableland, Nandewar, Brigalow Belt South, Sydney Basin, South Eastern Highlands, NSW South Western Slopes, South East Corner and Riverina Bioregions – Critically Endangered. | Superb Parrot Squirrel Glider Sloane's Froglet (Sloane's Froglet Survey identified none present, refer to Section 6.9 for additional information) |
| Table Top Yard | BC Act - White Box - Yellow Box -Blakely's Red Gum Grassy Woodland and Derived Native Grassland in the NSW North Coast, New England Tableland, Nandewar, Brigalow Belt South, Sydney Basin, South Eastern Highlands, NSW South Western Slopes, South East Corner and Riverina Bioregions – Critically Endangered. | Superb Parrot Squirrel Glider Sloane's Froglet (Sloane's Froglet Survey identified none present) Key's Matchstick grasshopper |
| Culcairn Pedestrian bridge | None | Superb Parrot Squirrel Glider Sloane's Froglet (Sloane's Froglet Survey identified none present) |
| Culcairn Yard | None | Superb Parrot Squirrel Glider Sloane's Froglet (Sloane's Froglet Survey identified none present) |
| Henty Yard | BC Act - White Box - Yellow Box -Blakely's Red Gum Grassy Woodland and Derived Native Grassland in the NSW North Coast, New England Tableland, Nandewar, Brigalow Belt South, Sydney Basin, South Eastern Highlands, NSW South Western Slopes, South East Corner and Riverina Bioregions – Critically Endangered. | Superb Parrot Squirrel Glider Sloane's Froglet (Sloane's Froglet Survey identified none present) |
| Yerong Creek Yard | None | Sloane's Froglet (Sloane's Froglet Survey identified none present) |
| The Rock Yard | None | None |
| Uranquinty Yard | None | Superb Parrot Squirrel Glider Sloane's Froglet (Sloane's Froglet Survey identified none present) |
| Pearson Street bridge | BC Act - White Box - Yellow Box -Blakely's Red Gum Grassy Woodland and Derived Native Grassland in the NSW North Coast, New England | Superb ParrotSquirrel Glider |



| ENHANCEMENT SITE | THREATENED ECOLOGICAL COMMUNITIES | THREATENED FAUNA / FLORA POLYGONS PRESENT |
|------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | Tableland, Nandewar, Brigalow Belt South, Sydney Basin, South Eastern Highlands, NSW South Western Slopes, South East Corner and Riverina Bioregions – Critically Endangered. | Sloane's Froglet (Sloane's Froglet Survey identified none present) |
| Cassidy Parade bridge | None | Sloane's Froglet (Sloane's Froglet Survey identified none present) |
| Edmonson Street bridge | None | Sloane's Froglet (Sloane's Froglet Survey identified none present) |
| Bomen Yard | BC Act - White Box - Yellow Box -Blakely's Red Gum Grassy Woodland and Derived Native Grassland in the NSW North Coast, New England Tableland, Nandewar, Brigalow Belt South, Sydney Basin, South Eastern Highlands, NSW South Western Slopes, South East Corner and Riverina Bioregions – Critically Endangered. | Superb Parrot Squirrel Glider Sloane's Froglet (Sloane's Froglet Survey identified none present) |
| Harefield Yard | BC Act - White Box - Yellow Box -Blakely's Red Gum Grassy Woodland and Derived Native Grassland in the NSW North Coast, New England Tableland, Nandewar, Brigalow Belt South, Sydney Basin, South Eastern Highlands, NSW South Western Slopes, South East Corner and Riverina Bioregions – Critically Endangered. | Superb Parrot Squirrel Glider Sloane's Froglet (Sloane's Froglet Survey identified none present) |
| Kemp Street bridge | None | Sloane's Froglet (Sloane's Froglet Survey identified none present) |
| Junee Station Pedestrian bridge | None | None |
| Junee Yard | None | None |
| Olympic Highway Underbridge | BC Act - White Box - Yellow Box -Blakely's Red Gum Grassy Woodland and Derived Native Grassland in the NSW North Coast, New England Tableland, Nandewar, Brigalow Belt South, Sydney Basin, South Eastern Highlands, NSW South Western Slopes, South East Corner and Riverina Bioregions – Critically Endangered. | Superb Parrot Squirrel Glider Sloane's Froglet (Sloane's Froglet Survey identified none present) Key's Matchstick grasshopper |
| Junee to Illabo | BC Act - White Box - Yellow Box -Blakely's Red Gum Grassy Woodland and Derived Native Grassland in the NSW North Coast, New England Tableland, Nandewar, Brigalow Belt South, Sydney Basin, South Eastern Highlands, NSW South Western Slopes, South East Corner and Riverina Bioregions – Critically Endangered. EPBC Act - White Box-Yellow Box-Blakely's Red Gum Grassy Woodland and Derived Native Grassland – Critically Endangered | Superb Parrot Squirrel Glider Sloane's Froglet (Sloane's Froglet Survey identified none present) Key's Matchstick grasshopper |



5.2.1 Clearing of non-native vegetation

Non-native vegetation occurs within and adjacent to the proposal site. Two non-native vegetation communities were identified. Some removal of non-native vegetation including, urban exotic/native landscape plantings may result because of the proposal. Where non-native vegetation occurred adjacent to areas of PCT 277 in moderate-good and derived broad condition states along the Junee to Illabo clearances for the Inland Slopes IBRA subregion these were assigned to vegetation zone 277_non-native.

TABLE 12: DIRECT IMPACTS ON NON-NATIVE VEGETATION WITHIN THE INLAND SLOPES IBRA SUBREGION AND THE CORRESPONDING PRECINCT AND ENHANCEMENT SITES

| VEGETATION TYPE | VEGETATION ZONE | PRECINCT | ENHANCEMENT SITE | DIRECT IMPACT (HA) |
|---------------------------------------------------------------------------------------------------------------|--------------------|----------|----------------------------|-----------------------|
| PCT 277 – Blakely's Red Gum – Yellow Box grassy tall woodland of the NSW South Western Slopes Bioregion | Non-Native | Junee | Junee to Illabo clearances | 30.5 |

5.2.2 Clearing of native vegetation

Stage C of the Project has the potential to impact on 4.57 hectares of native vegetation, comprising 0.04ha of PCT5 and 4.53ha of PCT 277. These impacts on native vegetation as they relate to Stage C, including each PCT, for each IBRA subregion and the corresponding precinct and enhancement sites are outlined in Table 13 and Table 14.

TABLE 13: DIRECT IMPACTS ON NATIVE VEGETATION WITHIN THE LOWER SLOPES IBRA SUBREGION AND THE CORRESPONDING PRECINCT AND ENHANCEMENT SITES

| VEGETATION TYPE | VEGETATION ZONE | PRECINCT | ENHANCEMENT SITE | DIRECT IMPACT (HA) |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------|-------------|---------------------------|-----------------------|
| PCT 277 – Blakely's Red | | Albury | Billy Hughes bridge | 0.01 |
| Gum – Yellow Box grassy tall woodland of the NSW South Western | Poor condition | Wagga Wagga | Bomen Yard clearances | 0.02 |
| Slopes Bioregion | | Junee | Harefield Yard clearances | 0.11 |
| PCT 5 – River Red Gum herbaceous grassy very tall open forest wetland on inner floodplains in the lower slopes sub- region of the NSW South Western Slopes Bioregion and the eastern Riverina Bioregion | Poor condition | Junee | Harefield Yard clearances | 0.02 |
| Total native vegetation impact | | | | |

TABLE 14: DIRECT IMPACTS ON NATIVE VEGETATION WITHIN THE INLAND SLOPES IBRA SUBREGION AND THE CORRESPONDING PRECINCT AND ENHANCEMENT SITES

| VEGETATION TYPE | VEGETATION ZONE | PRECINCT | ENHANCEMENT SITE | DIRECT IMPACT (HA) |
|---------------------------------------------------------------------------------------|--------------------|-------------|----------------------------|-----------------------|
| PCT 5 – River Red Gum herbaceous grassy very | | Albury | Murray River bridge | 0.02 |
| tall open forest wetland on inner floodplains in the lower slopes sub-region of | Poor condition | Wagga Wagga | Uranquinty Yard clearances | 0.01 |



| VEGETATION TYPE | VEGETATION ZONE | PRECINCT | ENHANCEMENT SITE | DIRECT IMPACT (HA) |
|---------------------------------------------------------------------------------|--------------------|----------|-----------------------------|-----------------------|
| the NSW South Western Slopes Bioregion and the eastern Riverina Bioregion | | | | |
| | Moderate condition | Junee | Junee to Illabo clearances | 0.47 |
| | | | Albury Yard clearances | 0.01 |
| | Poor condition | Albury | Billy Hughes bridge | 0.14 |
| PCT 277 – Blakely's Red | | | Tabletop Yard clearances | 0.01 |
| Gum – Yellow Box grassy tall woodland of the NSW South Western Slopes | | Junee | Olympic Highway underbridge | 0.02 |
| Bioregion | | | Junee to Illabo clearances | 1.11 |
| | Derived condition | Junee | Junee to Illabo clearances | 2.34 |
| | N | | Junee to Illabo clearances | 0.07 |
| | Native plantings | Junee | Olympic Highway underbridge | 0.19 |
| Total native vegetation impact | | | | |

Removal of threatened ecological communities

Stage C of the project will impact on a total of 4.27 hectares of threatened ecological community in the form of White Box – Yellow Box – Blakely's Red Gum Grassy Woodland and Derived Native Grassland. Potential direct impacts on threatened ecological communities due to the project for each IBRA subregion are outlined in Table 15.

All Moderate and Derived condition TEC is located within or adjacent to the Junee to Illabo clearances enhancement site. Impacts to the threatened ecological communities will not exceed the limits set out in CoA E20.

TABLE 15: DIRECT IMPACTS ON TEC DUE TO THE PROJECT

| THREATENED ECOLOGICAL | VEGETATION | | IBRA SUBREGION | | DIRECT | |
|-----------------------------------------------------------------------------------------------|---------------------------------|--------------------------|-----------------|------------------|----------------|--|
| COMMUNITY | TYPE AND ZONE | BC ACT | Lower slopes | Inland slopes | IMPACT (HA) | |
| | PCT 277 – Moderate condition | | 0 | 0.5 | 0.50 | |
| White Box – Yellow Box – Blakely's Red Gum Grassy Woodland and Derived Native Grassland | PCT 277 – Poor condition | Critically Endangered | 0.14 | 1.29 | 1.43 | |
| | PCT 277 – Derived condition | | 0 | 2.34 | 2.34 | |
| Total direct impact on threatened ecological communities | | | | | | |

Removal of threatened flora

No threatened flora was identified as existing within the Revised BDAR study area during the field surveys undertaken as part of the Revised BDAR.



Removal of threatened fauna species habitat and habitat features

The removal of the vegetation communities described in Table 13 and Table 14 would impact fauna habitats due to the removal of foraging and breeding habitats of fauna species. The predicted impact to species credit threatened fauna due to the removal of habitat is outlined in Table 16. Impacts to threatened species' habitats will not exceed the limits set out in CoA E20.

TABLE 16: DIRECT IMPACTS ON THREATENED SPECIES CREDIT SPECIES WITHIN THE PROJECT

| SCIENTIFIC NAME | COMMON NAME | BC ACT ¹ | SAII | PCT AND HABITAT FEATURES | DIRECT IMPACT (HA) | | |
|--------------------------|---------------------------------|------------------------|------|---------------------------------------------------------------------------------|-----------------------|--|--|
| Lower Slopes | Lower Slopes IBRA Sub-region | | | | | | |
| Crinia sloanei | Sloane's Froglet* | E | No | PCT 5 (poor condition) and PCT 277 (poor condition) | 0.03 | | |
| Polytelis swainsonii | Superb Parrot | V | No | PCT 5 (poor condition) and PCT 277 (poor condition) | 0.16 | | |
| Petaurus norfolcensis | Squirrel Glider | V | No | PCT 5 (poor condition) and PCT 277 (poor condition) | 0.16 | | |
| Inland Slopes | IBRA Sub-region | | | | | | |
| Crinia sloanei | Sloane's Froglet* | Е | No | PCT 5 (poor condition), PCT 277 (native plantings) and PCT 277 (poor condition) | 0.23 | | |
| Keyacris scurra | Key's Matchstick Grasshopper | V | No | PCT 277 (poor condition) and PCT 277 (moderate condition) | 0.21 | | |
| Polytelis swainsonii | Superb Parrot | V | No | PCT 5 (poor condition) and PCT 277 (poor and moderate condition) | 1.82 | | |
| Petaurus norfolcensis | Squirrel Glider | V | No | PCT 5 (poor condition) and PCT 277 (poor and moderate condition) | 1.82 | | |

Threat status under the BC Act: V = Vulnerable, E = Endangered.

Existing development and land uses, such as agriculture and road infrastructure, have created barriers to movement for some fauna species, particularly those that are limited by dispersal abilities and habitat preferences. Vegetation removal for the Project may exacerbate fragmentation for the Squirrel Glider (*Petaurus norfolcensis*), whose movement is limited by gliding distances between areas of habitat. This species was recorded foraging in woodland patches at the Billy Hughes bridge enhancement site and in areas located 3 km to the north of the Uranquinty Yard clearances enhancement site

Fauna connectivity measures to mitigate the potential impacts to Squirrel Glider (*Petaurus norfolcensis*) at the Billy Hughes enhancement site will be outlined in the Fauna Connectivity Strategy to be prepared in accordance with CoA E31. as discussed in Section 6.10.

5.2.3 Impacts to aquatic biodiversity

Direct impacts from the Project on aquatic biodiversity would include the removal of riparian and instream vegetation and woody debris, temporary barriers to fish passage and potential mortality to aquatic flora and fauna from poor water quality due to clearing of riparian vegetation and instream works.

Indirect impacts to aquatic biodiversity relate to the mobilisation of poor-quality stormwater runoff from construction activities including vegetation removal, earthworks, accidental spills, establishment and use of construction compounds, as well as riverbank and streambed disturbance that would result in sedimentation and pollution downstream.

The potential impacts during construction are considered to be a moderate risk at one watercourse during Stage C works:

^{*}Potential Sloane's Froglet habitat was not found to support any froglets during targeted surveys undertaken in accordance with CoA E25



- Murray River (Murray River bridge) this watercourse is defined as type 1 highly sensitive KFH and a class 1
 perennial watercourse. Potential impacts on this watercourse relate mainly to indirect impacts to water quality
 during bridge modification.
- Sandy Creek (Uranquinty Yard clearances) this watercourse is defined as type 1 highly sensitive KFH as it is
 within the mapped distribution of a threatened species (Flathead Galaxias (Galaxias rostratus)) and a class 2
 ephemeral watercourse.
- Jeralgambeth Creek north arm (Junee to Illabo clearances) this watercourse is defined as type 2 moderately sensitive KFH through the presence of some habitat features such as remnant pools and aquatic vegetation and a class 2 ephemeral watercourse

Temporary water crossings are expected to be required at Sandy Creek (Uranquinty Yard clearances) and Jeralgambeth Creek (Junee to Illabo clearances). Management of potential impacts to aquatic biodiversity is considered further in Section 6.3. No instream works are permitted to occur in the Murray River or Oddies Creek. There will be no works to the substructure of Murray River bridge.

The aquatic biodiversity impact assessment prepared for the project as part of the EAD concluded that the impacts of the Project would not significantly compromise the functionality, long-term connectivity or viability of habitats, or ecological processes within watercourses in the study area. It was determined that most of the potential construction impacts are associated with indirect impacts on water quality and would therefore be temporary and managed through the adoption of appropriate erosion and sediment control measures.

The Construction Soil and Water Management Plan (CSWMP) details how erosion and sedimentation would be controlled during construction. Site specific Erosion and Sedimentation Control Plans (ESCPs) will be developed for each enhancement site.

5.2.4 Habitat fragmentation

The Revised BDAR concluded the project is considered unlikely to result in a large increase to landscape scale fragmentation and to further limit connectivity and movement corridors above what already exists in the project site. This is as the project occurs within an already highly fragmented landscape with limited large patches of remnant vegetation. The impacts from the project would largely involve small areas of disturbance of vegetation patches, which would not result in significant habitat fragmentation.

The predicted level of fragmentation from the project is not expected to be enough to prevent the breeding and dispersal of plant pollinators or the dispersal of plant propagules (i.e. seed or other vegetative reproductive material) between habitat patches. The existing functional connectivity for many species would remain in the project site and be alleviated with connectivity mitigation measures. The fauna connectivity strategy required by CoA E29 is further considered in Section 6.10.

5.2.5 Injury and mortality of fauna

A Fauna Handling and Rescue Procedure has been prepared as part of this plan and is attached as Appendix B. This Procedure applies to the handling of any fauna encountered during construction if required.

Injury and mortality of fauna could occur during construction activities. Injury and mortality may occur:

- During construction when vegetation and habitat are being cleared;
- During construction when machinery and plant are moved to, from and on-site;
- During construction with open excavations.

All roads and rail have the potential to result in the mortality of native animals. The risk is higher where roads and rail:

- Traverse areas of substantial animal habitat;
- Are located near natural or artificial water bodies:
- Contain food sources (e.g. mown grass verges, nectar-producing shrubs) which attract animals to the road edge;
- Have high-speed limits;
- Provide poor visibility of wildlife (e.g. due to bends, crests and poor lighting).

While it is not possible to eliminate the risk of roadkill and train strikes occurring, it is possible to minimise this through consideration of the above factors in the design of roads/access routes, landscaping, fauna connectivity structures and infrastructure and the implementation of road signs and reduced speed limits, where possible. The provision of fauna crossings such as glider poles, incorporated into the design will reduce the likelihood of crossing attempts at inappropriate or dangerous locations and minimise operational train strike risk.



Measures to minimise roadkill will be delivered in the concept and detailed design processes of the roads and rail infrastructure including use of fauna crossings and landscaping plans.

During construction there would also be risks of wildlife strikes during workforce travelling to and from site. A driver code of conduct will be put in place for all vehicle drivers on the project to address safe driving behaviour. The project fauna handling and rescue procedure would apply to any wildlife strikes that happen during travel to and/or from construction sites. It is unlikely that the project would contribute significantly to vehicle strikes to native fauna, and the Revised BDAR determined that the consequences of impacts to species are likely to be negligible.

5.2.6 Invasion and spread of weeds and pests

Thirteen high-threat weeds were recorded during field surveys, along with two (2) priority WoNS. Typically, weed invasion and spread is an indirect impact of projects that are often generated during construction by clearing vegetation and moving contaminated plant/equipment throughout the area. Other activities, including earthworks and movement of soil, can also result in the dispersal and introduction of weeds throughout the area.

5.2.7 Invasion and spread of pathogens and disease

The project has the potential to increase the spread of pathogens that threaten native biodiversity values, such as the soil-borne pathogen *Phytophthora cinnamomi* (Phytophthora) and *Austropuccinia psidii* (Myrtle rust). Phytophthora infects root systems whereas Myrtle Rust deforms leaves and leads to heavy defoliation. Both pathogens are associated with damage and death to native plants and may be dispersed over large distances.

Phytophthora can be spread through flowing water, such as storm runoff, or may spread within a site via mycelial growth from infected roots to roots of healthy plants. Propagules of Phytophthora may also be dispersed by vehicles (e.g. cars and earth-moving equipment), animals, walkers and movement of soil. Myrtle rust spores can be spread easily via contaminated clothing, hair, skin and personal items, infected plant material, and equipment as well as by insect/animal movement and wind dispersal.

The Project also has the potential to introduce or spread Amphibian Chytrid Fungus (Chytrid Fungus) (*Batrachochytrium dendrobatidis*). The accidental introduction or spread of Chytrid Fungus has the potential to adversely affect frog populations. Chytrid Fungus is a lethal and highly contagious frog disease that is detrimental to frogs and tadpoles. Chytrid is a water-borne fungus that may be spread as a result of handling frogs or through cross-contamination of water bodies, including through mud or moist soil.

The proposed construction activities could lead to an increased risk of dispersal of Phytophthora, Myrtle Rust and Chytrid Fungus through works involving soil disturbance, importation of fill and through the movement of water.

5.2.8 Water pollution

There is potential for sedimentation and spills to affect water quality in the waterways during the construction phase which could also affect native fish and frogs, including downstream of the construction footprint. Water pollution may also result from hydrocarbon leaks or spills from vehicles or equipment used during construction adjacent to waterways.

The CSWMP details how erosion and sedimentation would be controlled during construction. Site specific ESCPs will be developed for each enhancement site.

5.2.9 Noise, vibration, dust, light and contaminants

Construction in the project area may result in adverse impacts on locally occurring fauna species as a result of noise, vibration, dust and light. Increased noise, vibration, dust and light levels in the rail corridor and immediate surroundings are likely during construction.

Noise, vibration and light from construction sites would potentially disturb fauna and may disrupt foraging, reproductive, or movement behaviours, and may result in fauna temporarily avoiding habitats adjacent to the project site. Elevated levels of dust may be deposited onto the foliage of vegetation adjacent to the project area, resulting in reduced growth rates and decreases in the overall health of the vegetation.

Fauna are currently subject to varying levels of disturbance from noise, vibration and light as the Project site mostly encompasses an existing operational rail corridor that is located adjacent to existing roads in urban centres, rural townships and agricultural settings. Thus, there would be some habituation of fauna to noise and vibration in the study area. Given the project's ecological setting, the impacts from noise, vibration, dust and light emissions during construction are likely to be highly localised to the rail corridor and intermittent, with low impacts to flora and fauna species.



6 MANAGEMENT AND MITIGATION

A range of environmental requirements and mitigation measures are identified in the EAD. Specific safeguards and management measures to address impacts to biodiversity are identified within Section 6.1 to Section 6.11 and summarised in Table 20.

6.1 Vegetation clearing process

Impacts to threatened ecological communities, threatened species and their habitat, including clearing of native vegetation, will be avoided and minimised to the greatest extent practicable during detailed design and construction planning for the project.

The following tasks are required to occur before clearing commencement:

- A clearing and grubbing work pack, Environmental Work Method Statement (EWMS) and/or sensitive area plans will be developed for construction teams;
- Opportunities to retain and protect native vegetation, fauna habitat and riparian habitat will be identified during construction planning through a review of design and construction methodologies;
- The predicted extent of clearing of native vegetation will be checked against the extent of clearing as permitted by CoA E20. The predicted extent of clearing will also consider the type of clearing (e.g. temporary or permanent);
- Martinus Rail will endeavour to provide the indicative extent of clearing to IRPL at least 80 days prior to commencing;
- The construction impact zone is to be delineated by a surveyor;
- The extent of clearing required for construction of infrastructure is to be surveyed and marked out on site;
- The Martinus Rail Site Supervisor is to ensure the clearing limits and any exclusion and protection zones are delineated in accordance with the following requirements before clearing works commence. In areas that are not adjacent to exclusion zones (refer below), the clearing limits will be delineated using regularly placed pegs or identification markers at a maximum distance of three (3) metres apart. In locations adjacent to exclusion zones or where pegs and identification markers will not be suitably visible (for example, if obscured by existing vegetation), highly visible barrier or star pickets with tape such as colour-coded UV-stabilised rope, bunting, nightline, or other similarly robust and durable materials will be used ensuring a clear marking line;
- Any habitat trees to be retained within and adjacent to the clearing extents are to be prominently marked and tagged (see Section 6.1.1);
- Potential and confirmed Superb Parrot nest trees within the construction impact zone and visible surrounding
 areas will be identified and mapped. If identified, mitigation measures are to be considered in consultation with
 the project ecologist where works are proposed to occur during breeding season (September to November);
- Exclusion zones include areas of retained vegetation, including riparian, retained threatened species habitats,
 habitat trees and areas of biodiversity value adjoining the project that are located in close proximity to work
 areas. Delineation of these areas will be completed per the requirements above and the extent will be verified by
 a suitably qualified ecologist prior to the commencement of clearing or any site activity that could damage the
 vegetation within the exclusion zone;
- The Martinus Rail Environment, Sustainability and Approvals Manager (ESM) or delegate will ensure delineation installed is consistent with the requirements detailed above to reduce the risk of error or misinterpretation of boundaries and that exclusion zones are consistent with those identified as exclusion zones within the SAPs.

6.1.1 Pre-clearing survey

The project ecologist will undertake a pre-clearing survey within the proposed clearing extent prior to the commencement of clearing. The pre-clearing survey will include:

- Confirmation of the location and extent of any exclusion zones as well as verify the clearing extent as permitted by CoA E20;
- Identification and demarcation of all habitat trees within the proposed clearing extent with flagging (typically
 yellow), unique identifier numbers indicated by identification tags and GPS coordinates. Identification and
 demarcation may also occur during earlier surveys. If this is the case, the ecologist will confirm that habitat trees
 are prominently marked/tagged;
- Inspections of structures that provide potential microbat habitat (see Section 6.1.2);
- Identification of fauna that require relocation (including wild bees). This may include dusk stag-watches and/or endoscope searches where necessary (as detailed below);

CONSTRUCTION BIODIVERSITY MANAGEMENT PLAN - STAGE C



- Identification of nearby habitats for suitable release of fauna;
- Identification of suitable resources for salvage and beneficial reuse including, for example, hollows, tree trunks, logs, mulch, bush rock and root balls;
- Recording of GPS coordinates for all identified habitat trees, nests and habitat features during the pre-clearing survey, including potential and confirmed Superb Parrot nest trees within the construction impact zone and visible surrounding areas;
- Native aquatic fauna salvage in watercourses of residual pools directly impacted by construction;
- Survey and identify weed species targeted at listed species under the Biosecurity Act 2015;
- Collection of seeds from native plants to be removed for use in revegetation and rehabilitation across the Project area;
- Consideration of whether two-stage clearing is required (see Section 6.1.4) and therefore whether a rapid survey
 is required by the project ecologist within 24 hours of clearing.

Additional consideration will be given to hollow-bearing trees that are identified as having a high-likelihood of containing threatened microbats or gliders. In particular, trees should be thoroughly inspected for scars, claw marks or staining in proximity to hollow-bearing trees scheduled for removal.

Where the project ecologist identifies hollow-bearing trees, with a high-likelihood to be occupied by threatened microbats or gliders, the project ecologist will undertake a visual hollow search using a torch or extendable inspection camera (endoscope). Where a visual hollow search is not practical or possible, dusk stag-watches will be conducted once for each required hollow within three days prior to the scheduled clearing. Hollows in close proximity may be surveyed at the same time and by the same surveyor. Stag-watches are typically 40 minutes long at dusk. If there is no evidence of threatened microbat or glider activity, then no further consideration is recommended.

In the event that any pre-clearing surveys, visual hollow search or stag-watch indicates the presence of these species, their exclusion from habitat would be undertaken by the project ecologist. Where exclusion cannot be undertaken prior to clearing, the tree must be soft-felled using a harvester or similar. Clearing must be undertaken at dusk, or following sunset to minimise risk of predation if fauna cannot be captured safely.

The results of the pre-clearing surveys will be used to update and confirm the accuracy of the GIS and SAPs and these will be communicated and distributed to the construction team.

6.1.2 Management of fauna during pre-clearing

If identified by the project ecologist during the pre-clear survey, additional activities will be undertaken to encourage fauna to escape from the area to be cleared. This may include:

- Tree knocking approximately 24 hours prior to clearing;
- Manually disturbing Keys Matchstick Grasshopper habitat (see Appendix C) in areas of assumed presence by physical separation of grass tussocks and other refugia to encourage self-relocation outside the proposed clearing extents;
- Other techniques recommended by the project ecologist.

The project ecologist, or a suitably qualified handler, will capture and/or remove any remaining fauna that have the potential to be disturbed as a result of clearing activities and relocate any captured fauna into nearby suitable habitats documenting the location of any fauna release sites per the Fauna Handling and Rescue Procedure (Appendix B). If any unexpected finds are identified, the Unexpected Finds Protocol (Appendix A) will be followed.

Prior to the demolition of any structures, a diurnal pre-clearing survey is to be undertaken for microbats. Roost searches are to be carried out in a manner consistent with the methodologies provided in the NSW survey guide for the Biodiversity Assessment Method: 'Species credit' threatened bats and their habitats'. Surveys will consist of:

- Visual examination using a torch or extendable inspection camera (endoscope) of cavities in structures and hollows for roosting microbats;
- Visual inspection of the structure for evidence of microbat usage (scat);
- Ultrasonic detection using Echo-meter, or similar hand-held device.

Immediately prior (24 hours) to construction works at a structure, a diurnal rapid pre-clearing survey is required to determine whether the structure is free of microbats. A list of potential microbat roosting habitat is provided in Table 17.



TABLE 17: POTENTIAL MICROBAT ROOSTING HABITAT

| POTENTIAL HABITAT FEATURE TO INSPECT | SOUTHERN MYOTIS | BENT-WINGED BATS |
|-----------------------------------------------------------------------------------------------------------------------------------------|-----------------|------------------|
| CONCRETE STRUCTURES | | |
| Grab holes in culverts and bridge decking and girders | X | X |
| Expansion joints in concrete plank and Super-T bridges | X | Х |
| Parapet of Super-T girders on bridges | X | X |
| Semi-open concrete abutments | Х | Х |
| Under concrete bridge piles | X | Х |
| Scuppers on bridges and culverts | Х | Х |
| Join seals between reinforced concrete box culverts and BEBO arches | Х | Х |
| Aggregate/roughened sections of concrete and exposed steel reinforcement in culverts and stormwater drains | Х | Х |
| Roughened exposed areas and uneven surfaces including closure pours and the space between concrete girders and diaphragms under bridges | Х | Х |
| Purpose-built microbat habitat | X | X |
| Fairy Martin, Welcome Swallow and Paper/Mud Wasp nests under bridges or in culverts | Х | Х |
| Cavities below pile caps in bridges | X | X |
| Bridges and wharves with protected concrete joins between decking, girders and/or headstock | Х | Х |
| TIMBER STRUCTURES | | <u>'</u> |
| Timber jetties and wharves with cavities from rotting timber or design features. Habitat not exposed to rain or direct sunlight | Х | |
| Bridges – including the timber decking, split stringers, secondary stringers, cross girders, truss and support beams | Х | Х |

Individual microbats are typically not clearly visible, but evidence of microbat activity may include:

- audible sounds of bat calls 'squeaking';
- bat scats/guano;
- roosting bats concealed within the structure e.g. between culvert joins, lift holes or cracks;
- discolouration or staining from urine;
- presence of parasitic bat flies (Nycteribiid and Streblid);
- musty animal smells.

If there is no evidence of microbat activity and thorough inspection was possible, then no further consideration of microbats is recommended. In the event that any pre-clearing surveys or assessments and inspections of structures and vegetation indicates the presence of roosting/ hibernating bats or micro-bats, in the structures or elsewhere, their exclusion from habitat would be undertaken by the project ecologist.

Areas requiring demolition inspection will be identified by the Environment and Sustainability Manager, or delegate, in consultation with the Construction Manager, Area Manager or Foreperson and any specialist ecology consultants required.

Additionally, all native aquatic fauna salvaged from construction-impacted watercourses and residual pools will be relocated to similar habitat nearby.



6.1.3 Pre-clearing survey report

Following the completion of all pre-clearing surveys, a pre-clearing survey report is to be prepared which will include:

- Description of the presence of threatened flora species;
- Description of the presence or evidence of threatened fauna species (including fresh scats, scratches and remains of prey);
- Description and locations of identified habitat trees;
- Description and photographs of identified suitable resources for salvage and beneficial reuse;
- Description of identified weeds including the location of identified weeds;
- Details of weed management measures and controls for each of the weeds identified;
- Details of any fauna including aquatic fauna, salvaged and relocated;
- Details of native plant seeds collected.

6.1.4 Staged or non-staged clearing

All areas that need to be cleared will be subject to staged or non-staged clearing. Staged clearing occurs in locations where the ecologist identifies habitat and is typically referred to as 'two-stage clearing'. Areas where no habitat trees or structures are identified by the ecologist may be cleared in one step. The project ecologist must be onsite to supervise the clearing works during two stage clearing and in areas of known and assumed present threatened species habitat (i.e. species polygons).

Clearing – No habitat features identified (one-stage clearing)

If no habitat features have been identified by the project ecologist in the pre-clearing surveys, then a two-stage clearing process is not required and clearing can be undertaken in a single step without the ecologist present. Examples include cropland/agricultural pasture areas and areas outside of known and assumed present threatened species habitat (i.e. species polygons).

All other demarcation and flagging are to occur as required for exclusion zones or retained vegetation.

Clearing – Habitat features identified (two-stage clearing)

Two-stage clearing is required where habitat features have been identified by the project ecologist during the pre-clearing surveys and in areas of known and assumed present threatened species habitat (i.e. species polygons). For these locations, the clearing area must be surveyed by the project ecologist within 24 hours or immediately before clearing to:

- Obtain updated information on fauna and flora habitat that is present, including:
 - o Inspection of identified habitat features for evidence of fauna occupation;
 - Identify any fauna that will require relocation before clearing (including wild bees);
 - Document the location of any fauna release sites off easement;
 - Demarcate any newly identified habitat and confirm that habitat trees are prominently marked/tagged;
 - Confirm that habitat trees to be retained within and adjacent to the clearing extents are prominently marked/tagged;
 - o Capture and relocate any identified non-mobile fauna;
 - Collect data on any newly identified threatened species in the area.
 - o Identify any habitat features appropriate for salvage (See Section 6.2)

Initial clearing - Removal of non-habitat vegetation

In this first stage, non-habitat vegetation will be removed, and all marked habitat features will be retained until the final stage of clearing. This allows respite between the initial disturbance and the final removal of habitat. The changed environment and the disturbance from non-habitat vegetation clearing should encourage residing fauna to relocate voluntarily without human handling.

A respite period of a minimum of 24 hours after the removal of non-habitat vegetation is required to allow resident fauna the opportunity to vacate the remaining habitat before final clearing commences.

Final clearing - Removal of habitat vegetation

The project ecologist must be onsite to supervise the final clearing works. The project ecologist will:

Thoroughly inspect all hollows that are accessible from the ground immediately before clearing;



- Carefully determine the appropriate felling methodology and supervise the removal of habitat features and hollows when trees are dropped to the ground;
- Ensure detected fauna are encouraged to self-relocate or capture and relocate any encountered fauna to preidentified release sites;
- Ensure that any injured wildlife is transported to a veterinarian or wildlife carer;
- Where breeding fauna or dependent young are detected during the clearing works, consult with a licensed carer
 to determine whether the animal/s require ongoing care or can be safely relocated to an adjacent habitat.

Locations of fauna release (including GPS coordinates) will be recorded in a post-clearing report. Once all fauna habitat inspections and any required fauna removal are complete, the remaining vegetation clearing will commence.

6.1.5 Post-clearing report

At the completion of clearing, the project ecologist will prepare a Post-Clearing Report. The report will include:

- Confirm and map the final area cleared, the number and identity of all habitat trees removed, and specifically, the post-clearance abundance and density count of hollow-bearing trees;
- Information on clearing operations, dates, procedures, and areas;
- A breakdown of the spatial extent and type of clearing of each mapped Plant Community Type (PCT) including vegetation zone as identified in the Revised BDAR;
- A breakdown of the spatial extent and type of clearing of mapped threatened ecological communities and threatened flora;
- Fauna, nests or other fauna habitats were impacted by clearing works;
- Live animal sightings, captures, any releases or injured/shocked wildlife;
- The location of any fauna relocations;
- Fauna that may have died as a result of clearing;
- Photographs of any rescued fauna (where obtained);
- Reuse, relocation or disposal of snags, hollows or coarse woody debris will be included in the post-clearing report.

The spatial extent of clearing will be recorded in GIS file format. The clearing of native vegetation will be monitored and recorded to inform any final biodiversity offset requirements within the biodiversity offset package.

6.1.6 Vegetation clearing limits

All vegetation clearing will be undertaken in accordance with the requirements in this section. Clearing limits for threatened fauna species and plant community types will be limited to the area of impact allowed by CoA E20 detailed in Table 18 and Table 19.

In accordance with CoA E22, if potential or actual impacts to any threatened communities or species not listed in CoA E20 are discovered, all work that may impact the identified species or community will stop to prevent further impact and the Planning Secretary and DCCEEW (NSW) (and DCCEEW (Cth) where relevant) will be notified in writing. Work will not recommence until the relevant agencies have been consulted and any required approvals have been obtained.

To manage the clearing of endangered native vegetation, all clearing of mapped threatened plant community types will be assessed by an ecologist prior to vegetation being removed. This information will then be tracked in a register with a corresponding GIS tool to ensure that the PCT impacts are in accordance with the limits outlined in the EAD.

TABLE 18: PLANT COMMUNITY TYPES CLEARING LIMITS

| NAME OF PLANT COMMUNITY TYPE/ID | AREA OF IMPACT (HA) PER COA E20 |
|----------------------------------------------------------------------------------------------------------------|------------------------------------|
| 277 – Moderate – Blakely's Red Gum – Yellow Box grassy tall woodland of the NSW South Western Slopes Bioregion | 0.5 |
| 277 – Poor - Blakely's Red Gum – Yellow Box grassy tall woodland of the NSW South Western Slopes Bioregion | 1.44 |



| NAME OF PLANT COMMUNITY TYPE/ID | AREA OF IMPACT (HA) PER COA E20 |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------|
| 277 – Derived - Blakely's Red Gum – Yellow Box grassy tall woodland of the NSW South Western Slopes Bioregion | 2.3 |
| 277 – Native plantings - Blakely's Red Gum – Yellow Box grassy tall woodland of the NSW South Western Slopes Bioregion | 0.26 |
| 277 – Non-native - Blakely's Red Gum – Yellow Box grassy tall woodland of the NSW South Western Slopes Bioregion | 30.5 |
| 5 - River Red Gum herbaceous-grassy very tall open forest wetland on inner floodplains in the lower slopes sub-region of the NSW South- Western Slopes Bioregion and the eastern Riverina Bioregion | 0.04 |
| Total | 34.78 |

TABLE 19: CLEARING LIMITS FOR THREATENED FAUNA SPECIES

| Fauna Species | Area of impact (ha) per CoA E20 |
|------------------------------------------------|------------------------------------|
| Lower Slopes IBRA Subregion | |
| Sloane's Froglet (Crinia sloanei) | 0.03 |
| Squirrel Glider (Petaurus norfolcensis) | 0.16 |
| Superb Parrot (Polytelis swainsonii) | 0.16 |
| Inland Slopes IBRA Subregion | |
| Sloane's Froglet (Crinia sloanei) | 0.23 |
| Key's Matchstick Grasshopper (Keyacris scurra) | 0.21 |
| Squirrel Glider (Petaurus norfolcensis) | 1.82 |
| Superb Parrot (Polytelis swainsonii) | 1.82 |
| Total | 4.43 |

6.1.7 Unexpected Finds Procedure

If during construction activities the project ecologist (or other project personnel) identify a threatened species or threatened ecological community that has not been (or is suspected to have not been) assessed as a part of the Project assessment, or that has been assessed but has been found at a new location, the Unexpected Threatened Species Finds Procedure (Appendix A) will be followed.

6.2 Re-use of woody debris and landscape features

Woody debris and snags (branches, trunks and whole trees that fall into rivers and streams) provide important habitat for aquatic and terrestrial flora and fauna.

In accordance with CoA E37, cleared native vegetation and other landscape features will be reused as part of the Project. If reuse is not practicable, consultation with the relevant council(s), land-care groups and relevant government agencies will be undertaken to determine if hollows, tree trunks, mulch, bush rock, root balls and collected plant material, seeds



and/or propagated plants, can be used by others in habitat enhancement, beneficial re-use and rehabilitation work, before pursuing other disposal options.

Suitable resources for salvage and beneficial reuse including hollows, tree trunks, logs, mulch, bush rock and root balls will be identified within pre-clearing surveys. Within the project, the following re-use would occur where practicable as directed by the project ecologist:

- Large woody debris will be retained for creek crossing works;
- Woody debris may also be used for terrestrial habitat creation;
- Snags removed as part of construction will be returned as close as possible to their original location;
- Coarse woody debris will be relocated within receiving sites determined to be suitable by the project ecologist during pre-clearing surveys.

The re-use of woody debris and snags in waterways would require approval from landowners and DPI Fisheries in the event of snags being proposed in waterways.

6.2.1 Fauna habitat transportation and placement

The transportation and placement of fauna habitat will depend on the amount and size of selected fauna habitat to be relocated. Pre-clearing survey reports will include the description and photographs of identified fauna habitat.

The Martinus Rail Area Manager and/or MR ESM or delegate will ensure the following best-practice methods are undertaken when relocating woody debris, bush rock, and other fauna habitat:

- Removal, stockpiling, transportation, and relocation of woody debris and bush rock will be carried out in a
 manner that minimises disturbance to native vegetation, including the canopy, shrubs, dead trees, fallen timber
 and groundcover species;
- The spread of any weeds or pathogens that may be in the soil will be avoided when relocating woody debris and bush rock from stockpiles;
- An ecologist will be engaged to provide advice on positioning fauna habitats such as woody debris and bush
 rock in designated relocation areas to maximise the likelihood of fauna utilisation;
- Areas of existing native vegetation, including ground cover, will not be cleared, and trees will not be felled to
 place habitat in a wooded area. If habitat cannot be easily placed in an area without clearing trees or shrubbery,
 an alternate recipient site will be sought;
- Topsoil disturbance will be kept to a minimum and will not be heaped up against woody debris and bush rock because of the potential to provide habitat for rabbits;
- Woody debris and bush rock will be placed appropriately for the target species as dictated by the project ecologist.

The re-use of woody debris and other fauna habitat would only be considered where landowner approval is granted.

6.3 Aquatic and riparian habitat

Activities within vegetated riparian zones will be managed to minimise impacts to aquatic and riparian environments as far as practicable. The project must protect the integrity of riparian corridors in accordance with the *Controlled activities – Guidelines for riparian corridors on waterfront land* (DPE 2022) when carrying out work within 40 metres of a watercourse. Additionally, appropriate erosion and sediment control will be installed and maintained in accordance with *Managing Urban Stormwater: Soils and Construction* (Landcom 2004). Aquatic and riparian habitat will be managed during construction in with consideration for the standard precautions and mitigation measures outlined in Section 3.3.2 of the *Policy and Guidelines for Fish Habitat Conservation and Management Update* (DPI, 2013), where relevant.

Works on waterfront land will be carried out in accordance with controlled activity guidelines. Where refuelling is required on waterfront land, an EWMS will be prepared. Where work is required within waterways, an EWMS for the work(s) will be prepared. The EWMS will detail the control measures to avoid or minimise erosion and any adverse impact on water quality and riparian fauna and flora as detailed in Section 6 of the CSWMP. Discharged water quality will be managed in accordance with Section 6.6 of the CSWMP. Clearing within riparian corridors impacted by the project will be undertaken in accordance with the vegetation-clearing process outlined in Section 6.1.

No instream works are permitted to occur in the Murray River or Oddies Creek. There will be no works to the substructure of Murray River bridge.

As per UMM BD12, instream works at Sandy Creek (Uranquinty Yard clearances) and Jeralgambeth Creek (Junee to Illabo clearances) will be undertaken in dry conditions as far as practicable. Where works cannot be conducted in the dry,



appropriate erosion and sediment control will be installed in line with a site specific ESCP (i.e., a silt curtain or sediment boom around the work area and attached to the same side of the bank to maintain fish passage).

As per UMM BD13, any instream habitat features (woody debris, large rocks and boulders) at the temporary creek crossing location at Sandy Creek (Uranquinty Yard clearances) will be removed and placed up or downstream of the construction area in consultation with a suitably qualified aquatic ecologist. Any such aquatic features will be reinstated within the watercourse at the completion of construction.

6.3.1 Permanent and temporary waterway crossings

Martinus Rail will design, construct and maintain temporary waterway crossings consistent with *Managing Urban Stormwater: Soils and Construction* (Landcom, 2004) and maintain fish passage in accordance with DPI Fisheries guideline "Why do Fish Need to Cross the Road? Fish Passage Requirements for Waterway Crossings.

The design of temporary waterway crossings, stream diversions, drainage swales and depressions will be carried out by a suitably qualified and experienced professional in consultation with DPI Fisheries. During the construction of permanent waterway crossings, Martinus Rail will ensure that all reasonable and practicable measures are taken to prevent or minimise environmental harm including:

- Minimising restrictions of fish passage;
- Minimising the release of sediment into the stream;
- Minimising damage to, or the removal of, bank vegetation, particularly vegetation that shades the low-flow channel.

Where practical, construction works across the bed of a waterway should be staged to minimise the total disturbance at any given time and to allow the full bypassing of stream flows around the works to maintain fish passage. Instream structures (bridges and culverts) that provide for the flow of watercourses will be inspected and maintained to address any issues that may contribute to the blockage of fish passage.

6.4 Weed, pest and pathogen control

Weed, pest and pathogen management and control practices will be implemented throughout construction, including weed monitoring, to minimise the risk of spread into and out of the Project and between construction sites during construction of the project. As outlined in the CMP, weed monitoring would be undertaken and noted as part of weekly environmental inspection checklists, which will inform the annual weed monitoring report. Weed monitoring would focus on the weeds detailed in Section 4.2.1.

A pest management contractor will be available at all times and treatment records will be provided to IRPL upon request.

Construction personnel and subcontractors will be inducted in the importance of preventing weeds from entering the Project and the measures that must be taken for vehicles, machinery and plant used on the project.

Washdown bays will be established at designated points along the project and compounds. Washdown bays will contain apparatus to clean vehicles, plant, equipment and footwear. The location of washdown bays will be dependent on the biosecurity risks identified in that location. Water from washdown bays will drain to a contained sump/low point and materials (sediments) from washdown bays will be contained and disposed of in accordance with the Construction Waste, Contamination and Hazardous Materials Management Plan (CWCHMMP).

All vehicles and mobile plant will be inspected on arrival on site or at the construction compounds. If plant or equipment arrives on the project site unclean it will either be washed down at the site compound or be removed from the project site by the supplier/owner and cleaned an appropriate facility. This process would also occur where plant is transferred between enhancement sites.

6.4.1 Biosecurity

The Biosecurity Regulation 2017 (Regulation) includes requirements for the notification of certain weeds, pests and diseases that are found in NSW and could have a severe effect on the economy, environment or community if not managed appropriately.

Weeds that require notification to sell or import into NSW are identified in Schedule 3 of the Regulation.

Pests and diseases that require notification are listed in:

- Schedule 2 of the Act;
- Schedule 1 of the Regulation.





The list of notifiable pests and diseases in the *Biosecurity Act 2015* and *Regulation* is large and they typically require specialist knowledge to identify. The list is not, therefore, repeated within this plan. No notifiable pests or diseases were identified as occurring or likely to occur in the construction impact zone.

As per the A2P CEMF, any movement restrictions (e.g. fire ant zone restrictions) will be assessed prior to undertaking the movement of high-risk material (e.g. soil, gravel, ballast).

Biosecurity incident

A biosecurity incident on the project means the detection of a terrestrial contaminant or terrestrial species on freight, people, plant, or equipment on the Project that was not previously identified in the EAD. In the event of a biosecurity incident that has occurred as a result of construction activities, the process outlined in the CEMP will be implemented. Incident management and response will be undertaken in accordance with the incident reporting procedures detailed within the CEMP.

Several instances require notification in accordance with the *Biosecurity Act 2015* and *Biosecurity Regulation 2017*. These include the requirement to notify a biosecurity event and the requirement to notify a certain pest or disease as outlined above.

6.5 Unexpected threatened species finds

If any threatened species or threatened ecological community are unexpectedly encountered, the Unexpected Threatened Species Finds Procedure (Appendix A) will be implemented.

6.6 Fauna rescue and release procedure

Handling of fauna during the project may be required if fauna is encountered during construction and is required to be relocated or transported to a vet or wildlife carer in the case of injury. Fauna encountered will be managed in accordance with the Fauna Handling and Rescue Procedure (Appendix B) The purpose of the Procedure is to detail the actions to be implemented in the event that fauna (including injured, shocked, dependent juvenile or other) is discovered that requires handling during construction of the project.

6.7 Vegetation rehabilitation

Stage A and B presented little opportunity for permanent rehabilitation works as the end state of Stage A, nor Stage B will not realise the completion of works at any site. Where there is a substantial gap in construction at enhancement sites, erosion and sediment controls will be put in place in accordance with Managing Urban Stormwater: Soils and Construction Vol 1 4th ed. by Landcom, 2004 (The Blue Book). The site stabilisation principles presented in Chapter 7 of the Blue Book would be generally followed to minimise potential erosion and sediment impacts and stabilise the enhancement sites between stages. This may include revegetation of select areas to reduce runoff.

Details of strategies to rehabilitate, regenerate or revegetate disturbed areas will be provided in the Stage 2 Urban Design and Landscape Plan for the Project. This will be based on the Inland Rail Landscape and Rehabilitation Strategy, the Inland Rail Landscape and Rehabilitation Framework and property-specific reinstatement commitments. In accordance with CoA E36 seeds from native plants to be removed will be collected before clearing ideally during spring through to mid-summer and used in revegetation and rehabilitation across the project area. This will be undertaken as part of the pre-clearing survey detailed in Section 6.1.1. Plant propagation must ensure that native species of local provenance from the relevant native vegetation community are available for successful revegetation and landscaping.

In accordance with CoA E34 and UMM BD12, riparian land and watercourses disturbed during construction will be rehabilitated and revegetated with native species of local provenance from the relevant native vegetation community on completion of Work impacting the riparian land in accordance with the *Controlled activities – Guidelines for riparian corridors on waterfront land* (DPE 2022) and *A Rehabilitation Manual of Australian Streams* (Rutherfurd et al. 2000);

As per UMM BD8 and BD9, riparian areas subject to disturbance will be progressively stabilised and rehabilitated and aquatic habitat will be returned to pre-works condition (or better) in accordance with the rehabilitation strategy.

Resources that may be available within the enhancement sites will be identified for salvage where possible per Section 6.1. This includes vegetative and soil resources which may be reused beneficially during the rehabilitation and restoration of the site. Seed collection would ideally take place from Spring through to mid-Summer.

Rehabilitation, reinstatement and stabilisation areas will be monitored for their performance against SMART objectives in accordance with the Monitoring Plan in Appendix G.



6.8 Biodiversity offsets

As required by CoA E20 and E21, biodiversity offsets have been made in the form of the retirement of ecosystem and species credits. These offsets are documented separately in the BAM Biodiversity Credit Report which forms part of Revision M of the Biodiversity Development Assessment Report, which is included in the PIR as Revised Technical Paper 8: Biodiversity Development Assessment Report (WSP, October 2023).

In accordance with CoA E23, the retirement of the credits has been carried out in accordance with the BC Act prior to impact. Evidence of the retirement of credits in satisfaction of CoA E24 has been provided to the Planning Secretary prior to impacts to the biodiversity values.

6.9 Sloane's Froglet Surveys

Sloane's Froglet was listed as having the potential to occur within the Project site in Appendix D2.8 of the Revised BDAR. As seasonal survey timeframes could not be met prior to the publishing of the EIS, the species was assumed present in areas where suitable habitat values were present.

Per CoA E25 targeted surveys were undertaken by NGH during July and/or August 2024 for Sloane's Froglet in all areas where that species was assumed present. The Methods and Results report for these surveys is attached as Appendix D of this CBMP. The survey effort was completed in accordance with CoA E25 and with consideration for the NSW Survey Guide for Threatened Frogs (DPIE, 2020). The target species, Sloane's Froglet (*Crinia sloanei*), was not detected aurally or visually at any site. The survey report noted that based on the results, a Sloane's Froglet Management Plan is not required as the species does not occur in the project area. Condition E25 of the CoA has been satisfied and there is no further survey work required for Sloane's Froglet to fulfill this condition.

The survey report was issued to DCCEEW and the Planning Secretary for information and forwarded to CPHR. CPHR provided feedback stating that the survey method was 'generally adequate to confirm species absence', however noted that 'Sloane's Froglet (*Crinia sloanei*) can be difficult to distinguish from other *Crinia* species when there are multiple species and large numbers of frogs calling' and that additional measures were not taken to confirm species absence at the Billy Hughes Bridge enhancement site. As such, CPHR provided a written recommendation to DPHI that a precautionary approach be applied at the Billy Hughes bridge enhancement site and that a site-specific Sloane's Froglet Management Plan be implemented in accordance with CoA E26 in their letter dated 27 November 2024 and titled 'Inland Rail – Albury to Illabo (SSI-10055), Sloane's Froglet survey results'. This approach was supported by DPHI as per the letter dated 3 December 2024, which states 'The Department supports the advice of CPHR recommending a Sloane's Froglet Management Plan is implemented for construction works at the Billy Hughes bridge site as required by Condition E26'.

As per CoA E26, the site-specific Sloane's Froglet Management Plan for the Billy Hughes bridge enhancement site would be implemented prior to the commencement of construction in areas identified as a precaution in the southern end of the enhancement site. Refer to Appendix C for mapping of predicted breeding habitat for Sloane's Froglet within the southern drainage line at the Billy Hughes bridge enhancement site. Site-specific management plans are not required for any other enhancement sites.

6.10 Fauna Connectivity Strategy

The Fauna Connectivity Strategy required by CoA E31 for Stage B and Stage C works at the Billy Hughes bridge and Uranquinty Yard enhancement sites is being prepared independently of this CBMP and will be prepared in accordance with CoA E29, E30 and E32.

Mitigation measures will be implemented to address impacts on habitat connectivity. Movement corridors at the Billy Hughes bridge and Uranquinty Yard enhancement sites have been identified as potential locations suitable for connectivity measures. During the development of this CBMP, CPHR confirmed that glider poles are not required Oddies Creek or Murray River bridge due to the isolated nature of these locations.

Specific design and location details of connectivity measures will be provided in the Fauna Connectivity Strategy and Stage 2 of the Urban Design and Landscape Plan for the Project.

6.11 Management and mitigation measures

A range of environmental requirements and management measures are identified in the EAD and CoA. Specific measures and requirements to address biodiversity impacts are outlined in Table 20. The following mitigation measures have been developed with consideration of SMART (specific, measurable, achievable, relevant and time-based) principles.





TABLE 20: BIODIVERSITY MANAGEMENT AND MITIGATION MEASURES

| ID | MANAGEMENT MEASURE | LOCATION | WHEN TO IMPLEMENT | RESPONSIBILITY FOR IMPLEMENTATION | REFERENCE OR SOURCE | EVIDENCE OF IMPLEMENTATION |
|---------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------------------------------------------|----------------------------------------------|------------------------|---------------------------------------------------------------------------------------------------|
| General | | | | | | |
| CB-01 | Training will be provided to all project personnel, including relevant sub-contractors on biodiversity management practices and the requirements from this Plan through inductions, toolbox talks and activity-specific training. | All | Pre-construction | MR ESM | Good Practice | Toolbox Talks Project Induction Training Records |
| CB-02 | Construction workforce will be supplied with sensitive area maps (showing clearing boundaries and exclusion zones), including updates as required. | All | Pre- Construction Construction | MR ESM | UMM BD7 A2P CEMF | Sensitive Area Plans |
| CB-03 | All personnel must drive to the conditions, speed limits and road rules. Any fauna strikes must be reported to IRPL as soon as possible. | All | Pre- Construction Construction | MR ESM MR Safety Manager All personnel | Good Practice | Fauna Handling Record Sheet |
| CB-04 | Should changes to the project's design or construction methodology or additional field surveys result in increased impacts to biodiversity that have not been included in the Revised BDAR, these will be assessed by a suitably qualified ecologist. | All | Detailed Design Pre-Construction Construction | MR ESM Project ecologist | Good practice | Additional biodiversity assessment if required |
| CB-05 | Detailed design and construction planning will identify refinements that further avoid or minimise the need to further impact or disturb native vegetation, fauna habitat and riparian habitat. | All | Detailed Design Pre-Construction Construction | MR ESM MR Design Manager | UMM BD1 | Detailed Design Reports Environmental Work Method Statements Construction Work Methods Statements |



| ID | MANAGEMENT MEASURE | LOCATION | WHEN TO IMPLEMENT | RESPONSIBILITY FOR IMPLEMENTATION | REFERENCE OR SOURCE | EVIDENCE OF IMPLEMENTATION |
|-------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|----------------------------------|----------------------------------------------------------------------------------|---------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------|
| CB-06 | Impacts to plant community types and threatened species habitat must not exceed the impacts identified in CoA E20. Prior to impacts on the biodiversity values of the CSSI, the number and classes of ecosystem credits and species credits (like-for-like) as set out in the BAM Biodiversity Credit Report in Revision M of the Biodiversity Development Assessment Report, which is included in the PIR as Revised Technical Paper 8: Biodiversity Development Assessment Report (WSP, October 2023), will be retired in accordance with the BC Act. Evidence of retirement be provided to DPHI prior to impact. | All | Pre-Construction Construction | MR ESM MR Design Manager MR Project Manager MR Site Supervisor MR Engineers IRPL | CoA E20 CoA E21 CoA E25 CoA E26 | Detailed Design Reports Post-clearing Report Project Clearing Register Retirement Evidence per CoA E24 |
| CB-07 | Works within the Tree Protection Zones of retained trees within or immediately adjacent to the disturbance area will be planned with consideration of the tree protection measures outlined in managed in accordance with AS4970–2009 Protection of Trees on Development Sites. Where practicable, appropriate measures will be implemented to minimise the impact of the works on the long–term health of these trees. | All | Pre-Construction Construction | MR ESM MR Site Supervisor MR Engineers | Good Practice AS4970–2009 Protection of Trees on Development Sites. | Weekly Environmental Inspection Checklist Sensitive Area Plans Environmental Work Method Statements Construction Work Methods Statements |
| CB-08 | The project disturbance footprint/construction impact zone to be delineated by a surveyor before works commence. | All | Pre-Construction | MR ESM MR Site Supervisor MR Engineers | Good Practice | Project disturbance footprint survey/GIS layer |
| CB-09 | The project's fauna handling and rescue procedure would be implemented for: All activities conducted by site personnel (including sub-contractors) that have the potential to encounter fauna that will need to be relocated or removed from site; and Vegetation clearing and land disturbance. | All | Pre-Construction Construction | MR ESM Project ecologist | Good Practice | Fauna Handling Record Sheet |



| ID | MANAGEMENT MEASURE | LOCATION | WHEN TO IMPLEMENT | RESPONSIBILITY FOR IMPLEMENTATION | REFERENCE OR SOURCE | EVIDENCE OF IMPLEMENTATION |
|---------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------------------------------------------|-----------------------------------------------------------------------------|-------------------------|-------------------------------------------------------------------------------------------------------------------------------|
| | Handling of fauna may be necessary for fauna to be relocated or, if injured, taken to a vet or wildlife carer. | | | | | |
| | A wildlife licence and/or scientific licence must be held by any staff handling fauna and should be undertaken either by the Project Ecologist or a person skilled in handling the species of fauna encountered. | | | | | |
| Pre-cle | aring and clearing | | | | | |
| CB-10 | The clearing of native vegetation will be minimised to the greatest extent practicable with the objective of reducing impacts to threatened ecological communities, threatened species and their habitat. Indicative clearing extents will be provided to IRPL at least 80 days prior to clearing. | All | Detailed Design Pre-Construction Construction | MR ESM MR Design Manager MR Project Manager MR Site Supervisor MR Engineers | CoA E19 | Detailed Design Reports Pre-clearing Survey Reports Environmental Work Method Statements Construction Work Methods Statements |
| CB-11 | Pre-clearance surveys will be carried out prior to construction by a suitability qualified ecologist. This would include but not be limited to: Inspections of artificial and natural structures that provide potential microbat habitat. If bats are identified roosting in these structures, individuals will be excluded from this habitat (meaning bats can exit the habitat unharmed during their nocturnal activity period but not re-enter); Visual identification and mapping of potential and confirmed Superb Parrot nest trees within the construction impact zone and visible surrounding areas. If identified, mitigation measures are to be considered in consultation with the project ecologist where works are proposed to occur | All | Pre-Construction Construction | MR ESM Project ecologist | UMM BD5 Revised BDAR | Pre-clearing Survey Reports Fauna Handling Record Sheet |



| ID | MANAGEMENT MEASURE | LOCATION | WHEN TO IMPLEMENT | RESPONSIBILITY FOR IMPLEMENTATION | REFERENCE OR SOURCE | EVIDENCE OF IMPLEMENTATION |
|-------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|----------------------------------|-----------------------------------|------------------------|------------------------------------------------------------------|
| | during breeding season (September to November); Native aquatic fauna salvage in watercourses of | | | | | |
| | residual pools directly impacted by construction, including but not limited to Sloane's Froglet mapped habitat areas. All salvaged aquatic fauna will be relocated to similar habitat nearby; | | | | | |
| | Pre-clearance disturbance survey including mapping of weeds and development of suitable controls to manage them | | | | | |
| | Verification that the area to be cleared is correct and within the boundary and GIS data provided to IRPL. | | | | | |
| CB-12 | The project ecologist must be onsite to supervise the clearing works during two stage clearing and in areas of known and assumed present threatened species habitat (i.e. species polygons). They will: | All | Pre-Construction Construction | MR ESM Project ecologist | Good practice | Pre-clearing Survey Reports Fauna Handling Record Sheet |
| | Thoroughly inspect all hollows that are accessible from the ground immediately before clearing; | | | | | Post-clearing report |
| | Carefully determine the appropriate felling methodology and supervise the removal of habitat features and hollows when trees are dropped to the ground; | | | | | |
| | Ensure detected fauna are encouraged to self- relocate or capture and relocate any encountered fauna to pre-identified release sites; | | | | | |
| | Ensure that any injured wildlife is transported to a veterinarian or wildlife carer; | | | | | |
| | Where breeding fauna or dependent young are detected during the clearing works, consult with a licensed carer to determine whether the animal/s | | | | | |



| ID | MANAGEMENT MEASURE | LOCATION | WHEN TO IMPLEMENT | RESPONSIBILITY FOR IMPLEMENTATION | REFERENCE OR SOURCE | EVIDENCE OF IMPLEMENTATION |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------|-----------------------------------------------------|-----------------------------------------------------------------------------|------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | require ongoing care or can be safely relocated to an adjacent habitat. | | | | | |
| | Locations of fauna release (including GPS coordinates) will be recorded in a post-clearing report. Once all fauna habitat inspections and any required fauna removal are complete, the remaining vegetation clearing will commence. | | | | | |
| CB-13 | At the completion of clearing, the project ecologist will prepare a Post-Clearing Report. | All | Pre-Construction Construction | MR ESM Project ecologist | Good practice | Post-clearing report |
| Exclusi | on zones | | | | | |
| CB-14 | Exclusion areas will be established and maintained around native vegetation and riparian vegetation identified for retention and protection, particularly areas of biodiversity value adjoining the project site that are located in close proximity to work areas and identified on the Sensitive Area Maps for consideration. | All | Pre-Construction Construction | MR ESM Project ecologist MR Site Supervisor MR Engineers | UMM BD6 | Weekly Environmental Inspection Checklist Sensitive Area Plans Pre-clearing Survey Report Environmental Work Method Statements Construction Work Methods Statements |
| CB-15 | No works to the substructure of the Murray River bridge or instream works in the Murray River or Oddies Creek will be undertaken. | Murray River bridge (Murray River and Oddies Creek) | Detailed Design Pre-Construction Construction | MR ESM MR Design Manager MR Project Manager MR Site Supervisor MR Engineers | CoA E33 | Detailed Design Reports Weekly Environmental Inspection Checklist Sensitive Area Plans Environmental Work Method Statements Construction Work Methods Statements |



| ID | MANAGEMENT MEASURE | LOCATION | WHEN TO IMPLEMENT | RESPONSIBILITY FOR IMPLEMENTATION | REFERENCE OR SOURCE | EVIDENCE OF IMPLEMENTATION | | |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------|-----------------------------------------------|-----------------------------------------------------------------------------|------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|
| Threate | hreatened species management | | | | | | | |
| CB-16 | A species Unexpected Finds Protocol will be implemented if TECs, flora and fauna species, not assessed in the biodiversity assessment, are identified in the project site and will include stop work orders in the immediate area and notifying the DPHI. | All | Pre-construction Construction | MR ESM MR Site Supervisor MR Engineers | UMM BD14 | Unexpected Finds Protocol | | |
| CB-17 | During heavy rainfall events, wet areas such as drainage lines will be avoided and movement of machinery be restricted where practicable. | Billy Hughes Bridge | Construction | MR ESM Project ecologist MR Site Supervisor | Consultation with CPHR | Sloane's Froglet Management Plan Weekly Environmental Inspection Checklist Monitoring Reports | | |
| CB-18 | Temporary frog exclusion fencing will be considered where construction compounds/laydown areas occur adjacent to mapped potential Sloane's froglet breeding habitat. [Feedback received during the preparation of the Stage A and Stage B CBMP identified that frog fencing is not recommended by CPHR as a mitigation for Sloane's Froglet.] | Areas adjacent to Sloanes Froglet habitat. | Detailed Design Pre-Construction Construction | MR ESM Project ecologist MR Site Supervisor MR Engineers | UMM BD9 | Weekly Environmental Inspection Checklist Sensitive Area Plans Temporary Work Designs Environmental Work Method Statements Construction Work Methods Statements | | |
| CB-19 | If potential or actual impacts to any threatened communities or species not listed in Condition E20 are discovered, all work that may impact the identified species or community must stop to prevent further impact. The Planning Secretary and DCCEEW (NSW) (and DCCEEW (Cth) where relevant) will be notified in writing. Work will not recommence until the relevant | All | Detailed Design Pre-Construction Construction | MR ESM Project ecologist MR Project Manager MR Site Supervisor MR Engineers | CoA E22 | Communications with the Planning Secretary and DCCEEW (NSW) (and DCCEEW (Cth) where relevant). Monitoring Reports | | |



| ID | MANAGEMENT MEASURE | LOCATION | WHEN TO IMPLEMENT | RESPONSIBILITY FOR IMPLEMENTATION | REFERENCE OR SOURCE | EVIDENCE OF IMPLEMENTATION |
|---------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------|---------------------------------------------------|----------------------------------------------------------|------------------------|--------------------------------------------------------------------------------------------------------------------|
| | agencies have been consulted and any required approvals have been obtained. | | | | | |
| CB-20 | In all remaining areas that assumed the presence of Sloane's Froglet (<i>Crinia sloanei</i>), erosion and sediment control measures and protection of riparian areas must be installed in accordance with Conditions C10, E173, and E174 prior to work in these area. | Identified Sloanes Froglet habitat. | Stage B / C Pre- Construction/ Construction | MR ESM Project ecologist MR Site Supervisor MR Engineers | CoA E28 | CSWMP Sensitive Area Plans Erosion and Sediment Control Plans Weekly Environmental Inspection Checklist |
| CB-21 | Where existing fauna fencing is identified, it will be retained where it does not impact construction of the Project. | All | Construction | MR ESM MR Site Supervisor MR Engineers | Good practice | Weekly Environmental Inspection Checklist Toolbox Talks Project Induction Training Records |
| Habitat | retention | | | | | |
| CB-22 | Seed from native plants to be removed will be collected before clearing and used in revegetation and rehabilitation across the project area. Plant propagation must ensure that native species of local provenance from the relevant native vegetation community are available for successful revegetation and landscaping. | All areas where seed can be collected. | Pre-Construction/ Construction | MR ESM Project ecologist | CoA E36 | Pre-clearing Survey Reports Post-clearing report |
| CB-23 | Cleared native vegetation and other landscape features will be reused. If reuse is not practicable, consultation with the relevant council(s), land-care groups and relevant government agencies will be undertaken to determine if hollows, tree trunks, mulch, bush rock, root balls, collected plant material, seeds and/or propagated plants, can be used by others in | All | Stage B / C Construction | MR ESM Project ecologist | CoA E37 | Pre-clearing Survey Reports Post-clearing report Communications with the relevant council(s), land-care groups and |



| ID | MANAGEMENT MEASURE | LOCATION | WHEN TO IMPLEMENT | RESPONSIBILITY FOR IMPLEMENTATION | REFERENCE OR SOURCE | EVIDENCE OF IMPLEMENTATION |
|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|----------------------------------|----------------------------------------------------------------------------|------------------------|--------------------------------------------------------------------------------------------------------------------------|
| | habitat enhancement, beneficial re-use and rehabilitation work, before pursuing other disposal options. | | | | | relevant government agencies where relevant). |
| CB-24 | Riparian land and watercourses disturbed during construction will be rehabilitated and revegetated with native species of local provenance from the relevant native vegetation community on completion of Work impacting the riparian land in accordance with the Controlled activities – Guidelines for riparian corridors on waterfront land (DPE 2022) and A Rehabilitation Manual of Australian Streams (Rutherfurd et al. 2000). | All | Stage B / C Construction | MR ESM MR Design Manager Project ecologist MR Site Supervisor MR Engineers | CoA E34 | Pre-clearing Survey Reports Post-clearing reports |
| Lighting | | | | | | |
| CB-25 | Where works are undertaken at night, direction lighting will be used and directed away from vegetated areas where practicable. | All | Detailed Design Construction | MR ESM Project ecologist MR Site Supervisor MR Engineers | Good Practice | Weekly Environmental Inspection Checklists Temporary Lighting Designs Construction Work Method Statements |
| Soil and | d water quality | | | | | |
| CB-26 | Before undertaking any work and during maintenance or construction activities, erosion and sediment controls will be implemented and maintained to prevent water pollution consistent with Managing Urban Stormwater: Soils and Construction Vol 1 4th ed. by Landcom, 2004 (The Blue Book). | All | Pre-Construction Construction | MR ESM MR Site Supervisor MR Engineers | CoA E174 | CSWMP Erosion and Sediment Control Plans Weekly Environmental Inspection Checklist |



| ID | MANAGEMENT MEASURE | LOCATION | WHEN TO IMPLEMENT | RESPONSIBILITY FOR IMPLEMENTATION | REFERENCE OR SOURCE | EVIDENCE OF IMPLEMENTATION |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|----------------------------------|---------------------------------------------------|----------------------------------------------------------------|------------------------------------------------------------------------------------|
| CB-27 | Soil and water quality management measures will be implemented in accordance with the Soil and Water Management Plan to minimise erosion during clearing. | All | Pre-Construction Construction | MR ESM MR Site Supervisor MR Engineers | Good Practice | CSWMP Erosion and Sediment Control Plans Weekly Environmental Inspection Checklist |
| Biosecu | urity | | | | | |
| CB-28 | Where weeds are present in locations that are accessed for construction activities, they will be managed in consultation with the relevant landholder. Consultation would also occur with the relevant authority (LLS Local Land Services, the relevant local council, or NSW DPI) in relation to notifiable weeds. | All | Pre-Construction Construction | MR ESM Project ecologist MR Site Supervisor | Good Practice Biosecurity Regulation 2017 Biosecurity Act 2015 | Weed Monitoring Report Weekly Environmental Inspection Checklists |
| CB-29 | A pest management contractor will be available at all times and treatment records will be provided to IRPL upon request. In the event of new infestations of notifiable weeds as a result of construction activities, the relevant control authority will be notified as per the <i>Biosecurity Act</i> 2015 and Biosecurity Regulation 2017. | All | Construction | MR ESM Project ecologist MR Site Supervisor | Good Practice Biosecurity Regulation 2017 Biosecurity Act 2015 | Weed Monitoring Report Weekly Environmental Inspection Checklists |



| ID | MANAGEMENT MEASURE | LOCATION | WHEN TO IMPLEMENT | RESPONSIBILITY FOR IMPLEMENTATION | REFERENCE OR SOURCE | EVIDENCE OF IMPLEMENTATION | |
|--------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------|---------------------------------|----------------------------------------------------------|-------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|
| Workin | Vorking in waterways and on waterfront land | | | | | | |
| CB-30 | Refuelling will be conducted outside of waterfront land, 50m or more from a watercourse and not within long grass during the summer months. Spill kits will be kept with maintenance vehicles and or machinery within 100 metres of a watercourse. | All | Construction | MR Site Supervisor | UMM BD15 Junee Council consultation | Weekly Environmental Inspection Checklist Sensitive Area Plans Temporary Work Designs Environmental Work Method Statements Construction Work Methods Statements | |
| CB-31 | Fish passage will be maintained at Jeralgambeth Creek (Junee to Illabo clearances) during construction. | Junee to Illabo clearances | Construction | MR ESM MR Design Manager | UMM BD4 | Weekly Environmental Inspection Checklist Temporary Work Designs Environmental Work Method Statements Construction Work Methods Statements | |
| CB-32 | Activities within vegetated riparian zones will be managed to minimise impacts to aquatic environments as far as practicable. Riparian areas subject to disturbance will be progressively stabilised and rehabilitated. | All | Detailed Design Construction | MR ESM MR Design Manager MR Site Supervisor MR Engineers | UMM BD8 | Detailed Design Reports Weekly Environmental Inspection Checklist Environmental Work Method Statements Construction Work Methods Statements Landscape Design Reports | |



| ID | MANAGEMENT MEASURE | LOCATION | WHEN TO IMPLEMENT | RESPONSIBILITY FOR IMPLEMENTATION | REFERENCE OR SOURCE | EVIDENCE OF IMPLEMENTATION |
|-------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------|---------------------------------|----------------------------------------------------------|------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| CB-33 | Instream works at Sandy Creek (Uranquinty Yard clearances) and Jeralgambeth Creek (Junee to Illabo clearances) will be undertaken in dry conditions as far as practicable. Where works cannot be conducted in the dry, appropriate erosion and sediment control will be installed (i.e. a silt curtain or sediment boom around the work area and attached to the same side of the bank to maintain fish passage). Appropriate erosion and sediment control will be installed and maintained. Aquatic habitat will be returned to pre-works condition. | Uranquinty Yard clearances Junee to Illabo clearances | Detailed Design Construction | MR ESM MR Site Supervisor MR Engineers | UMM BD12 | Weekly Environmental Inspection Checklist CSWMP Erosion and Sediment Control Plans Environmental Work Method Statements Construction Work Methods Statements Landscape Design Reports |
| CB-34 | Instream structures (bridges and culverts) that provide for the flow of watercourses will be inspected and maintained to address any issues that may contribute to the blockage of fish passage. | All | Construction | MR ESM MR Site Supervisor MR Engineers | UMM BD16 | Weekly Environmental Inspection Checklist |
| CB-35 | When carrying out work within 40 metres of a watercourse the integrity of riparian corridors would be protected in accordance with the Controlled activities – Guidelines for riparian corridors on waterfront land (DPE 2022). | All | Detailed Design Construction | MR ESM MR Design Manager MR Site Supervisor MR Engineers | CoA E173 | Detailed Design Reports Weekly Environmental Inspection Checklist Environmental Work Method Statements Construction Work Methods Statements Landscape Design Reports |

CONSTRUCTION BIODIVERSITY MANAGEMENT PLAN - STAGE C



| ID | MANAGEMENT MEASURE | LOCATION | WHEN TO IMPLEMENT | RESPONSIBILITY FOR IMPLEMENTATION | REFERENCE OR SOURCE | EVIDENCE OF IMPLEMENTATION |
|------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------|----------------------------------|-----------------------------------|------------------------|-----------------------------------------------------------------------------------------------------------|
| Monitoring | | | | | | |
| CB-36 | Clearing of native vegetation will be monitored to confirm actual impacts to biodiversity values to inform any final biodiversity offset requirements. | All | Construction | MR ESM Project ecologist | Good Practice | Project Clearing Register |
| CB-37 | Biodiversity monitoring will be undertaken in accordance with the Biodiversity Monitoring Program detailed in Section 7.3. | All | Pre-construction Construction | MR ESM Project ecologist | CoA C26 | Monitoring Reports |
| CB-38 | Biodiversity monitoring will include a weekly inspection regime to monitor potential impacts to water quality and monthly inspections supervised by a suitably qualified ecologist to review environmental controls in locations where Sloane's Froglet may be located (such as the southern drainage line). | Billy Hughes Bridge | Construction | MR ESM Project Ecologist | Consultation with CPHR | Sloane's Froglet Management Plan Weekly Environmental Inspection Checklist Monitoring Reports |



7 COMPLIANCE MANAGEMENT

7.1 Roles and responsibilities

The project's organisational structure and overall roles and responsibilities are outlined in the CEMP. Specific responsibilities for the implementation of environmental controls are detailed in Table 20 of this CBMP.

7.2 Training

To ensure that this Plan is effectively implemented, all site personnel (including sub-contractors) will undergo site induction training that includes construction biodiversity management issues prior to construction commencing. The induction training will address elements related to biodiversity management including:

- Existence and requirements of this Plan;
- Relevant legislation, regulations and conditions (where applicable);
- Existence of the SAPs;
- Clearing procedures;
- Exclusion zones;
- Threatened species within the project area;
- Unexpected finds procedures for threatened species; and
- Biosecurity and weeds procedures.

Targeted training in the form of toolbox talks or specific training will also be provided to personnel with a key role in biodiversity management or those undertaking an activity with a high risk of environmental impact.

Daily pre-start meetings conducted by the Martinus Rail Foreman/Site Supervisor will inform the site workforce of any environmental issues relevant to biodiversity that could potentially be impacted by, or impact on, the day's activities.

Further details regarding staff induction and training are outlined in the CEMP.

7.3 Monitoring

The Construction Biodiversity Monitoring Program will be prepared in consultation with the relevant identified government agency (CPHR) and reviewed by the Project ecologist in order to compare the actual performance of construction against the predicted performance. This process will be used to inform the requirement for any additional mitigation measures or preventative corrective actions, which may be captured as part of an update to this CBMP, if required. The Construction Biodiversity Monitoring Program is provided in Appendix G.

7.4 Inspections

Regular inspections of sensitive areas and activities will occur for the duration of the project. The project will carry out weekly site inspections. Weekly and other routine inspections by the ER will occur throughout construction. Details on the nature and frequency of these inspections are documented in the CEMP.

The inspections will check the implementation and effectiveness of the management measures identified in Section 6 and the environmental performance of the project relevant to biodiversity. Visual monitoring of delineated/fenced disturbance boundaries will be undertaken.

7.5 Auditing

Audits (both internal and external) will be undertaken to assess the effectiveness of biodiversity management measures, compliance with this Plan, conditions of approval and other relevant approvals, licenses and guidelines. Audit requirements are detailed in Section 9 of the CEMP.

7.6 Reporting and identified records

Reporting requirements and responsibilities are documented in Section 10.2 of the CEMP and Sections 1.5 and 4.1 of the Monitoring Program in Appendix G.

Additionally, in the event of an incident or non-compliance, the Planning Secretary will be notified in writing of the findings of the review conducted by the project relating to the incident or non-compliance.

A2I | ALBURY TO ILLABO





The project will maintain accurate records substantiating all construction activities associated with the project or relevant to the conditions of approval, including measures taken to implement this Plan.

Records will be made available to the Planning Secretary upon request, within the timeframe nominated in the request.



8 REVIEW AND IMPROVEMENT

8.1 Continuous improvement

Continuous improvement of this Plan will be achieved by the ongoing evaluation of environmental management performance against environmental policies, objectives and targets to identify opportunities for improvement.

Issues requiring management during construction (including cumulative impacts), as identified through ongoing environmental risk analysis, will be managed through SMART principles.

The continuous improvement process will be designed to:

- Identify areas of opportunity for improvement of environmental management and performance;
- Identify environmental risks not already included in the risk register;
- Determine the cause or causes of non-conformances and deficiencies;
- Develop and implement a plan of corrective and preventative action to address any non-conformances and deficiencies;
- Verify the effectiveness of the corrective and preventative actions;
- Document any changes in procedures resulting from process improvement;
- Make comparisons with objectives and targets.

Martinus Rail will be responsible for ensuring that project environmental risks are identified and included in the risk register and that appropriate mitigation measures are implemented throughout the construction of the project, as part of the continuous improvement process as outlined in Section 6 of the CEMP.

8.2 Update and amendment

The processes described in Section 10 of the CEMP may result in the need to update or revise this Plan.

Any revisions to this Plan will be in accordance with the process outlined in Section 10.4 of the CEMP and reviewed and approved as described in Section 3.3.1 of the CEMP. A copy of the updated Plan and changes will be distributed to all relevant stakeholders in accordance with the approved document control procedure.






APPENDICES





APPENDIX A

Unexpected Threatened Species Finds Procedure









APPENDIX B

Fauna Handling and Rescue Procedure









Document Control

| DOCUMENT TITLE: | Fauna Handling and Rescue Procedure – Stage C | | | |
|-----------------|--------------------------------------------------------------------|--|---------------------------------|--------------|
| DOCUMENT OWNER: | Chris Standing – Environment, Approvals and Sustainability Manager | | | |
| PREPARED BY: | Steven Dando TITLE: E | | Environmental Approvals Advisor | |
| SIGNATURE: | S.Dando | | DATE: | 23/09/2025 |
| REVIEWED BY: | Alison Kriegel TITLE: | | Environmental Approvals Lead | |
| SIGNATURE: | aism Kingel | | DATE: | 23/09/252025 |

Approved by

| NAME | TITLE | SIGNATURE | DATE |
|---------------|------------------|-----------|------------|
| Andy Williams | Project Director | AME | 23/09/2025 |

Revision History

| REVISION | REVISION DATE | AMENDMENT | DATE TO CLIENT |
|----------|---------------|------------------------------|----------------|
| А | 17/09/2025 | Prepared to consider Stage C | 17/09/2025 |
| 0 | 23/09/2025 | For ER approval | 23/09/2025 |

Disclaimer: This document has been prepared by Martinus. Use of this document shall be subject to the terms of the relevant contract with Martinus. The electronic file of this current revision is the controlled copy. This file is stored on Martinus' server located at Head Office, Unit 1, 23-27 Waratah St, Kirrawee, NSW.

This document is the property of and contains proprietary information owned by Martinus. No permission is granted to publish, reproduce, transmit or disclose to another party, any information contained in this document, in whole or in part, without prior written permission from the issuing authority.

For the purpose of this document, Martinus refers to the Martinus Group of companies.

This document is uncontrolled when printed.



TABLE OF CONTENTS

| 1 | INTRODUCTION | 3 |
|-----|---------------------------------------------|------|
| 1.1 | INTRODUCTIONInduction and training | 3 |
| 1.2 | Scope | 3 |
| 1.3 | Permits and Licences | 3 |
| 2 | GENERAL FAUNA HANDLING AND RESCUE PROCEDURE | 4 |
| 3 | SPECIFIC HANDLING REQUIREMENTS | 6 |
| 3.1 | Birds | |
| 3.2 | Small ground-dwelling mammals | 6 |
| 3.3 | Large ground-dwelling mammals | 6 |
| 3.4 | Arboreal mammals | 6 |
| 3.5 | Reptiles | 7 |
| 3.6 | Amphibians | 7 |
| 3.7 | Other mammals: Bats | 7 |
| 4 | EUTHANASIA | 8 |
| 4.1 | When to euthanise | |
| 4.2 | Euthanasia methods | 8 |
| 5 | CONTACT DETAILS | 9 |
| 6 | INCIDENT REPORTING PROTOCOL | . 10 |



1 INTRODUCTION

This Fauna Handling and Rescue Procedure (this Procedure) forms part of the Construction Biodiversity Management Plan (CBMP) prepared for the Albury to Illabo Inland Rail project and forms part of the overall environmental management framework for the project.

This Procedure applies to the handling of any fauna encountered during construction if required.

1.1 Induction and training

All Project personnel are to be inducted on the existence of this Procedure during the Project Induction and in more detail as required in Site Inductions and regular Toolbox Talks. Records of all training, including inductions, will be maintained. Records will include the name and role of the attendee, the date of training/induction as well as the name of the course.

1.2 Scope

This procedure is applicable for the following:

- All activities conducted by site personnel (including sub-contractors) that have the potential to encounter fauna that will need to be relocated or removed from site and;
- Vegetation clearing and land disturbance.

Handling of fauna may be necessary for fauna to be relocated or, if injured, taken to a vet or wildlife carer. A wildlife licence and/or scientific licence must be held by any staff handling fauna and should be undertaken either by the project ecologist or a person skilled in handling the species of fauna encountered.

Should any threatened species be identified, the Unexpected Threatened Species Finds Procedure (Appendix A of the CBMP) will be implemented.

1.3 Permits and Licences

A Scientific Licence under Part 2 of the *Biodiversity Conservation Act 2016* (BC Act) (including Animal Ethics Approval under the Animal Research Act 1985) is required for fauna handling/rescue and survey work. Where rescued fauna requires rehabilitation and care, only wildlife rehabilitation organisations authorised under Part 2 of the BC Act may be used. A wildlife licence and/or scientific licence must be held by any staff handling fauna.



2 GENERAL FAUNA HANDLING AND RESCUE PROCEDURE

This Procedure will be implemented only if intervention is necessary (i.e. where fauna is injured or otherwise unable to leave the site without intervention), or to minimise stress to native fauna and/ or remove the risk of further injury.

Fauna may be encountered in a variety of situations during delivery of the project. During staged clearing activities, any fauna handling will be carried out by the Project Ecologist or a trained fauna handler. During other construction activities or non-staged clearing (when the Project Ecologist or fauna handler may not be present on site), fauna may require handling by other Project personnel. Wherever possible, the Project Ecologist or trained fauna handler will be used.

Due to the remoteness and large distances between work sites, there may be times when the Project Ecologist or fauna handler is not present on-site, and it is more important to move the fauna from danger or harm. In these circumstances, Martinus Rail personnel may be required to handle the fauna (i.e. where that movement removes the fauna from danger or harm). Appropriate animal handling gear, as described below and in Section 3, should be kept at the site offices and in site vehicles where possible.

The Project must contact local veterinary clinics and/or wildlife carers at least seven days in advance of clearing works commencement to confirm their willingness to treat injured wildlife and advise them of the upcoming clearing schedule.

If wildlife (including aquatic) is discovered on the project site during construction activities that may harm the animal or pose a risk to site personnel, the following steps will be taken:

- 1. Stop all work in the vicinity of the fauna, turn off all machinery, and immediately notify the Foreman who is then to notify the Environment Manager. The Environment Manager is then to immediately notify the Project Ecologist to discuss the best course of action, e.g. if the animal is injured then take it to a wildlife rescue organisation or the closest Veterinary clinic;
- 2. Preferably allow fauna to leave the area without intervention if it is not injured or in shock and if safe to do so (i.e. no machinery in the immediate vicinity). In the event the Project Ecologist or local wildlife rescue cannot be contacted, the injured animal will be delivered to the closest vet as soon as possible. The contact details for available vets and WIRES are provided in Table 1;
- 3. Where necessary, to minimise stress to native fauna and/ or remove the risk of further injury before the appropriate rescue agency arrives onsite, Martinus Environmental Personnel shall cover the animal with a towel or blanket and place it in a cardboard box and/or hessian bag. Appropriate temporary housing for fauna is species-dependent. Gliders, possums, bats, snakes and lizards can be held individually in a calico bag until released in adjacent habitat. Healthy frogs are to be placed in separate, partially inflated single-use plastic bags and include a small amount of leaf litter or clean (i.e. washed in a 0.1 per cent concentration of a benzalkonium chloride-based disinfectant solution such as F10SC at 1:250 dilution and not re-used) damp cloth bag containing a small amount of leaf litter. Nesting birds and eggs are best placed in a covered cardboard box equipped with soft cloth.
 - a. Place small animals in a cotton bag, tied at the top;
 - b. Rescued fauna must be protected from exposure to heat and removed from the areas undergoing clearing activities to minimise noise exposure. Keep the animal in a quiet, cool, ventilated and dark place. A designated site would be decided upon in advance of any construction work;
 - c. Aquatic fauna to be placed in a plastic aquarium or plastic bag with a sufficient amount of water sourced from the point of collection. Frogs would be transported without water or debris in recognition of the risk of transporting disease and the minimal transport time. Any frog handling would be undertaken in accordance with the Hygiene Guidelines (DPIE, 2020) (see Section 3.6);
 - d. Some animals require particular handling (e.g. venomous reptiles, raptors) and should only be handled by appropriately qualified personnel;
 - e. If handling bats, the handler must be vaccinated against the Australian Bat Lyssavirus (ABLV), which is a form of rabies and have appropriate licences to handle;
 - f. Equipment for fauna rescue (including but not limited to a hessian sack, calico bags, cloths/ towels, single-use, non-latex, non-powdered (i.e. nitrile) disposable gloves, suitable animal handling gloves and transport boxes) will be kept in designated locations for emergency use by site staff if required. The fauna specialist will carry a fauna rescue kit in a site vehicle, and an additional kit will be located in the site office;
 - g. Ensure a fully equipped standard first aid kit is on their person at all times, which should include a minimum of two snake bandages. Any animal handling must be undertaken by, or under the supervision of, a person with first-aid training;
- 4. If the animal cannot be handled but appears to be injured or in shock and has not moved on of its own accord, exclude personnel from the vicinity, record the exact location of the animal and contact the Project Ecologist and/ or rescue agency who will advise on a case-by-case basis;
- 5. If the fauna species is identified as a threatened species that is not a species identified in the CBMP, the Environment Manager must:

A2I | ALBURY TO ILLABO





- a. Immediately cease all work likely to affect the threatened species;
- b. If the fauna is injured, call the rescue agency and notify the Project Ecologist; and
- c. Implement the Unexpected Threatened Species Find procedure in Appendix A of the CBMP.
- 6. If the fauna is to be released, the Project Ecologist must identify suitable fauna release locations within or near the project site.

All relevant project documentation would be updated to display the new findings and subsequent management measures where required. This would include such documents as CBMP (and associated documents) and Sensitive Area Plans (SAPs).

If fauna is handled or moved during clearing activities, this will be recorded in post-clearing reports. Due to the linear nature of the Project, there will be a range of different roads and access tracks in which Project personnel or subcontractors may encounter fauna. The likelihood of encountering fauna during dawn and dusk is increased. If fauna is struck by a vehicle, the general fauna handling and rescue procedure is to be followed and the incident is to be recorded by the MR Environment team in the Incident Reporting Protocol (Table 2) and requires reporting via the incident management database per the Safety Management Plan.



3 SPECIFIC HANDLING REQUIREMENTS

3.1 Birds

General rescue approach for birds:

- If habitat trees are found to contain nestlings or juveniles prior to felling, then it would be preferable to leave trees intact until such a time that juveniles have vacated the nest or den. However, if construction timing does not permit this then attempts should be made to rescue juveniles for possible captive rearing and subsequent release into relocation sites;
- Where possible and safe to do so, gain access to nests/hollows and relocate to nearby safe areas avoiding the
 direct handling of eggs and chicks where possible. Nest platforms/poles and nest boxes will be considered on a
 case-by-case basis where they provide benefit to a threatened species and as advised by the project ecologist;
- Capture and remove any nestlings;
- Place nestlings in cotton capture bags and assess for injuries. Store bags containing nestlings in a pet-carrying cage or ventilated cardboard box. The animal container will be covered to reduce stress on the bird. Deliver to specialist wildlife carer;
- If adult birds are captured, they will be released away from construction activities; and
- Raptors should only be handled by experienced fauna handlers and with welders' gloves for the talons.

3.2 Small ground-dwelling mammals

General rescue approach for ground-dwelling mammals:

- If a small mammal is within the construction zone, activities in the area that may impact the animal may need to cease:
- Small mammals should be calmly encouraged or left to leave the work area;
- If small mammals are found during habitat removal, they will need to be captured and relocated;
- If an echidna is found, dig it out by hand or carefully by shovel to the side of the echidna. The aim is to get a hand(s) beneath the animal and to lift it from the soil. Ensure thick gloves are used if handling;
- If native rodents or bandicoots are found, capture them using your gloved hands or with a net and place them in a cloth bag;
- Handling of small mammals will be undertaken by suitably trained and qualified animal handlers; and
- Place small mammals in a larger container, such as a pet carry case. Captive mammals will be kept in a cool, well-ventilated location, out of direct sun. Uninjured small mammals will be translocated to adjacent un-impacted bushland and released as soon as possible.

3.3 Large ground-dwelling mammals

General rescue approach for kangaroos, wallabies, wombats and introduced pests:

- If a large mammal is within the construction zone, activities in the area that may impact the animal may need to cease;
- Large mammals should be calmly encouraged, or left, to leave the work area;
- In the event that a juvenile is displaced (thrown from a pouch) and cannot be reunited with its parent, it will be taken to a vet or wildlife carer;
- Gloves should be worn at all times when handling mammals to mitigate risks from kicking and scratching; and
- Introduced pests such as goats, deer and pigs should not be handled. All pest species should be corralled/ directed out of the project.

3.4 Arboreal mammals

General rescue approach for arboreal mammals:

- If arboreal mammals are found during vegetation clearing, the Project Ecologist/ fauna handler will determine if capture and relocation are warranted;
- Animals will be captured either by hand or net and placed into a suitable cage;
- If uninjured, captured animals will be released at a location deemed suitable by the Project Ecologist, and;



• In the event that juvenile possums/ gliders are displaced and cannot be reunited with their mother, they will be managed in accordance with the recommendations of the Project Ecologist or fauna handler. As required, the juvenile will be taken to a vet or wildlife carer.

3.5 Reptiles

General rescue approach for reptiles:

- Snakes will only be captured and relocated if they present a potential threat to construction personnel or are likely to be harmed by the works. In most cases, snakes will attempt to move away from a disturbed area;
- Reptiles will be captured by the Project Ecologist (when they are available) or by a person who is licensed under the Biodiversity Conservation Act 2016 to catch and release reptiles;
- Snakes will only be handled by approved personnel who are qualified and trained to do so;
- No contact handling techniques (i.e. use a snake hook and bag as opposed to manually handing the snake) are recommended for all snakes, and;
- Lizards will be released as soon as possible after capture into suitable habitats outside of the construction zone;

3.6 Amphibians

The Hygiene Guidelines (DPIE, 2020) must be followed for all frog handling to prevent pathogen spread amongst individuals and between catchments. General rescue approach for frogs:

- If there is no option other than to handle amphibians, single-use, non-latex, non-powdered (i.e. nitrile) disposable gloves must be worn when handling individuals. If gloves are not available, then avoid touching the frog with bare hands by using implements to transfer to a container;
- Healthy frogs are to be placed in separate single-use plastic bags which should be partially inflated or clean (i.e. washed in a 0.1 per cent concentration of a benzalkonium chloride-based disinfectant solution such as F10SC at 1:250 dilution and not re-used) damp cloth bag;
- Sick or injured individuals would be euthanised immediately unless there is a high probability of recovery, in which case treatment would be as for healthy frogs;
- Handling equipment, hands and boots to be cleaned of all soil and sprayed with a 0.1 per cent concentration of a benzalkonium chloride-based disinfectant solution (i.e. F10SC at 1:250 dilution) or a Chlorhexidine-based product (e.g. Halamid©) and rinsed when moving between water bodies. Hands may be disinfected using 70 per cent methylated spirits in water;
- Frogs and tadpoles are not to be moved between catchments;
- Dead frogs would be handled only using single-use gloves and buried in situ to avoid movement of pathogens.

3.7 Other mammals: Bats

General rescue approach for bats:

- Bats must only be handled by a qualified ecologist or wildlife carer experienced in bat handling and vaccinated against the Australian Bat Lyssavirus (ABLV);
- Gloves must be worn when handling bats;
- As soon as possible, captured microbats will be placed into a cloth/calico bag hung vertically in a quiet, cool, dark place until released at night;
- Larger bats would be handled by wearing elbow length puncture proof gloves, wrapped in a large towel and placed in a large cloth/calico bag;
- All bats will be relocated into adjacent suitable habitat at night;
- In the event that a juvenile bat is displaced and cannot be reunited with its parent, orphaned animals will be managed in accordance with the recommendations of the Project Ecologist or fauna handler. As required the juvenile will be taken to a vet or wildlife carer.



4 EUTHANASIA

4.1 When to euthanise

In some cases, rehabilitation and/ or relocation of fauna will not be possible. When it is not possible to transport an injured animal to a wildlife carer or veterinarian (e.g. when injuries are so extreme that survival is not possible), injured fauna must be assessed by the Project Ecologist or Martinus ER and a decision made regarding euthanasia. In keeping with the NSW Code of Practice for Injured, Sick and Orphaned Protected Fauna (Office of Environment and Heritage, 2011), fauna must be euthanised without exception when:

- Death is imminent or highly likely regardless of the treatment provided;
- The animal is suffering from chronic, un-relievable pain or distress;
- The animal is carrying (or suspected to be carrying) an incurable disease that may pose a health risk to wild animals;
- Its ability to consume food unaided is permanently impaired due to a missing or injured jaw, teeth or beak.

Fauna must be euthanised when one or more of the following circumstances apply:

- Its ability to locomote normally (i.e. run, climb, crawl, hop, fly or swim) is permanently impaired due to a missing or injured limb, wing, foot, backbone or tail;
- Its ability to sense its environment (i.e. see, hear, smell, taste or feel) is permanently impaired due to a missing or injured organ (e.g. eye, ear or nose);
- Its ability to catch or handle food is permanently impaired due to missing or injured digits (e.g. missing rear toe in raptors);
- Its advanced age renders it unable to survive in its natural habitat.

4.2 Euthanasia methods

A method appropriate for the species and circumstances should be utilised to ensure minimal pain and suffering. These methods could include:

- Stunning followed by decapitation and/or destruction of the brain for reptiles and amphibians;
- Stunning followed by cervical dislocation for small birds and mammals (less than 0.5 kg)
- Euthanasia carried out by a veterinarian for any other animal.

Any euthanasia methods utilised will be in accordance with those identified in the NSW Code of Practice for Injured, Sick and Orphaned Protected Fauna (Office of Environment and Heritage, 2011).

Fauna that requires euthanasia should not be exposed to additional stressors such as large numbers of onlookers, people touching it, loud noises or extreme temperatures.

Death must be confirmed prior to disposal of the carcass. The absence of a heartbeat and the loss of corneal reflexes indicate death has occurred.

The decision to euthanise an animal can only be made by the Project Ecologist and/or fauna handler. Euthanasia should be carried out by a licenced wildlife carer, veterinarian or the Project Ecologist.



5 CONTACT DETAILS

The contact details for the Project Ecologist and WIRES are provided within Table 1.

TABLE 1: CONTACT DETAILS

| Role | Organisation | Location | Contact details |
|----------------------|------------------------------------|---------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------|
| Project Ecologist | East Coast Ecology | Sydney, NSW | The contact details for the Project Ecologist will be retained by the MR project staff and available to personnel upon request |
| Wildlife Carers | WIRES | National service utilising local volunteers | 1300 094 734 |
| Veterinarian | Albury Animal Hospital | 323 Wagga Rd, Lavington NSW 2641 | (02) 6040 6995 |
| Veterinarian | Wagga Wagga Veterinary Hospital | 132 Urana St, Turvey Park NSW 2650 | (02) 6926 0900 |
| Veterinarian | Lake Road Vet on Broadway | 113 Broadway, Junee NSW 2663 | (02) 6926 2289 |



6 INCIDENT REPORTING PROTOCOL

For any incidents involving fauna, this form (Table 2) is to be completed and provided to the Environment Manager and filed appropriately.

TABLE 2: FAUNA RESCUE RECORDING SHEET.

| Item | Detail |
|-------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|
| Date fauna located | |
| Time fauna located | |
| Weather (temperature, wind, cloud cover, precipitation) | |
| Location (Coordinates and description i.e. in tree hollow; under stockpile, open area etc) | |
| Fauna type (Mammal, bird, reptile etc) | |
| Species (if known) | |
| Visual signs of behaviour | |
| Condition, general health signs, description of injuries, note if a dead specimen | |
| Is the fauna injured (YES / NO) | |
| If YES, please complete Section A; If NO pl | ease complete Section B |
| A – Injured Fauna Reporting | |
| What time was a fauna specialist (qualified ecologist or wildlife handler) called | |
| What time did the fauna specialist arrive? | |
| Fauna specialist name and contact | |
| What was the outcome? (e.g. Animal euthanized; animal in care; animal taken to vet; treated and relocated) | |
| B – Non-injured Fauna Reporting | |
| Where was the fauna relocated? (Coordinates and description) NB Only a qualified fauna ecologist or wildlife handler is to relocate fauna | |
| Time the fauna relocated? | |
| Name and qualification of fauna handler | |
| Visual signs of behaviour on release | |
| Condition – general health signs – on release | |
| General | |
| Other comments | |
| Completed by | |
| Signed | |










APPENDIX C

Sensitive Area Mapping - Biodiversity























Construction Impact Zone

PCT0 (miscellaneous/non-native vegetation)


PCT5,(poor condition)

PCT277 (poor condition)

Superb Parrot / Squirrel Glider habitat

Potential Sloane's Froglet breeding habitat


Potential Sloane's Froglet breeding habitat (15m buffer)































Inland Rail - A2I

Construction Impact Zone

PCT0 (miscellaneous/non-native vegetation)

PCT277 (poor condition)

Superb Parrot / Squirrel Glider habitat

Sloanes Froglet Breeding Habitat

Potential Sloane's Froglet breeding habitat

Potential Sloane's Froglet breeding habitat (15m buffer)

- Minor Watercourse

- Major Watercourse

Pearson Street Bridge

































































APPENDIX D

Sloane's Froglet Survey



Prepared for Martinus

Methods & Results Report

Inland Rail A2I Sloane's Froglet Surveys

October 2024

Project Number: 240414



Inland Rail A2I Sloane's Froglet Surveys



Document verification

Project Title: Inland Rail A2I Sloane's Froglet Surveys

Project Number: 240414

Project File Name: 240414 Inland Rail A2I Methods & Results Report FINAL V1.2 20241101

| Revision | Date | Prepared by | Approved by |
|------------|------------|-----------------------------------|----------------|
| Draft V1.0 | 5/09/2024 | Julia Chabros | Timothy Garvey |
| Draft V2.0 | 19/09/2024 | Justin Solomons | Timothy Garvey |
| Final V1.0 | 24/09/2024 | Justin Solomons | Timothy Garvey |
| Final V1.1 | 09/10/2024 | Justin Solomons, Julia Chabros | Timothy Garvey |
| Final V1.2 | 01/11/2024 | Bianca Heinze, Julia Chabros | Jane Lambert |

NGH Pty Ltd is committed to environmentally sustainable practices, including fostering a digital culture and minimising printing.

We acknowledge the traditional owners of this land and pay our respect to Elders past, present and emerging. We recognise that the First Nations peoples of Australia have traditionally managed the resources of this land in a sustainable way, and that they are the original stewards of the Australian environment.



Table of contents

| 1. | Introduction | 3 |
|-------|----------------------------------------------------------------|-----|
| 2. | Background | 3 |
| 3. | Methods | 3 |
| 3.1. | Survey methodology | 3 |
| 3.2. | Survey team | 4 |
| 3.3. | Survey effort | 4 |
| 3.4. | Weather conditions | 10 |
| 3.5. | Limitations | 11 |
| 4. | Results | 13 |
| 5. | Conclusion | 30 |
| 6. | References | 31 |
| | | |
| Tab | oles | |
| Table | e 3-1 Survey effort | 5 |
| Table | e 3-2 Daily weather conditions for the duration of the surveys | 10 |
| Table | e 4-1 Results of <i>Crinia sloanei</i> targeted surveys | 13 |
| | | |
| Арр | pendices | |
| Appe | endix A Survey effort atlas maps | A-I |
| Appe | endix B Raw habitat assessment data | B-I |
| Appe | endix C Survey memos | |



Acronyms and abbreviations

| BC Act | NSW Biodiversity Conservation Act 2016 |
|----------|----------------------------------------------------------------------------|
| BDAR | Biodiversity Development Assessment Report |
| ВОМ | Bureau of Meteorology |
| СоА | Conditions of Approval |
| Cwth | Commonwealth |
| DPIE | (Former) Department of Planning, Industry and Environment (NSW) (now DPE) |
| EIS | Environmental impact statement |
| EPBC Act | Commonwealth Environment Protection and Biodiversity Conservation Act 1999 |
| GDA | Geographic Datum of Australia |
| GIS | Geographic information system |
| GPS | Geographical positioning system |
| km | kilometres |
| m | metres |
| Sp/spp | Species/multiple species |
| | l . |



1. Introduction

Martinus engaged NGH to undertake targeted amphibian surveys for the Albury to Illabo (A2I) section of Inland Rail. The A2I scope broadly includes works to enhance 185 kilometres (km) of existing rail corridor between Albury and Illabo, New South Wales (NSW). Surveys were conducted for one target species, Sloane's Froglet (*Crinia sloanei*) which is listed as Endangered at both state and commonwealth levels, under the *Biodiversity Conservation Act 2016* (NSW) (BC Act) and the *Environmental Protection and Biodiversity Conservation Act 1999* (Cwth) (EPBC Act). This memo details the Sloane's Froglet surveys undertaken by NGH on the proposed Project site on behalf of Martinus. Surveys were completed between 15 July – 22 August 2024.

2. Background

Sloane's Froglet was listed as having the potential to occur within the Project site in Appendix D2.8 of the *Albury to Illabo (A2I) Project Environmental Impact Statement Technical Paper 8 - Biodiversity Development Assessment Report* (BDAR) (ARTC, 2022a). As seasonal survey timeframes could not be met prior to the publishing of the *Albury to Illabo Environmental Impact Statement* (EIS), the species was assumed present in areas where suitable habitat values were present (ARTC, 2022b).


The surveys detailed in this memorandum were undertaken in response to the NSW Government Conditions of Approval (CoA), which stated that the Proponent must complete targeted surveys during July and/or August for Sloane's Froglet in all areas where that species was assumed present (condition E25) (NSW Government, n.d.). The CoA also stated that no works impacting areas where Sloane's Froglet presence was assumed are to be carried out prior to the completion of the targeted surveys. If the target species is identified on site, a *Sloane's Froglet Management Plan* must be prepared. Sloane's Froglet habitat mapping, demonstrating potential breeding habitat surrounding and within the Project site, was published in Appendix C-5 of the BDAR.

3. Methods

3.1. Survey methodology

Sloane's Froglet surveys were two-phased. First, areas of potential habitat illustrated within Appendix C-5 of the Albury to Illabo BDAR (ARTC, 2022a) were assessed by NGH ecologists in the field to determine the presence or absence of 'breeding habitat' as prescribed within the NSW Guidelines. Breeding habitat is defined as "still or very slow sections of permanent and temporary streams as well as pools (e.g. farm dams) with vegetation located on the subject land" p.15 (DPIE, 2020).

Where potential breeding habitat was confirmed, surveys were conducted using the aural-visual survey technique described in *NSW Survey Guide for Threatened Frogs* ('the guidelines') (DPIE, 2020). Aural-visual surveys are a combination of active listening for the calls of frogs and searching for individuals along a transect. The surveys included a call-playback component where a loudspeaker was used to broadcast the advertisement calls of the target frog species to elicit a response from any resident individuals who may not be actively calling.





Four replicates of Sloane's Froglet aural-visual surveys were undertaken after sundown within the July-August survey window, in accordance with the CoA and the NSW Government BioNet Atlas (NSW Government, 2008), to optimise the likelihood of recording Sloane's Froglet if present at a site.

Five hundred metre transects were located along potential breeding habitat, such as permanent and ephemeral streams and farm dams. Surveys were conducted between 6:00pm (or following full sun-down) and 1:00am. Observers actively listened for target species calls for 5-minutes during the aural survey. Where there was suitable breeding habitat, a call-playback (2 mins broadcast + 2 mins listening) was conducted. This was followed by five minutes of visual surveying covering 50 m of the transect using head lamps and hand-held torches to scan for frogs within 10 m of either side of the transect, making 15 mins of active survey per point. Sightings of non-target species were recorded opportunistically. Where there was less than 500 m of potential habitat, all available habitat was surveyed.

All field data was collected via Mergin Maps and recorded using NGH field forms. All survey data was georeferenced, and date and time of entries recorded. GPS tracks were collected with a handheld GPS or tracking app. These were used to compile GIS maps.

3.2. Survey team

The surveys were completed by:

- Jonathon Sweeney (Senior Ecologist)
- Michael Cleland (Ecologist)
- Stella O'Dwyer (Ecologist)
- Maddie Robertson (Ecologist)
- Marcus Hoskins (Ecologist)

- Ben Sloggett (Ecologist)
- Taylor Hume (Ecologist)
- Julia Chabros (Graduate Ecologist)
- Justin Solomons (Graduate Ecologist)
- Evan Creek (Graduate Ecologist).


3.3. Survey effort

Survey dates at each of the 21 sites are show in Table 3-1. For aural-visual surveys of Sloane's Froglet, the guidelines require 480 minutes (eight hours) of survey per 500 m of suitable breeding habitat (with call playback points approximately 50 m apart) over four replicates. The replicate requirement was met at all sites where potential breeding habitat was confirmed. Survey points along breeding habitat transects are shown in figures in Appendix A. Survey dates, number of survey points and the length of potential breeding habitat at each site is listed in Table 3-1. Overall, there was 9311 m of breeding habitat surveyed over 201 hours. The effort in parts of the Murray River, Albury, Billy Hughes, Uranquinty, Harefield, Junee 2 Illabo 3 and Junee 2 Illabo 4 sites did not meet the 480 minutes per 500 m survey effort requirement, however, the overall effort achieved for the sites significantly exceeded the effort required.



Table 3-1 Survey effort

| No. | Site name | Survey dates | Length of o potential b habitat (m) | reeding | No. of survey points | Survey time achi | eved | Survey time achieved in full effort (4 nights) (min) | Required survey effort achieved? |
|-----|--------------------------------------------------------------------------|--------------------------------------|---------------------------------------------------------|------------------------------|----------------------------------------------------------------------|--------------------------------------------------------------------------|----------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------|
| Tot | Total habitat outside Study Area: 6197 m Total breeding habitat: 9311 m | | outside Study | side Study Area | | | Total effort required: 8938 min (149 hours) Total effort undertaken: 12,060 min (201 hours) | | |
| 1 | Murray River Bridge | 22-25 July 2024 12 August 2024 | | • | Inside Study Area: 2 Outside Study Area: 2 | Outside study Are | 30 min a: 2 | Inside Study Area: 30 min x 4 reps = 120 min Outside Study Area: 30 min x 4 reps = 120 min | Inside Study Area: effort exceeded by 93 minutes Outside Study Area: effort insufficient by 115 min |
| 2 | Albury | 15-18 July 2024 | m | y Area: 664 udy Area: 0 m | 10 | 10 points x 15 min 150 min | ı = | 150 min x 4 reps = 600 min | Effort insufficient by 37 min |
| 3 | Billy Hughes Bridge | 15-18 July 2024 12-15 August 2024 | Inside Stud Outside Stu 370 Outside Stu 210 | • | Inside Study Area: 4 Outside Study Area A: 9 Outside Study Area B: 3 | Inside Study Area Outside Study Are 135 Outside Study Are 45 | ea A: | Inside Study Area: 240 Outside Study Area A: 540 Outside Study Area B: 135 | Inside Study Area: effort achieved Outside Study Area A: effort exceeded Outside Study Area B: effort insufficient by 25 |





| No. | Site name | Survey dates | Length of confirmed potential breeding habitat (m) | No. of survey points | Survey time achieved in 1 night (min) | Survey time achieved in full effort (4 nights) (min) | Required survey effort achieved? |
|-----|--------------|-------------------------------------------------------------------------|----------------------------------------------------|---------------------------------------------|-----------------------------------------------|------------------------------------------------------|-------------------------------------------------------------------------|
| | | | | | | | min |
| 4 | Table Top | 15-18 July 2024 13-15 August 2024 21 August 2024 | Inside Study Area: 16 Outside Study Area: 568 | Inside Study Area: 1 Outside Study Area: 6 | Inside Study Area: 15 Outside Study Area: 240 | Inside Study Area: 60 Outside Study Area: 960 | Inside Study Area: effort exceeded Outside Study Area: effort exceeded |
| 5 | Culcairn | 22-25 July 2024 | Inside Study Area: 61 Outside Study Area: 0 | Inside Study Area: 1 | Inside Study Area: 15 | Inside Study Area: 60 | Inside Study Area: effort satisfied |
| 6 | Henty | 22-25 July 2024 6 August 2024 13-15 August 2024 20 August 2024 | Inside Study Area: 0 Outside Study Area: 600 | Outside Study Area: 12 | Outside Study Area: 180 | Outside Study Area: 720 | Outside Study Area: effort exceeded |
| 7 | Yerong Creek | 22 July 2024 29 July-1 August 2024 19-22 August 2024 | Inside Study Area: 0 Outside Study Area: 160 | Outside Study Area: 9 | Outside Study Area: 135 | Outside Study Area: 540 | Outside Study Area: effort exceeded |
| 8 | The Rock | 22-25 July 2024 29 July 2024 19-22 August 2024 | Inside Study Area: 6 Outside Study Area: 387 | Inside Study Area: 1 Outside Study Area: 13 | Inside Study Area: 15 Outside Study Area: 195 | Inside Study Area: 60 Outside Study Area: 780 | Inside Study Area: effort exceeded Outside Study Area: |



| No. | Site name | Survey dates | Length of confirmed potential breeding habitat (m) | No. of survey points | Survey time achieved in 1 night (min) | Survey time achieved in full effort (4 nights) (min) | Required survey effort achieved? |
|-----|-------------------|-----------------------------------------------|----------------------------------------------------|---------------------------------------------|-----------------------------------------------|------------------------------------------------------|----------------------------------------------------------------------------------------|
| | | | | | | | effort exceeded |
| 9 | Uranquinty | 22-25 July 2024 29 July 2024 | Inside Study Area: 148 Outside Study Area: 611 | Inside Study Area: 3 Outside Study Area: 8 | Inside Study Area: 45 Outside Study Area: 120 | Inside Study Area: 180 Outside Study Area: 480 | Inside Study Area: effort exceeded Outside Study Area: effort insufficient by 100 min |
| 10 | Pearson Street | 22-25 July 2024 | Inside Study Area: 300 Outside Study Area: 141 | Inside Study Area: 8 Outside Study Area: 4 | Inside Study Area: 120 Outside Study Area: 60 | Inside Study Area: 480 Outside Study Area: 240 | Inside Study Area: effort exceeded Outside Study Area: effort exceeded |
| 11 | Wagga Yard | Assessed on 22 July 2024, no suitable habitat | - | - | - | - | - |
| 12 | Bomen | 29 July-1 August 2024 19-22 August 2024 | Inside Study Area: 21 Outside Study Area: 344 | Inside Study Area: 1 Outside Study Area: 14 | Inside Study Area: 15 Outside Study Area: 210 | Inside Study Area: 60 Outside Study Area: 840 | Inside Study Area: effort exceeded Outside Study Area: effort exceeded |
| 13 | Harefield | 29 July-1 August 2024 19-22 August 2024 | Inside Study Area: 55 Outside Study Area: 540 | Inside Study Area: 2 Outside Study Area: 7 | Inside Study Area: 30 Outside Study Area: 105 | Inside Study Area: 120 Outside Study Area: 420 | Inside Study Area: effort exceeded Outside Study Area: |



| No. | Site name | Survey dates | Length of confirmed potential breeding habitat (m) | No. of survey points | Survey time achieved in 1 night (min) | Survey time achieved in full effort (4 nights) (min) | Required survey effort achieved? |
|-----|---------------------|-------------------------------------------------------------|----------------------------------------------------|-----------------------------------------------------------------------------|------------------------------------------------|------------------------------------------------------------|-------------------------------------------------------------------------|
| | | | | | | | effort insufficient by 98 min |
| 14 | Kemp Street | Assessed on 29 July 2024, no suitable habitat | - | - | - | - | - |
| 15 | Junee Yard | Assessed on 29 July 2024, no suitable habitat | _ | - | - | - | - |
| 16 | Olympic Highway | Assessed on 29 July 2024, no suitable habitat | - | - | - | - | - |
| 17 | Junee 2 Illabo | 30 July-1 August 2024 5 August 2024 19-22 August 2024 | Inside Study Area: 0 Outside Study Area: 40 | Outside Study Area: 2 | Outside Study Area: 30 | Outside Study Area: 120 | Effort exceeded |
| 18 | Junee 2 Illabo 2 | 30 July-1 August 2024 5 August 2024 19-22 August 2024 | Inside Study Area: 72 Outside Study Area: 226 | Inside Study Area: 2 Outside Study Area: 7 Surveys in unsuitable habitat: 6 | Inside Study Area: 30 Outside Study Area: 105 | Inside Study Area: 120 Outside Study Area: 420 | Inside Survey Area: effort exceeded Outside Study Area: effort exceeded |
| 19 | Junee 2 Illabo | 30 July-1 August 2024 5 August 2024 | Inside Study Area: 1175 Outside Study Area: 284 | Inside Study Area: 17 Outside Study Area: 11 | Inside Study Area: 255 Outside Study Area: 165 | Inside Study Area: 1020 mins Outside Study Area: 660 | Inside Study Area: effort insufficient by 108 min Outside Study Area: |



| No. | Site name | Survey dates | Length of confirmed potential breeding habitat (m) | No. of survey points | Survey time achieved in 1 night (min) | Survey time achieved in full effort (4 nights) (min) | Required survey effort achieved? |
|-----|---------------------|--------------------------------------|----------------------------------------------------|---------------------------------------------------------------------------------------------------------------------|-----------------------------------------------|------------------------------------------------------|------------------------------------------------------------------------------------------------------------|
| | | 19-22 August 2024 | | | | | effort exceeded |
| 20 | Junee 2 Illabo 4 | 5-8 August 2024 19-22 August 2024 | Inside Study Area: 150 Outside Study Area: 942 | Inside Study Area: 2 Outside Study Area: 12 | Inside Study Area: 30 Outside Study Area: 180 | Inside Study Area: 120 Outside Study Area: 720 | Inside Study Area: effort insufficient by 24 min Outside Study Area: effort insufficient by 184 min |
| 21 | Junee 2 Illabo 5 | 5-8 August 2024 19-22 August 2024 | Inside Study Area: 173 Outside Study Area: 529 | Inside Study Area: 4 Outside Study Area: 14 Plus 1 survey point of extra effort in area later determined unsuitable | Inside Study Area: 60 Outside Study Area: 210 | Inside Study Area: 240 Outside Study Area: 840 | Inside Study Area: effort exceeded Outside Study Area: effort exceeded Additional extra effort = 60 mins |



3.4. Weather conditions

Weather conditions during survey influence survey success (DPIE, 2020). Generally, ideal conditions for amphibian surveys are warm (>18°C) and moist (recent rainfall). However, particular species may differ such as Sloane's Froglet with the peak calling period occurring in winter. The weather data in Table 3-2 was drawn from Wagga Wagga AMO, station 072150 (Bureau of Meteorology, 2024). Weather during the survey period was cold to mild with variable rainfall. The weather conditions satisfied the guidelines' requirement to sample across a variety of conditions.

Table 3-2 Daily weather conditions for the duration of the surveys

| Week | Date | Temp min (°C) | Temp max (°C) | Rainfall (mm) | Max. wind gust (km/h) | RH 9am¹(%) |
|---------|------------|---------------|------------------|------------------|-----------------------|------------|
| | 15/07/2024 | 0.5 | 10.0 | 0.2 | 39 | 97 |
| Week 1 | 16/07/2024 | 3.3 | 11.8 | 13.6 | 46 | 98 |
| Wook 1 | 17/07/2024 | 6.0 | 11.6 | 6.2 | 20 | 99 |
| | 18/07/2024 | 1.0 | 10.8 | 0.2 | 33 | 80 |
| | 22/07/2024 | 6.7 | 14.9 | 0.8 | 30 | 99 |
| Week 2 | 23/07/2024 | 2.1 | 16.3 | 0 | 15 | 89 |
| WCCK Z | 24/07/2024 | 1.8 | 15.2 | 0 | 19 | 68 |
| | 25/07/2024 | 6.5 | 13.4 | 0 | 33 | 99 |
| | 29/07/2024 | -1.5 | 12.1 | 0 | 33 | 77 |
| Week 3 | 30/07/2024 | -2.8 | 13.2 | 0.2 | 17 | 78 |
| Week | 31/07/2024 | -2.2 | 14.7 | 0 | 19 | 78 |
| | 1/08/2024 | -2.5 | 14.7 | 0 | 15 | 86 |
| | 5/08/2024 | 5.9 | 13.9 | 0 | 28 | 98 |
| Week 4 | 6/08/2024 | 2.2 | 15.2 | 0.4 | 31 | 95 |
| TTOOK 1 | 7/08/2024 | -0.8 | 16.1 | 0 | 24 | 81 |
| | 8/08/2024 | 0.7 | 16.9 | 0 | 28 | 96 |

¹ RH = relative humidity. Provided for 9am the following morning as best matches site conditions on survey night.

_



| Week | Date | Temp min (°C) | Temp max (°C) | Rainfall (mm) | Max. wind gust (km/h) | RH 9am¹(%) |
|--------|------------|---------------|------------------|------------------|-----------------------|------------|
| | 12/08/2024 | 5.4 | 19.9 | 0 | 26 | 80 |
| Week 5 | 13/08/2024 | 5.4 | 20.5 | 0 | 22 | 96 |
| | 14/08/2024 | 10.4 | 18.8 | 15.4 | 19 | 91 |
| | 15/08/2024 | 6.1 | 20.7 | 0.4 | 17 | 91 |
| | 19/08/2024 | 3.6 | 18.4 | 0 | 26 | 77 |
| Week 6 | 20/08/2024 | 7 | 18.8 | 0.2 | 39 | 90 |
| | 21/08/2024 | 8.5 | 14.7 | 0 | 31 | 92 |
| | 22/08/2024 | 6.1 | 17.9 | 0 | 26 | 88 |

3.5. Limitations

The discussion on limitations below is based on the approach of the guidelines as well as particular limitations of the site.

Optimise time of year and meteorological conditions

Targeted surveys were taken at the optimal time of year and in mostly optimal conditions in terms of rainfall and temperature. However, some nights of surveys were conducted at low temperatures (Table 3-2). As some frog species can become less active in these lower temperatures, this may impact results for cold nights. As the surveys were taken across a range of conditions, as per the guidelines, this limitation has not affected the efficacy of the survey.

Identified potential habitat

Despite available research on habitat characteristics and key microhabitat components required for Sloane's Froglet (Knight A., 2015; Knight, Watts, Allan, McDonald, & Lappin, 2024), we opted for the most conservative definition of potential breeding habitat as defined by the guidelines. This likely resulted in more areas categorised as potential breeding habitat than may actually occur. This limitation has ensured high survey coverage of the proposal area and a high confidence that Sloane's Froglet would be detected should it occur.

Some areas that were mapped as potential habitat in Appendix C-5 of the Albury to Illabo BDAR were not surveyed after habitat assessment (see Table 4-1). The sites that did not contain suitable habitat and were excluded completely were Wagga Yard, Kemp Street, Junee Yard and Olympic Highway. Other sites had areas that were excluded, such as a large concrete drainage spillway in Pearson Street that was filled with concrete slabs, or a depression with exotic grass and no water in Junee to Illabo 4. These areas lacked water and/or vegetation, and as a result do not meet the prescribed criteria for suitable Sloane's Froglet habitat.

Inland Rail A2I Sloane's Froglet Surveys



Access

Visual surveying was difficult to accomplish in some areas where the watercourse was inaccessible due to steep drainage line walls, particularly in the southern section of the Albury site. In these instances, transects were completed along the verge or the drain, as close to the waterline as possible. As frogs were heard from these locations, this limitation has not affected the efficacy of survey.

Access to the areas identified in the BDAR was organised by Martinus, including entry into rail corridors and onto privately-owned land. There were several potential habitat areas that were inaccessible due to non-agreeance by private landholders: Some areas of private property at sites Junee 2 Illabo 1, Junee 2 Illabo 2, Junee 2 Illabo 3 and Junee 2 Illabo 4 were inaccessible for survey. Likewise, several dams and survey points at the Harefield, Bomen and Yerong Creek sites were inaccessible directly.

An assessment of habitat was made from closest access points (e.g. property fencelines) and where breeding habitat could not be observed, no surveys were undertaken. Where breeding habitat was observed or considered likely to occur, aural-playback surveys were conducted at points along the fence-line closest to the waterbody. Visual surveys were not possible; however, aural surveys confirmed the presence of conspecific frogs (e.g. Eastern Sign Bearing Froglet and Bibron's Froglet). This indicates a capacity for assessors to identify calling frogs present at the site, despite not having physical access. Sloane's Froglet were not recorded calling or responding to call-playback efforts across the four survey nights. This limitation is not considered to have affected the efficacy of the survey.

Site conditions

Proximity to roads and highways may have limited the efficacy of call playback at some sites due to noise competition with passing traffic. This was prevalent at all sites where survey points were within approximately 30 m of roadways. Some points were not surveyed due to proximity to main highway. For example, the southern habitat area for Billy Hughes Bridge ought to have had an additional survey point but due to proximity to Hume Freeway, this point was not utilised. This may have impeded the ability for local frogs to hear broadcast calls. This limitation is likely mitigated by the repetitive structure of the survey methodology giving multiple opportunities for call-playback within and across survey nights to maximise the opportunity for a successful response call were the target species present. Thus, the efficacy of the survey is satisfactory.

Inland Rail A2I Sloane's Froglet Surveys



4. Results


Sloane's Froglet was not recorded at any of the 21 sites across the entire survey period. A summary of each site is provided in the Table 4-1. Details from each site are given in Appendix B.

Table 4-1 Results of Crinia sloanei targeted surveys

| Map ID | Site | Habitat assessment | C. sloanei presence | Site photo |
|-----------|---------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|------------|
| 1 | Murray River Bridge | This site had juvenile <i>Eucalyptus sp.</i> on the water's edge with some scattered <i>Acacia sp.</i> The understorey was made up mostly of Kikuyu grass (<i>Cenchrus clandestinus</i>). Several logs and debris were within the river. Eastern Sign-bearing Froglets (<i>Crinia parinsignifera</i>) recorded aurally. Murray River Bridge A contained fast flowing water and a strong current. The faster flow and small amount of riparian vegetation made this sub-site unsuitable breeding habitat for the target species. Murray River Bridge B had slow-moving water near the bank, which made the habitat suitable for the target species. Murray River C was made up of a string of ponds with overgrown vegetation, also suitable breeding habitat. | Absent | |



| Map ID | Site | Habitat assessment | C. sloanei presence | Site photo |
|-----------|--------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|------------|
| 2 | Albury | The site consisted mainly of concrete drainage areas with stagnant or slow-moving water. Vegetation surrounding the water was predominantly exotic, and included Kikuyu (<i>Cenchrus clandestinus</i>), Privet (<i>Ligustrum lucidum</i>), Ash (<i>Fraxinus</i> sp.), and <i>Phalaris</i> sp. Native species included <i>Austrostipa sp</i> . No frog species were recorded aurally or visually. Albury A had a low level of slow flowing water in concrete drain, and vegetation along banks. Albury B was a concrete drain with no water, therefore, no habitat for the target species. Albury C had slow moving water with algae in deep concrete drain algae present. Albury D was a wide concrete drain, with shallow flowing or still water, and some vegetation surrounding it. | Absent | |






| Map ID | Site | Habitat assessment | C. sloanei presence | Site photo |
|-----------|---------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|------------|
| 3 & 4 | Billy Hughes Bridge | Potential breeding habitat present; surveys undertaken. This site consisted of a dam and dry creek beds, as well as some riparian vegetation along the western side of the Hume Highway. The overstorey of the site consisted of Eucalyptus melliodora, Eucalyptus camaldulensis and Eucalyptus bridgesiana. With the understorey consisting of Typha sp., Drain Sedge (Cyperus eragrostis), Juncus sp., and Phalaris sp. Eastern Sign-bearing Froglets (Crinia parinsignifera), Spotted Marsh Frog (Limnodynastes tasmaniensis), Victorian Tree Frog (Litoria paraewingi) and Common Eastern Froglet (Crinia signifera) were recorded aurally. Potential Sloane's Froglet habitat occurred at Billy Hughes Bridge A, C, D and G. Billy Hughes Bridge A consisted of a dam surrounded by dead grass and weeds. Billy Hughes Bridge C was an ephemeral waterway, culvert and dam with nearby vegetation. Billy Hughes Bridge G consisted of a farm dam with pasture grasses, and Billy Hughes Bridge D was a natural waterway with groundcover and canopy layer vegetation. Billy Hughes Bridge B, D, E, F, H and I did not contain suitable breeding habitat. Billy Hughes Bridge E was a depression no water. Billy Hughes Bridge E was also a depressions with no water, and was situated around exotic pasture grasses and box gum woodland. Billy Hughes Bridge B consisted of a dry ephemeral creek bed. Billy Hughes Bridge H did not contain any | Absent | |



| Map ID | Site | Habitat assessment | C. sloanei presence | Site photo |
|-----------|-----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|------------|
| | | water, and Billy Hughes Bridge I consisted of a very small puddle with still, murky water, unsuitable for breeding habitat. | | |
| 5 | Table Top | The Northern area of the site contained two dams within private properties with agricultural land use, as well as a culvert under the roadway and train corridor that connected them. Vegetation around this area was sparse with weed species such as <i>Circium sp.</i> present. Potential breeding habitat occurred at Table Top B, D and F. Table Top D and F consisted of farm dams, and nontarget frog species were heard calling. Table Top B contained water in the form of muddy puddles. Bibron's Toadlet (<i>Pseudophryne bibronii</i>), Spotted Marsh Frog (<i>Limnodynastes tasmaniensis</i>), Eastern Sign-Bearing Froglet (<i>Crinia parinsignifera</i>) recorded visually and aurally. Table Top A C and E did not contain water, and were predominantly dry pasture areas. | Absent | |



| Map ID | Site | Habitat assessment | C. sloanei presence | Site photo |
|-----------|----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|------------|
| 6 | Culcairn | Culcairn C was considered potential habitat as it contained a small stagnant pool of water that showed signs of previous flooding (flood lines on trees). Pool contained Cumbungi (<i>Typha sp.</i>) that had died off. No frog species were recorded visually or aurally. Not breeding habitat occurred in Culcairn A or Culcairn B. Culcairn A was a small standing pond with a strong sulphuric smell and no frogs. Culcairn B did not contain water. | Absent | |
| 7 & 8 | Henty | Site contained concrete culverts, as well as areas with water adjacent to revegetation areas as well as along a vegetated creek line with exotic understorey and a <i>Eucalyptus</i> dominant canopy. No frog species were recorded visually or aurally. Henty A consisted of a culvert with no water, and was unsuitable as breeding habitat. Henty B was considered suitable, as it consisted of a creek line lined with <i>Eucalyptus camaldulensis</i> and other native vegetation. Henty C and D could not be inspected due to access issues, and habitat suitability was assumed. | Absent | |





| Map ID | Site | Habitat assessment | C. sloanei presence | Site photo |
|-----------|--------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|------------|
| 9 & 10 | Yerong Creek | Surveys were undertaken at Yerong Creek A, C, D and E. Yerong Creek A and D were dams that were clear of vegetation around the water and surrounded by exotic pastural grasses. Yerong Creek C was a small standing pool at a culvert, with <i>Juncus</i> sp. being the dominant vegetation. Yerong Creek E was a farm dam surrounded by exotic pasture grasses. Eastern Sign-Bearing Froglet (<i>Crinia parinsignifera</i>) recorded aurally. Yerong Creek B did not contain suitable habitat as it was a large concrete culvert that spanned under the railway corridor as well as the roadway, and a private property dam. The culvert area was dominated with Kikuyu (<i>Cenchrus clandestinus</i>). | Absent | |
| 11 | The Rock | Potential breeding habitat present; surveys undertaken. The site consisted of a stagnant drainage line with water underneath the train line at the wester end of the site. This area consisted mostly of exotic grasses, <i>Paspalum sp.</i> and Drain Sedge (<i>Cyperus eragrostis</i>). This connected to a drain that proceeded north, which was vegetated with <i>Typha sp.</i> which led to several larger dams on the other side of the tracks. These dams had a canopy cover consisting of Cootamundra Wattle (<i>Acacia baileyana</i>) and Pepper Tree (<i>Schinus molle</i>). Edges of dams were steep with deep water and Cumbungi (<i>Typha sp.</i>) prevalent. No frog species were recorded visually or aurally. | Absent | |



| Map ID | Site | Habitat assessment | C. sloanei presence | Site photo |
|-----------|------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|------------|
| 12 | Uranquinty | Uranquinty A was predominantly exotic groundcover and some canopy cover in northern edge. Uranquinty B consisted of small pools of water, and frogs were heard calling from the adjacent dam. Uranquinty D and E had small amounts of water. Eastern Sign-bearing Frog (<i>Crinia paringisnifera</i>) was visually and aurally recorded on site. No suitable habitat occurred at Uranquinty C, F and G, as no water was present at those sub-sites. Understorey vegetation at the southern end of the site consisted of exotic grasses, Kikuyu (<i>Cenchrus clandestinus</i>), <i>Phalaris sp.</i> and Drain Sedge (<i>Cyperus eragrostis</i>). Overstorey consisted of River Red-Gum (<i>Eucalyptus camaldulensis</i>). The middle of the site consisted of a drainage line, next to Pearson Street roadside. This area consisted of planted vegetation including Red Ironbark (<i>Eucalyptus sideroxylon</i>), Privet (<i>Ligustrum lucidum</i>), and Bamboo (<i>Bambusa sp.</i>). Understorey consisted of <i>Phalaris sp.</i> and some smaller Cootamundra wattles (<i>Acacia baileyana</i>). The northern portion of the site was vegetated with mostly weed species including; <i>Phalaris sp.</i> with some juvenile Ash (<i>Fraxinus sp.</i>). | | |



| Map ID | Site | Habitat assessment | C. sloanei presence | Site photo |
|-----------|----------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|------------|
| 13 | Pearson Street | One part of this site was a large concrete drainage spillway that was filled with concrete slabs and was not suitable as habitat. Other areas; potential breeding habitat present and surveys undertaken. Pearson St E consisted of a dam and eroded drainage line. Pearson St B and D were also drainage lines, with limited to no vegetation. Pearson St A was not suitable as it contained fast flowing water. Pearson St C was potential habitat as it consisted of pools of stagnant water with frogs calling. Pearson St H and F were roads and dry road verges. Pearson St G was not able to be inspected and was assumed suitable. This site contained a dam that was vegetated with <i>Typha sp</i> . with planted overstorey surrounding the water. Understorey consisted of Silky Blue-Grass (<i>Dichanthium sericeum</i>), and exotic grasses (<i>Phalaris sp., Paspalum sp.</i>). Other areas of the site contained exotic overstorey consisting of Ash species (<i>Fraxinus sp.</i>) with Pampas Grass (<i>Cortaderia sp.</i>) and <i>Typha sp.</i> within the drainage lines. Eastern Sign-bearing Froglet (<i>Crinia parinsignifera</i>) and Common Eastern Froglet (<i>Crinia signifera</i>) were recorded aurally on site. | Absent | |




| Map ID | Site | Habitat assessment | C. sloanei presence | Site photo |
|-----------|------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|------------|
| 14 | Wagga Yard | No available breeding habitat. This site consisted of a gravel pile with no standing water present. | NA | NA |
| 15 | Bomen | This site consisted of several farm dams, within private properties and concrete culverts that drain from underneath the railway corridor. Some dams contained stags, as well as some <i>Eucalypts sp.</i> and <i>Juncus sp.</i> near the water's edge. Eastern Sign Bearing Frog (<i>Crinia parinsignifera</i>) recorded aurally on site. Bomen G contained dirty, odorous water which showed signs of chemical contamination and had some reeds, and was considered unsuitable breeding habitat. Bomen F was a dam with muddy water, bare banks, and pasture and swamp vegetation within 2 m of the water. Bomen E could not be accessed, and suitability was assumed. Bomen B consisted of a road and built up area, and was not suitable. Bomen C was a small dam with high water, fringing vegetation and frog activity, and was considered suitable habitat. Bomen D was a small dam with water, muddy banks, and vegetation. Bomen A was a temporary pond with water, and considered potentially suitable habitat. | Absent | |



| Map ID | Site | Habitat assessment | C. sloanei presence | Site photo |
|------------|-----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|------------|
| 16 & 17 | Harefield | The site consisted primarily of culverts that ran under the railway corridor and roadways, with minimal water found in these areas. Some Dams in private property were also surveyed, these areas had minimal riparian vegetation around the banks. Eastern Signbearing Froglet (<i>Crinia parinsignifera</i>) and Common Eastern Froglet (<i>Crinia signifera</i>) recorded aurally on site. Harefield D was a farm dam with low water and <i>Juncus</i> sp. on border. Harefield B was not suitable as it did not have water and consisted of gravel. Harefield C was not accessible and highly industrial and suitability was assumed. Harefield G consisted of a dam with water; highly disturbed (light, road noise, little vegetation). Harefield A was considered unsuitable as it has no watercourse or standing water, and no frogs were heard calling. Harefield F was considered suitable as it contained a farm dam and road drains. Harefield E consisted of shallow, temporary water in culverts and drains and was considered to be potentially suitable habitat. | Absent | |



| Map ID | Site | Habitat assessment | C. sloanei presence | Site photo |
|-----------|-------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|------------|
| 18 | Kemp Street | No available breeding habitat. This site consisted of concrete drains running through the township of Junee, with no vegetation on either side. Water in these drains was minimal. | NA | |
| 19 | Junee Yard | No available breeding habitat. This site consisted of concrete drains running through the township of Junee with no vegetation on either side. Water in these drains was minimal. | NA | |





| Map ID | Site | Habitat assessment | C. sloanei presence | Site photo |
|-----------|------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|------------|
| 20 | Olympic Highway | No available breeding habitat. This site consisted of a drain coming from underneath the Olympic Highway in north Junee, that flowed into a grass reserve depression which continued to another drain. Minimal water was found on site. | NA | |
| 22 | Junee 2 Illabo 1 | This site contained 2 dams within private property farms along the Olympic Highway between Junee township and Illabo Township. Dams were absent of riparian vegetation with exotic pastural grass surrounding or cropped species. Other areas were made up of concrete and brick culverts, sometimes with still water within, other times dry of any water. These areas were covered in exotic vegetation mostly <i>Phalaris sp.</i> and <i>Paspalum sp.</i> , however some areas contained native Black-anther Flax-lily (<i>Dianella revoluta</i>). Overstorey in these areas were cleared within the rail corridor, yet some <i>Eucalyptus sp.</i> remained within private properties. Eastern Sign-bearing Froglet (<i>Crinia parinsignifera</i>) and Bibron's Froglet (<i>Pseudophryne bibronii</i>) recorded aurally on site. | Absent | |



| Map ID | Site | Habitat assessment | C. sloanei presence | Site photo |
|-----------------------|------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|------------|
| | | Junee 2 Illabo 1 A was a degraded farm dam and had no suitable vegetation, however, as water was present, it was considered to have suitable habitat. Junee 2 Illabo 1 B was a cropped wheat paddock with no water and no depressions, and was unsuitable. Junee 2 Illabo 1 D consisted of a farm dam with dirty stagnant water and no fringing vegetation and was considered unsuitable. Junee 2 Illabo 1 C had no water and exotic non-aquatic pasture species and was also determined to be unsuitable for breeding habitat. | | |
| 23, 24, 25 & 26 | Junee 2 Illabo 2 | Two private property dams were located on this site, other areas consisted of concrete drainage culverts, underneath the railway line and roadway. These locations had mostly disturbed habitat with exotic grasses being the dominant vegetation found. Some private property dams containing exotic vegetation and cropped vegetation surrounding water edges. Toward the northern end of the site within private property, there were some native trees within proximity to the water, these species were Blakely's Red Gum (<i>Eucalyptus blakelyi</i>) and Yellow Box (<i>Eucalyptus melliodora</i>), <i>Juncus sp.</i> Eastern Sign-bearing Froglet (<i>Crinia parinsignifera</i>) and Bibron's Froglet (<i>Pseudophryne bibronii</i>) recorded aurally on site. Junee 2 Illabo 2 A was a culvert with temporary water and limited native vegetation, therefore, was considered not suitable. Junee 2 Illabo 2 B consisted of a drainage area with puddles of | Absent | |



| Map ID | Site | Habitat assessment | C. sloanei presence | Site photo |
|-----------|------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|------------|
| | | water and vegetation and was considered suitable habitat. Junee 2 Illabo 2 C consisted of rail and road culverts no vegetation, therefore, was unsuitable. Junee 2 Illabo 2 D was a farm dam with water, and was considered suitable habitat. Junee 2 Illabo 2 E consisted of culverts, muddy puddles and wet depressions in paddocks. Junee 2 Illabo 2 F consisted of cropped and pasture paddocks with no water, farm dam no vegetation. Junee 2 Illabo 2 G consisted of cropped and pasture paddocks with no water, farm dam no vegetation. Junee 2 Illabo 2 J contained puddles in vegetated drain beside rail track with frogs calling, therefore, potential suitable habitat. Junee 2 Illabo 2 H consisted of a road and cropped and pasture paddocks with no water. Junee 2 Illabo 2 I contained cropped and pasture paddocks with no water. | | |



| Map ID | Site | Habitat assessment | C. sloanei presence | Site photo |
|---------------------------|------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|------------|
| 26, 27, 28, & 29 | Junee 2 Illabo 3 | This site also contains public properties and concrete culverts along the Olympic Highway, these sites contained mostly exotic grasses <i>Phalaris sp.</i> and <i>Paspalum sp.</i> Private properties within this site consisted of a long-vegetated drainage line that connected to a concrete culvert within the railway corridor. This patch of habitat contained <i>Juncus sp.</i> around areas of water. This area also contained some native upper storey such as Yellow Box (<i>Eucalyptus melliodora</i>). Eastern Sign Bearing (<i>Crinia parinsignifera</i>) and Bibron's Froglet (<i>Pseudophryne bibronii</i>) and Suddell's Frog (<i>Neobatrachus sudelli</i>) were recorded aurally on site. Junee 2 Illabo 3 A contained water and fringing vegetation, with some canopy trees. Junee 2 Illabo 3 B did not contain water, therefore, was unsuitable for the target species. Junee 2 Illabo 3 D was a grassy overflow area that was temporarily inundated. Junee 2 Illabo 3 E was a farm dam with fringing vegetation. Junee 2 Illabo 3 F consisted of farms dams and adjoining creek with fringing vegetation (pasture grass and <i>Juncus</i> sp.). Junee 2 Illabo 3 C was a rail culvert with some water and minimal vegetation. | Absent | |



| Map ID | Site | Habitat assessment | C. sloanei presence | Site photo |
|-------------|------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|------------|
| 30, 31 & 32 | Junee 2 Illabo 4 | Depression with exotic grass and no water not suitable habitat. Other areas are potential breeding habitat present; surveys undertaken. Sites along this section consist of private property dams with exotic vegetation surrounding, as well as drainage lines close to the southern borders of the Illabo township. Some private property dams and large water ways that flowed along the railway corridor could not be accessed. Eastern Sign Bearing (<i>Crinia parinsignifera</i>) and Bibron's Froglet (<i>Pseudophryne bibronii</i>) were recorded aurally on site. Junee 2 Illabo 4 A consisted of a farm dam, and was considered to be marginal habitat due to lack of vegetation. Junee 2 Illabo 4 B contained railway culverts with a concrete floor no vegetation. Junee 2 Illabo 4 C was a vegetated drain and farm dam with frogs calling. Junee 2 Illabo 4 I contained a Box Gum Woodland but no water. Junee 2 Illabo 4 D consisted of a farm dam with no vegetation near the water and exotic groundcover vegetation. Junee 2 Illabo 4 E consisted of muddy puddles and a vegetated culvert. Junee 2 Illabo 4 F consisted of culverts with stagnant water and without vegetation. Junee 2 Illabo 4 H was an overgrown ephemeral drainage line. Some areas of this sub-site were inaccessible. Junee 2 Illabo 4 G consisted of a road. Junee 2 Illabo 4 J contained small ephemeral puddles with exotic pasture species. Junee 2 Illabo 4 K contained inaccessible dams and vegetated drainage lines between. | Absent | |



| Map ID | Site | Habitat assessment | C. sloanei presence | Site photo |
|------------|------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|------------|
| | | Suitability was assumed and the area was surveyed from multiple points along the fence line, where frog calls were audible and multiple common frog species were recorded. Junee 2 Illabo 4 L consisted of stagnant water in pasture. Dams were inaccessible but appeared unsuitable (no vegetation). | | |
| 33 & 34 | Junee 2 Illabo 5 | This site contained some private property dams, one such dam was surrounded by planted Pine trees (<i>Pinus sp.</i>) with an exotic understorey made up of <i>Phalaris sp.</i> up until the banks which were sandy and clear. A vegetated drain ran the length of one side of this dam mainly <i>Phalaris sp.</i> with some <i>Juncus sp.</i> in areas with water. Eastern Sign Bearing (<i>Crinia parinsignifera</i>) and Bibron's Froglet (<i>Pseudophryne bibronii</i>) were recorded aurally on site. Junee 2 Illabo 5 A, B, C, D, F and H consisted of areas without water, therefore, were unsuitable for breeding habitat. Junee 2 Illabo 5 E consisted of a dam no vegetation, vegetated drainage lines, wet paddocks and culverts. Junee 2 Illabo 5 G was a drainage line with some water present. Junee 2 Illabo 5 J has water present in patches and native dominated vegetation, but no aquatic vegetation. Junee 2 Illabo 5 I was a farm dam with no vegetation. It was surrounded by dry grassy groundcover and the rail corridor and determined to be unsuitable habitat. | Absent | |



5. **Conclusion**

In summary, the survey effort for the Albury to Illabo (A2I) section of Inland Rail was completed in accordance with Condition E25 of the CoA and the NSW Survey Guide for Threatened Frogs (DPIE, 2020). Identified limitations such as site conditions and access did not reduce the efficacy of surveys. Surveys were conducted during the appropriate survey window during July - August, as per the CoA and the guidelines with the appropriate number of replicates (four). The target species, Sloane's Froglet (Crinia sloanei), was not detected aurally or visually at any site.

Based on survey results, a Sloane's Froglet Management Plan is not required as the species does not occur in the project area. Condition E25 of the CoA has been satisfied and there is no further survey or other work required for Sloane's Froglet to fulfill this condition.



6. References


- ARTC. (2022a). Albury to Illabo (A2I) Project Technical Paper 8 Biodiversity Development Assessment Report, Part

 2. WSP. Retrieved from https://majorprojects.planningportal.nsw.gov.au/prweb/PRRestService/mp/01/getContent?AttachRef= SSI-10055%2120220815T112123.839%20GMT
- ARTC. (2022b). *Inland Rail Albury to Illabo Environmental Impact Statement*. WSP. Retrieved from https://majorprojects.planningportal.nsw.gov.au/prweb/PRRestService/mp/01/getContent?AttachRef= SSI-10055%2120220815T072148.752%20GMT
- Bureau of Meteorology. (2024, September 06). *Daily Weather Observations for New South Wales*. Retrieved from Australian Government Bureau of Meteorology: http://www.bom.gov.au/climate/dwo/IDCJDW0213.shtml
- DPIE. (2020). NSW Survey Guide for threatened Frog. a guide for the survey of threatened frogs and their gabitat for the Biodiversity Assessment Method. Retrieved from chrome-extension://efaidnbmnnnibpcajpcglclefindmkaj/https://www.environment.nsw.gov.au/-/media/OEH/Corporate-Site/Documents/Animals-and-plants/Threatened-species/nsw-survey-guide-for-threatened-frogs-200440.pdf
- Knight, A. (2015). The case for Sloane's Froglet: generating ecological knowledge with the intent to benefit biodiversity. PhD Thesis, Charles Sturt University.
- Knight, A., Watts, R., Allan, C., McDonald, S., & Lappin, N. (2024). Habitat features important for the conservation of the endangered Sloane's Froglet (Crinia sloanei) in peri-urban environments. *Wildlife Research*. doi:doi.org/10.1071/WR23032
- NSW Government. (2008, March 28). *Crinia sloanei*. Retrieved from BioNet Atlas: https://atlaseditor.bionet.nsw.gov.au/UI_Modules/TSM_/ProfileEdit.aspx?pId=20088&pType=SpeciesCode
- NSW Government. (n.d.). Conditions of Approval for Inland Rail Albury to Illabo (SSI-10055). Sydney: NSW Government.
- Threatened Species Scientific Committee. (2019, July 4). *Conservation advice*. Retrieved from chrome-extension://efaidnbmnnnibpcajpcglclefindmkaj/https://www.environment.gov.au/biodiversity/threatened/species/pubs/59151-conservation-advice-04072019.pdf



Appendix A Survey effort atlas maps

























































































































































Inland Rail A2I Sloane's Froglet Surveys



Appendix B Raw habitat assessment data

| Map ID | Site | Result | Site sub-name | Comment |
|--------|---------------------|----------------------------|-----------------------|-----------------------------------------------------------------------------|
| 2 | Albury | Potential breeding habitat | Albury A | Slow flowing low level in concrete drain, vegetation along banks |
| 2 | Albury | Not breeding habitat | Albury B | Concrete drain, no water present |
| 2 | Albury | Potential breeding habitat | Albury C | Slow moving water in deep concrete drain, algae present. Marginal |
| 3 | Albury | Potential breeding habitat | Albury D | Wide concrete drain, shallow flowing or still water, some vegetation nearby |
| 4 | Billy Hughes Bridge | Potential breeding habitat | Billy Hughes Bridge A | Dam surrounded by dead grass and weeds |
| 4 | Billy Hughes Bridge | Not breeding habitat | Billy Hughes Bridge B | Dry ephemeral creek bed |
| 4 | Billy Hughes Bridge | Potential breeding habitat | Billy Hughes Bridge C | Ephemeral waterway, culvert and dam with nearby vegetation |
| 4 | Billy Hughes Bridge | Potential breeding habitat | Billy Hughes Bridge D | Natural waterway with vegetation |
| 4 | Billy Hughes Bridge | Not breeding habitat | Billy Hughes Bridge E | Depressions with no water, exotic pasture grasses and box gum woodland |
| 4 | Billy Hughes Bridge | Not breeding habitat | Billy Hughes Bridge F | Depression no water |
| 4 | Billy Huges Bridge | Potential breeding habitat | Billy Hughes Bridge G | Farm dam with pasture grasses |
| 4 | Billy Hughes Bridge | Not breeding habitat | Billy Hughes Bridge H | No habitat present |
| 4 | Billy Hughes Bridge | Not breeding habitat | Billy Hughes Bridge I | Tiny puddle with still murky water, unlikely to be suitable |
| 15 | Bomen | Potential breeding habitat | Bomen A | Temporary pond |
| 15 | Bomen | Not breeding habitat | Bomen B | Road and built up area |
| 15 | Bomen | Potential breeding habitat | Bomen C | Small dam with high water, fringing vegetation and frog activity |

Methods & Results Report



Inland Rail A2I Sloane's Froglet Surveys

| 15 | Bomen | Potential breeding habitat | Bomen D | Small full dam, muddy banks, vegetation |
|----|------------------|----------------------------|--------------------|---------------------------------------------------------------------------------|
| 15 | Bomen | Potential breeding habitat | Bomen E | Not accessed, suitability assumed |
| 15 | Bomen | Potential breeding habitat | Bomen F | Muddy water, bank bare, pasture and swamp veg within 2m of water |
| 15 | Bomen | Not breeding habitat | Bomen G | Dirty, odorous water, no frogs, some reeds |
| 6 | Culcairn | Not breeding habitat | Culcairn A | Small standing pond, stagnant, strong sulphuric smell. No frogs |
| 6 | Culcairn | Not breeding habitat | Culcairn B | Dry area |
| 6 | Culcairn | Potential breeding habitat | Culcairn C | Large pond with surrounding vegetation |
| 17 | Harefield | Not breeding habitat | Harefield A | No watercourse or body. No frogs present. |
| 16 | Harefield | Not breeding habitat | Harefield B | Gravel and industrial, no water |
| 16 | Harefield | Potential breeding habitat | Harefield C | Not accessible, highly industrial, suitability assumed |
| 16 | Harefield | Potential breeding habitat | Harefield D | Farm dam, low water, Juncus sp. on border |
| 17 | Harefield | Potential breeding habitat | Harefield E | Shallow temporary water in culverts and drains |
| 17 | Harefield | Potential breeding habitat | Harefield F | Part no accessible but surveyed from distance. Habitat farm dam and road drains |
| 17 | Harefield | Not breeding habitat | Harefield G | Dam with water; highly disturbed (light, road noise, little vegetation) |
| 7 | Henty | Not breeding habitat | Henty A | Culvert no water, unsuitable habitat |
| 8 | Henty | Potential breeding habitat | Henty B | Creek line lined with River Red Gum and other native vegetation |
| 8 | Henty | Potential breeding habitat | Henty C | Not inspected, suitability assumed |
| 7 | Henty | Potential breeding habitat | Henty D | Not inspected, suitability assumed |
| 21 | Junee 2 Illabo 1 | Potential breeding habitat | Junee 2 Illabo 1 A | Degraded farm dam, no suitable vegetation, water present |
| 22 | Junee 2 Illabo 1 | Not breeding habitat | Junee 2 Illabo 1 B | Cropped wheat paddock, no water, no depressions |

Methods & Results Report



Inland Rail A2I Sloane's Froglet Surveys

| 22 | Junee 2 Illabo 1 | Not breeding habitat | Junee 2 Illabo 1 C | No water, exotic non-aquatic pasture species |
|---------|------------------|----------------------------|--------------------|----------------------------------------------------------------------------------------|
| 22 | Junee 2 Illabo 1 | Not breeding habitat | Junee 2 Illabo 1 D | Farm dam, dirty stagnant water, no fringing vegetation |
| 23 | Junee 2 Illabo 2 | Not breeding habitat | Junee 2 Illabo 2 A | Culvert with temporary water, limited native vegetation, not suitable |
| 23 | Junee 2 Illabo 2 | Potential breeding habitat | Junee 2 Illabo 2 B | Drainage area with puddles of water and vegetation |
| 23 | Junee 2 Illabo 2 | Not breeding habitat | Junee 2 Illabo 2 C | Rail/road culverts no vegetation |
| 23 | Junee 2 Illabo 2 | Potential breeding habitat | Junee 2 Illabo 2 D | Farm dam |
| 24 | Junee 2 Illabo 2 | Potential breeding habitat | Junee 2 Illabo 2 E | Culverts, muddy puddles and wet depressions in paddocks |
| 25 | Junee 2 Illabo 2 | Not breeding habitat | Junee 2 Illabo 2 F | Cropped and pasture paddocks with no water, farm dam no vegetation |
| 25 | Junee 2 Illabo 2 | Potential breeding habitat | Junee 2 Illabo 2 G | Cropped and pasture paddocks with no water, farm dam no vegetation |
| 26 | Junee 2 Illabo 2 | Not breeding habitat | Junee 2 Illabo 2 H | Road, cropped and pasture paddocks with no water |
| 25 & 26 | Junee 2 Illabo 2 | Not breeding habitat | Junee 2 Illabo 2 I | Cropped and pasture paddocks with no water, farm dam no vegetation |
| 26 | Junee 2 Illabo 2 | Potential breeding habitat | Junee 2 Illabo 2 J | Puddles in vegetated drain beside rail track with frogs calling |
| 27 | Junee 2 Illabo 3 | Potential breeding habitat | Junee 2 Illabo 3 A | Excellent quality habitat |
| 27 | Junee 2 Illabo 3 | Not breeding habitat | Junee 2 Illabo 3 B | Dry |
| 26 & 27 | Junee 2 Illabo 3 | Potential breeding habitat | Junee 2 Illabo 3 C | Rail culvert some water, minimal habitat, culverts and puddles with some vegetation |
| 28 | Junee 2 Illabo 3 | Potential breeding habitat | Junee 2 Illabo 3 D | Grassy overflow area temporarily inundated |
| 29 | Junee 2 Illabo 3 | Potential breeding habitat | Junee 2 Illabo 3 E | Farm dam with fringing vegetation |
| 29 | Junee 2 Illabo 3 | Potential breeding habitat | Junee 2 Illabo 3 F | Farms dams and adjoining creek with fringing vegetation (pasture grass and Juncus sp.) |
| 30 | Junee 2 Illabo 4 | Potential breeding habitat | Junee 2 Illabo 4 A | Farm dam, marginal habitat due to lack of vegetation |
| 30 | Junee 2 Illabo 4 | Not breeding habitat | Junee 2 Illabo 4 B | Railway culverts, concrete floor no vegetation |

Methods & Results Report



Inland Rail A2I Sloane's Froglet Surveys

| 30 | Junee 2 Illabo 4 | Potential breeding habitat | Junee 2 Illabo 4 C | Vegetated drain and farm dam with frogs calling |
|----|------------------|----------------------------|--------------------|-------------------------------------------------------------------------------------------------|
| 31 | Junee 2 Illabo 4 | Potential breeding habitat | Junee 2 Illabo 4 D | Farm dam with no vegetation near water. Thistles around top |
| 31 | Junee 2 Illabo 4 | Potential breeding habitat | Junee 2 Illabo 4 E | Muddy puddles and vegetated culvert |
| 31 | Junee 2 Illabo 4 | Not breeding habitat | Junee 2 Illabo 4 F | Non vegetated culverts with stagnant water |
| 31 | Junee 2 Illabo 4 | Not breeding habitat | Junee 2 Illabo 4 G | Road |
| 31 | Junee 2 Illabo 4 | Potential breeding habitat | Junee 2 Illabo 4 H | Overgrown ephemeral drainage line. Some areas inaccessible. Marginal habitat |
| 31 | Junee 2 Illabo 4 | Not breeding habitat | Junee 2 Illabo 4 I | Box Gum Woodland no water |
| 31 | Junee 2 Illabo 4 | Potential breeding habitat | Junee 2 Illabo 4 J | Small ephemeral puddles with exotic pasture species. Marginal |
| 32 | Junee 2 Illabo 4 | Potential breeding habitat | Junee 2 Illabo 4 K | Dams inaccessible. Vegetated drainage lines between. Suitability assumed. |
| 32 | Junee 2 Illabo 4 | Not breeding habitat | Junee 2 Illabo 4 L | Lying water in pasture. Dams inaccessible but appear unsuitable (no vegetation) |
| 33 | Junee 2 Illabo 5 | Not breeding habitat | Junee 2 Illabo 5 A | Not water or habitat present |
| 33 | Junee 2 Illabo 5 | Not breeding habitat | Junee 2 Illabo 5 B | Channel with no water, not suitable |
| 33 | Junee 2 Illabo 5 | Not breeding habitat | Junee 2 Illabo 5 C | Dry channel not suitable |
| 33 | Junee 2 Illabo 5 | Not breeding habitat | Junee 2 Illabo 5 D | Habitat not viable for frogs |
| 33 | Junee 2 Illabo 5 | Potential breeding habitat | Junee 2 Illabo 5 E | Diverse potential habitat. Dam no vegetation; vegetated drainage lines, wet paddocks & culverts |
| 33 | Junee 2 Illabo 5 | Not breeding habitat | Junee 2 Illabo 5 F | Unsuitable for frogs |
| 33 | Junee 2 Illabo 5 | Potential breeding habitat | Junee 2 Illabo 5 G | Quality habitat present |
| 34 | Junee 2 Illabo 5 | Not breeding habitat | Junee 2 Illabo 5 H | Dry grassy groundcover and rail corridor |
| 34 | Junee 2 Illabo 5 | Not breeding habitat | Junee 2 Illabo 5 I | Farm dam with no vegetation; surrounding dry grassy groundcover and |



Inland Rail A2I Sloane's Froglet Surveys

| | | | | rail corridor |
|----|---------------------|----------------------------|-----------------------|---------------------------------------------------------------------------------------------------|
| 33 | Junee 2 Illabo 5 | Potential breeding habitat | Junee 2 Illabo 5 J | Water present in patches, native dominated vegetation but no aquatic vegetation. |
| 19 | Junee Yard | Not breeding habitat | Junee Yard A | No water present |
| 18 | Kemp Street | Not breeding habitat | Kemp Street A | No water present |
| 1 | Murray River Bridge | Not breeding habitat | Murray River Bridge A | Fast flowing water, strong current. Assume unsuitability south - little riparian veg; flow faster |
| 1 | Murray River Bridge | Potential breeding habitat | Murray River Bridge B | Slow moving water present near bank. Assume suitability beyond. |
| 1 | Murray River Bridge | Potential breeding habitat | Murray River Bridge C | Strings of ponds, overgrown vegetation. Traffic noise loud. |
| 20 | Olympic Hwy | Not breeding habitat | Olympic Hwy A | No water present |
| 13 | Pearson Street | Not breeding habitat | Pearson St A | Fast flowing water; unsuitable |
| 13 | Pearson Street | Not breeding habitat | Pearson St B | Drain line, no frogs over 3 nights |
| 13 | Pearson Street | Potential breeding habitat | Pearson St C | Pools of stagnant water with frogs calling |
| 13 | Pearson Street | Not breeding habitat | Pearson St D | Drainage line, limited to no vegetation, no frogs 3 nights |
| 13 | Pearson Street | Potential breeding habitat | Pearson St E | Dam and eroded drainage line |
| 13 | Pearson Street | Not breeding habitat | Pearson St F | Road |
| 13 | Pearson Street | Potential breeding habitat | Pearson St G | Unable to inspect, assume suitable |
| 13 | Pearson Street | Not breeding habitat | Pearson St H | Road and dry verge |
| 14 | Wagga Yard | Not breeding habitat | Wagga Yard A | Gravel pile, no water, no suitable habitat |
| 5 | Table Top | Not breeding habitat | Table Top A | No riparian vegetation |
| 5 | Table Top | Potential breeding habitat | Table Top B | Muddy puddles |
| 5 | Table Top | Not breeding habitat | Table Top C | Dry habitat |
| | | | | |



Inland Rail A2I Sloane's Froglet Surveys

| 5 | Table Top | Potential breeding habitat | Table Top D | Farm dam, access limited, suitability assumed |
|----|------------|----------------------------|--------------|--------------------------------------------------------------------------------------------|
| 5 | Table Top | Not breeding habitat | Table Top E | Dry pasture |
| 5 | Table Top | Potential breeding habitat | Table Top F | Farm dam, lots of frogs heard |
| 11 | The Rock | Potential breeding habitat | The Rock A | Dams with water, connected by channels. Groundcover vegetation growing up to water's edge. |
| 12 | Uranquinty | Potential breeding habitat | Uranquinty A | Predominantly exotic groundcover and some canopy cover in northern edge. |
| 12 | Uranquinty | Potential breeding habitat | Uranquinty B | Small pools of water, can hear frogs at adjacent dam also |
| 12 | Uranquinty | Not breeding habitat | Uranquinty C | No water present |
| 12 | Uranquinty | Potential breeding habitat | Uranquinty D | Small volume of water |
| 12 | Uranquinty | Potential breeding habitat | Uranquinty E | Small volume of water |
| 12 | Uranquinty | Not breeding habitat | Uranquinty F | Dry |
| 12 | Uranquinty | Not breeding habitat | Uranquinty G | Dry |
| 9 | Yerong Ck | Potential breeding habitat | Yerong Ck A | Dam with heavy stock use and bare edges. Marginal |
| 9 | Yerong Ck | Not breeding habitat | Yerong Ck B | Dry river bed and dry concrete culverts |
| 9 | Yerong Ck | Potential breeding habitat | Yerong Ck C | Small standing pool at culvert, Juncus sp. surrounding |
| 9 | Yerong Ck | Not breeding habitat | Yerong Ck D | Dried dam, no habitat |
| 10 | Yerong Ck | Potential breeding habitat | Yerong Ck E | Farm dam |



Appendix C Survey memos

240414 Inland Rail Sloane's Froglet surveys. - Survey Memo 15/7/24-19/07/24

By Julia Chabros, written on 02/08/2024

Fieldwork team

- Michael Cleland (Ecologist)
- Julia Chabros (Graduate Ecologist)

Fieldwork dates

15/7/24-19/07/24

Fieldwork scope

- To conduct targeted surveys for Sloane's Froglet across three survey sites.:
 - Albury Yard
 - o Billy Hughes Bridge
 - Table Top

Fieldwork Methodology


- The following methodology was conducted every 50 metres of confirmed potential habitat:
 - Active listening (5 minutes)
 - Call playback (2 minutes)
 - Active listening (2 minutes)
 - Active searching (5 minutes)

Where acceptable habitat is available*

This methodology was applied in areas of habitat that contained water (standing / flowing) and vegetation within the ephemeral zone. Each site was surveyed for 4 nights. Areas that did not contain water were marked as "no suitable habitat" and were not re-surveyed.

Survey Results

| Si | te | Results | Sloane's Froglet Presence | Other frog species recorded |
|----|-------------|----------------------------------------------------------------------------------------|------------------------------|-----------------------------|
| | bury ard | All areas surveyed. Lots of light and noise pollution, concrete drains and exotic veg. | Absent | Nil |





| Billy Hughes Bridge | The dam in the north and the waterway+dam in the south had lots of frogs (Eastern sign bearing and Common Eastern Froglets only). | Absent | Eastern sign bearing and Common Eastern froglets in the NW dam and southern dam and waterway |
|---------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|----------------------------------------------------------------------------------------------------------|
| Table Top | The dam was not accessible or visible due to a fence. Surveys were taken from the road. No frogs were heard calling. The culvert has a small puddle of water only, but one Eastern Sign Bearing froglet was heard calling on the last survey night. | Absent | One Eastern Sign bearing froglet on the last day calling from the culvert |

Incidental pest animal species found on sites: Nil

Incidental species found on sites: Nil

Follow Up

All sites were surveyed 4 times, and do not need to be re-visited.



240414 Inland Rail Sloane's Froglet surveys Field Memo 22/7/24-27/7/24

Fieldwork scope

- To conduct targeted surveys for Sloane's Froglet across four survey sites.:
 - Murray River Bridge
 - Culcairn
 - Henty
 - Yerong Creek

Yerong Creek was not surveyed after the first night as time constraints did not allow it. It is to be surveyed in later surveys.

Fieldwork Methodology


- Stella O'Dwyer and Evan Creek to attend sites listed above and conduct:
 - Active listening (5 minutes)
 - Call playback (2 minutes)
 - Active listening (2 minutes)
 - Active searching (5 minutes)

Where acceptable habitat is available*

This methodology was applied in areas of habitat that contained water (standing / flowing) and vegetation within the ephemeral zone.

Survey Results

| Date | Site | Results | Sloane's Froglet Presence |
|----------|------------------------|---------------------------------------------------------------------------------------------------------------------|------------------------------|
| 22/07/24 | Murray River Bridge | Hatched blue areas mapped within project area. Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. | Absent |
| 22/07/24 | Culcairn | Hatched blue areas mapped within project area. Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. | Absent |





| Date | Site | Results | Sloane's Froglet Presence |
|----------|------------------------|-----------------------------------------------------------------------------|------------------------------|
| 22/07/24 | Henty | Hatched blue areas mapped within project area. | Absent |
| | | Eastern sign-bearing frog (<i>Crinia</i> parasignifiera) recorded aurally. | |
| 22/07/24 | Yerong Creek | Hatched blue areas mapped within project area. | Absent |
| 23/07/24 | Murray River Bridge | Hatched blue areas mapped within project area | Absent |
| | | Eastern sign-bearing frog (<i>Crinia</i> parasignifiera) recorded aurally. | |
| 23/07/24 | Culcairn | Hatched blue areas mapped within project area. | Absent |
| | | Eastern sign-bearing frog (<i>Crinia</i> parasignifiera) recorded aurally. | |
| 23/07/24 | Henty | Hatched blue areas mapped outside of the project area. | Absent |
| | | Eastern sign-bearing frog (<i>Crinia</i> parasignifiera) recorded aurally. | |
| 24/07/24 | Murray River Bridge | Hatched blue areas mapped within project area. | Absent |
| | | Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. | |
| 24/07/24 | Culcairn | Hatched blue areas mapped within project area. | Absent |
| | | Eastern sign-bearing frog (<i>Crinia</i> parasignifiera) recorded aurally. | |
| | | Bibron's Froglet (<i>Pseudophryne</i> bibronii) recorded aurally. | |





| Date | Site | Results | Sloane's Froglet Presence |
|----------|------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|
| 24/07/24 | Henty | Hatched blue areas mapped outside of the project area. Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. 1 recorded visually. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | Absent |
| 25/07/24 | Murray River Bridge | Hatched blue areas mapped within project area. Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally and visually | Absent |
| 25/07/24 | Culcairn | Hatched blue areas mapped within project area. Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. | Absent |
| 25/07/24 | Henty | Hatched blue areas mapped outside of the project area. Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. | Absent |

Incidental pest species found on sites: Nil

Incidental species found on sites:

- Pacific Black Duck (Anas superciliosa): Murray River bridge

Follow Up

Vegetation photos were taken on the 23/07/24 (Murray River bridge south side), 24/07/24 (Murray River bridge north side) and on 25/07/24 (Culcairn and Henty).

All sites were surveyed only within the project area for surveys on 22/07/24. Areas outside the project area were surveyed for only 3 nights (may require an additional night survey).



240414 Inland Rail Sloane's Froglet surveys Field Memo 22/7/24-27/7/24

Fieldwork scope

- To conduct targeted surveys for Sloane's Froglet across three survey sites.:
 - o The Rock
 - Uranquinty
 - o Pearson Street- Wagga Wagga

Fieldwork Methodology


- Maddie Robertson and Justin Solomons to attend sites listed above and conduct:
 - Active listening (5 minutes)
 - Call playback (2 minutes)
 - Active listening (2 minutes)
 - o Active searching (5 minutes)

Where acceptable habitat is available*

This methodology was applied in areas of habitat that contained water (standing / flowing) and vegetation within the ephemeral zone.


Survey Results

| Date | Site | Results | Sloane's Froglet Presence |
|----------|----------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|
| 22/07/24 | The Rock | Hatched blue areas mapped within project area. Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | Absent |
| 22/07/24 | Uranquinty | Hatched blue areas mapped within project area. Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. | Absent |
| 22/07/24 | Pearson Street | Hatched blue areas mapped | Absent |






| Date | Site | Results | Sloane's Froglet Presence |
|----------|----------------|--------------------------------------------------------------------------------------------------------------|---------------------------|
| | | within project area. | |
| | | Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. | |
| | | Bibron's Froglet (<i>Pseudophryne</i> bibronii) recorded aurally. | |
| 23/07/24 | The Rock | All accessible hatched blue areas mapped (including outside project area). | Absent |
| | | Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. | |
| | | Bibron's Froglet (<i>Pseudophryne</i> bibronii) recorded aurally. | |
| 23/07/24 | Uranquinty | All accessible hatched blue areas mapped (including outside project area). | Absent |
| | | Eastern sign-bearing frog (<i>Crinia parasignifiera</i>) recorded aurally. 1 individual visually recorded. | |
| 23/07/24 | Pearson Street | All accessible hatched blue areas mapped (including outside project area). | Absent |
| | | Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. | |
| | | Bibron's Froglet (<i>Pseudophryne</i> bibronii) recorded aurally. | |
| 24/07/24 | The Rock | All accessible hatched blue areas mapped (including outside project area). | Absent |





| Date | Site | Results | Sloane's Froglet Presence |
|----------|----------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|
| | | Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. | |
| | | Bibron's Froglet (<i>Pseudophryne</i> bibronii) recorded aurally. | |
| 24/07/24 | Uranquinty | All accessible hatched blue areas mapped (including outside project area). Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | Absent |
| 24/07/24 | Pearson Street | All accessible hatched blue areas mapped (including outside project area). Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | Absent |
| 25/07/24 | The Rock | All accessible hatched blue areas mapped (including outside project area). Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. 1 recorded visually. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | Absent |
| 25/07/24 | Uranquinty | All accessible hatched blue areas mapped (including outside project area). | Absent |





| Date | Site | Results | Sloane's Froglet Presence |
|----------|----------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------|
| | | Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | |
| 25/07/24 | Pearson Street | All accessible hatched blue areas mapped (including outside project area). Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | Absent |

Incidental pest species found on sites: Nil

Incidental species found on sites:

- Unidentified Owl : Pearson Street
- Unidentified fish, maybe carp : Pearson Street
- Pacific Black Duck (Anas superciliosa): The Rock

Follow Up

Vegetation photos were planned to be taken on the afternoon of the final day of surveys. However, the PO for team 2 was changed with late notice and work commenced an hour after the planned start time. Vegetation photos were completed at the southern end of the Uranquinty site. After these were taken, there was not enough daylight to take quality photos.

All sites were surveyed only within the project area for surveys on 22/07/24. Therefore, some sites were surveyed for only 3 nights (may require an additional night survey).



240414 Inland Rail Sloane's Froglet surveys Field Memo 29/7/24-01/08/24

By Julia Chabros, written on 02/08/2024

Fieldwork team 1

- Jonny Sweeney (Senior Ecologist)
- Julia Chabros (Graduate Ecologist)

Fieldwork dates

29/7/24-01/08/24

Fieldwork scope

- To conduct targeted surveys for Sloane's Froglet across three survey sites.:
 - Yerong Creek
 - o Bomen
 - o Harefield

Fieldwork Methodology


- The following methodology was conducted every 50 metres of mapped potential habitat:
 - Active listening (5 minutes)
 - Call playback (2 minutes)
 - Active listening (2 minutes)
 - Active searching (5 minutes)

Where acceptable habitat is available*

This methodology was applied in areas of habitat that contained water (standing / flowing) and vegetation within the ephemeral zone. Each site was surveyed for 4 nights. Areas that did not contain water were marked as "no suitable habitat" and were not re-surveyed.


Survey Results

| Site | Results | Sloane's Froglet Presence | Other frog species recorded |
|--------------|------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|-----------------------------|
| Yerong Creek | The northernmost dam was surveyed from the road due to fence blocking access. The middle dam did not contain habitat and was excluded from surveys. | Absent | No frogs calling. |





| Site | Results | Sloane's Froglet Presence | Other frog species recorded |
|-----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------|---------------------------------------------------------------------------|
| | The southern long patch was surveyed in a culvert from both sides of the road. In the western area of that patch, a fence blocked access further. To the east, no habitat was present and no surveys were required. Even more east was not accessible due to a fence, so it is uncertain whether there is habitat or not. | | |
| Bomen | NE dam likely contains polluted water from adjacent industrial plant. NW was not accessible. Central dam was not accessible or visible due to fence, but lots of non-target frogs (Eastern sign bearing froglets) were calling. No frogs calling and barely any water in the culverts. Lots of eastern sign bearing froglets calling, but dam not accessible due to fence. It appeared to have lots of wetland veg. | Absent | Eastern sign bearing froglets calling from the central and southern dams. |
| Harefield | The northernmost dam, between Byrnes road and Junee Harefield Road, was accessible and traversed around on foot. The smaller dam to the west was not accessible due to a fence. | Absent | Eastern sign bearing froglets calling from the northernmost dam only. |





| Site | Results | Sloane's Froglet Presence | Other frog species recorded |
|------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|-----------------------------|
| | The culvert running under Junee Harefield road and the train tracks was accessible but contained only small patches/puddles of water. The long linear survey area SE of Junee Harefield road was not accessible due to a fence. From the fence line, it looked like the paddock did not contain habitat so it was not surveyed from the road. The large, L-shaped survey area further south did not contain suitable habitat where we could see, but parts of it were not accessible. The southernmost dam was surveyed from the road, from behind a fence. | | |

Incidental pest animal species found on sites: Nil

Incidental species found on sites: Nil

Follow Up

All sites were surveyed 4 times, and do not need to be re-visited.



240414 Inland Rail Sloane's Froglet surveys Field Memo 29/7/24-01/8/24

Memo completed by Justin Solomons 26/07/24

Fieldwork scope

- To conduct targeted surveys for Sloane's Froglet across three survey sites.:
 - o Junee Yard
 - Olympic Highway
 - Kemp Street
 - o Junee 2 Illabo 1
 - o Junee 2 Illabo 2
 - Junee 2 Illabo 3

Fieldwork Methodology


- Stella O'Dwyer and Justin Solomons to attend sites listed above and conducted:
 - Active listening (5 minutes)
 - o Call playback (2 minutes)
 - Active listening (2 minutes)
 - Active searching (5 minutes)

Where acceptable habitat is available*

This methodology was applied in areas of habitat that contained water (standing / flowing) and vegetation within the ephemeral zone.


Survey Results

| Date | Site | Results | Sloane's Froglet Presence |
|----------|------------------------|----------------------------------------------------------------------------|------------------------------|
| 29/07/24 | Junee Yard | Ruled out site as appropriate habitat for Frogs. | Absent |
| 29/07/24 | Olympic Highway | Ruled out site as appropriate habitat for Frogs. | Absent |
| 29/07/24 | Kemp Street | Ruled out site as appropriate habitat for Frogs. | Absent |
| 29/07/24 | The Rock (week 2 site) | Follow up from missed survey effort from week 2 Eastern sign-bearing frog | Absent |






| Date | Site | Results | Sloane's Froglet Presence |
|----------|--------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|
| | | (Crinia parasignifiera) recorded aurally. | |
| 29/07/24 | Uranquinty (week 2 site) | Follow up from missed survey effort from week 2 Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. | Absent |
| 30/07/24 | Junee 2 Illabo 1 | All accessible hatched blue areas mapped (including outside project area). Some areas were not possible to access as they were inside private property. These sites were surveyed with Callplayback at fence line. Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | Absent |
| 30/07/24 | Junee 2 Illabo 2 | All accessible hatched blue areas mapped (including outside project area). Some areas were not possible to access as they were inside private property. These sites were surveyed with Callplayback at fence line. Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | Absent |






| Date | Site | Results | Sloane's Froglet Presence |
|----------|------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|
| 30/07/24 | Junee 2 Illabo 3 | All accessible hatched blue areas mapped (including outside project area). Some areas were not possible to access as they were inside private property. These sites were surveyed with Callplayback at fence line. Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | Absent |
| 30/07/24 | Pearson Street (Week 2 site) | Follow up from missed survey effort from week 2 Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | Absent |
| 31/07/24 | Junee 2 Illabo 1 | All accessible hatched blue areas mapped (including outside project area). Some areas were not possible to access as they were inside private property. These sites were surveyed with Callplayback at fence line. Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | Absent |





| Date | Site | Results | Sloane's Froglet Presence |
|----------|------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|
| 31/07/24 | Junee 2 Illabo 2 | All accessible hatched blue areas mapped (including outside project area). Some areas were not possible to access as they were inside private property. These sites were surveyed with Callplayback at fence line. Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | Absent |
| 31/07/24 | Junee 2 Illabo 3 | All accessible hatched blue areas mapped (including outside project area). Some areas were not possible to access as they were inside private property. These sites were surveyed with Callplayback at fence line. Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | Absent |
| 01/08/24 | Junee 2 Illabo 1 | All accessible hatched blue areas mapped (including outside project area). Some areas were not possible to access as they were inside private property. These sites were surveyed with Callplayback at fence line. Eastern sign-bearing frog | Absent |





| Date | Site | Results | Sloane's Froglet Presence |
|----------|------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|
| | | (Crinia parasignifiera) recorded aurally. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | |
| 01/08/24 | Junee 2 Illabo 2 | All accessible hatched blue areas mapped (including outside project area). Some areas were not possible to access as they were inside private property. These sites were surveyed with Callplayback at fence line. Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | Absent |
| 01/08/24 | Junee 2 Illabo 3 | All accessible hatched blue areas mapped (including outside project area). Some areas were not possible to access as they were inside private property. These sites were surveyed with Callplayback at fence line. Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | Absent |

Incidental pest species found on sites: Nil

Incidental species found on sites:

Inland Rail A2I Sloane's Froglet Surveys



Unidentified Owl: Junee 2 Illabo 2

Follow Up

Vegetation photos were taken across all sites and follow up vegetation photos for Uranquinty and Pearson Street were also taken.

One survey point at the Eastern end of the Junee 2 Illabo sites was missed on night 3 of surveys.



240414 Inland Rail Sloane's Froglet surveys Field Memo 05/08/24-09/08/24

Memo completed by Justin Solomons 08/08/24

Fieldwork scope

- To conduct targeted surveys for Sloane's Froglet across three survey sites.:
 - Junee 2 Illabo 1 (one additional night survey)
 - o Junee 2 Illabo 2 (one additional night survey)
 - Junee 2 Illabo 3 (one additional night survey)
 - Henty (one additional night survey)

Fieldwork Methodology


- Jonny Sweeney and Justin Solomons to attend sites listed above and conducted:
 - Active listening (5 minutes)
 - Call playback (2 minutes)
 - Active listening (2 minutes)
 - Active searching (5 minutes)

Where acceptable habitat is available*

This methodology was applied in areas of habitat that contained water (standing / flowing) and vegetation within the ephemeral zone.

Survey Results

| Date | Site | Results | Sloane's Froglet Presence |
|----------|-------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|
| 05/08/24 | Junee 2 Illabo 1 | One additional night survey picked up from week 3 Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | Absent |
| 05/08/24 | Junee to Illabo 2 | One additional night survey picked up from week 3 Eastern sign-bearing frog (Crinia parasignifiera) | Absent |





| Date | Site | Results | Sloane's Froglet Presence |
|----------|---------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|
| | | recorded aurally. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | |
| 05/08/24 | Junee to Illabo 3 | One additional night survey picked up from week 3 Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | Absent |
| 05/08/24 | Junee to Illabo 4 | Assisted team 2 with southern sites | Absent |
| 06/08/24 | Junee to Illabo 4 Day time obs | Day obs | Absent |
| 06/08/24 | Henty | One additional night survey picked up from week 2 | Absent |
| 07/08/24 | Junee 2 Illabo 1-3 Day time obs | Fieldwork plans changed due to lack of permission to enter private properties. | Absent |
| 08/08/24 | Demobilisation | Demobilised as land access was not organised and only two sites were available for night time surveys. | |

Incidental pest species found on sites: Nil

Incidental species found on sites: Nil

Inland Rail A2I Sloane's Froglet Surveys



Follow Up

Day time observations and night surveys may be required in private property areas that have adequate habitat within Junee to Illabo 1-3.



240414 Inland Rail Sloane's Froglet surveys Field Memo 05/08/24-08/08/24

By Julia Chabros, written on 12/08/2024

Fieldwork team 2

- Michael Cleland (Ecologist)
- Julia Chabros (Graduate Ecologist)

Fieldwork dates

• 05/08/24-08/08/24

Fieldwork scope

- To conduct targeted surveys for Sloane's Froglet across three survey sites:
 - Junee to Illabo 4
 - Junee to Illabo 5

Fieldwork Methodology

- The following methodology was conducted every 50 metres of mapped potential habitat:
 - Active listening (5 minutes)
 - Call playback (2 minutes)
 - Active listening (2 minutes)
 - Active searching (5 minutes)

Where acceptable habitat is available*

This methodology was applied in areas of habitat that contained water (standing / flowing) and vegetation within the ephemeral zone. Each site was surveyed for 4 nights. Areas that did not contain water were marked as "no suitable habitat" and were not re-surveyed, but were photographed during daytime habitat assessments.



Survey Results

| Site | Results | Sloane's Froglet Presence | Other frog species recorded |
|----------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|---------------------------------------------------------------------------|
| Junee to Illabo | All 5 dams were accessed from the road only – not accessible due to fences. | Absent | Eastern Sign Bearing and Common Eastern Froglets calling. |
| | Sections of the long polygons were ruled out as "no available habitat". | | |
| | The largest dam had a high abundance of common frog species, as well as native veg and trees surrounding it. | | |
| Junee to Illabo 5 | The NE site was not suitable habitat. The central site (a small dam) was surveyed from the road, and not accessible due to a fence. | Absent | Eastern sign bearing froglets calling from the central and southern dams. |
| | The large survey area, SW in Junee to Illabo 5: southern side of the tracks was surveyed in full. Some areas were marked as not suitable habitat. The northern side of the tracks was not fully accessible due to a fence. Surveys were conducted on | | |
| | one side of the dam only (but ~20 metres from the edge), and following the drainage line. | | |

Incidental pest animal species found on sites: Nil

Incidental species found on sites: Nil

Follow Up

All accessible sites were surveyed 4 times and do not need to be re-visited.

Inland Rail A2I Sloane's Froglet Surveys



Inland Rail A2I Sloane's Froglet Surveys



240414 Inland Rail Sloane's Froglet surveys Field Memo 19/08/24-22/08/24

By Julia Chabros, written on 29/08/2024

Fieldwork team 2

- Marcus Hoskin (Ecologist)
- Julia Chabros (Graduate Ecologist)

Fieldwork dates

19/08/24-22/08/24

Fieldwork scope

- To conduct targeted surveys for Sloane's Froglet across three survey sites, in places previously not accessible due to private property boundaries:
 - Yerong Creek
 - o The Rock
 - o Bomen (1 night by Team 1 and 3 nights by Team 2)
- Plus one night of surveys at the following sites:
 - Table Top
 - Henty

Fieldwork Methodology

- The following methodology was conducted every 50 metres of mapped potential habitat:
 - Active listening (5 minutes)
 - o Call playback (2 minutes)
 - Active listening (2 minutes)
 - Active searching (5 minutes)

Where acceptable habitat is available*

This methodology was applied in areas of habitat that contained water (standing / flowing) and vegetation within the ephemeral zone. Each site was surveyed for 4 nights, except for Table Top and Henty, where 3 nights were already surveyed in the previous week and only one survey per site was required. Bomen was surveyed once by Team 1 and three times by Team 2. Areas that did not contain water were marked as "no suitable habitat" and were not re-surveyed, but were photographed during daytime habitat assessments.

Inland Rail A2I Sloane's Froglet Surveys



Survey Results

| Site | Results | Sloane's Froglet Presence | Other frog species recorded |
|--------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|---------------------------------------------------------------------------|
| Yerong Creek | All dams had water in them. Many common species calling from the southernmost dam. | Absent | Eastern Sign Bearing Froglets and Bibron's Toadlets calling. |
| The Rock | Lots of common frogs calling, particularly from the stream that led away from the dams and was just outside of the survey area. Lots of veg on the banks of the dams, including cumbungi and juncus. Waterbirds, such as whitefaced heron and ducks were observed during day obs. | Absent | Eastern sign bearing froglets, Bibron's toadlets and Spotted Marsh Frogs, |
| Bomen | Common frogs calling and observed. One of the dams had dirty water covered in scum and a bad small, and this was excluded from the surveys (no frogs calling from this one). | Absent | |
| Table Top | Common species recorded, 4/4 survey nights are now completed. Crayfish observed in the water, indicating good water quality. | Absent | |
| Henty | Common species recorded, 4/4 survey nights are now completed. | Absent | |

Incidental pest animal species found on sites: Nil

Incidental species found on sites: Nil

Follow Up

4 survey nights and day observations have now been completed at all sites.

Inland Rail A2I Sloane's Froglet Surveys





240414 Inland Rail Sloane's Froglet surveys Field Memo 19/08/24-22/08/24

Memo completed by Justin Solomons 23/08/24

Fieldwork scope

- To conduct targeted surveys for Sloane's Froglet across three survey sites.:
 - o Junee 2 Illabo 3 Private property areas
 - o Junee 2 Illabo 4 Private property areas
 - o Junee 2 Illabo 5 Private property areas
 - o Junee 2 Illabo 2 (pick up from team 2)

Fieldwork Methodology


- Jonny Sweeney and Justin Solomons to attend sites listed above and conducted:
 - Active listening (5 minutes)
 - o Call playback (2 minutes)
 - Active listening (2 minutes)
 - Active searching (5 minutes)

Where acceptable habitat is available*

This methodology was applied in areas of habitat that contained water (standing / flowing) and vegetation within the ephemeral zone.

Survey Results

| Date | Site | Results | Sloane's Froglet Presence |
|----------|------------------------------|------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|
| 19/08/24 | Junee 2 Illabo 3 - 5 | Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | Absent |
| 20/08/24 | Junee to Illabo 3-5 Day obs | Day obs Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | Absent |





| Date | Site | Results | Sloane's Froglet Presence |
|----------|---------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|
| 21/08/24 | Junee to Illabo 2 | Assisted Team 2 with J2I – 2 Northern sites Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. Bibron's Froglet (Pseudophryne bibronii) | Absent |
| 21/08/24 | Junee 2 Illabo 3-5 Day time obs | recorded aurally. Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. | Absent |
| | | Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | |
| 22/08/24 | Junee to Illabo 2 | Assisted Team 2 with J2I – 2 Northern sites Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. | Absent |
| 22/08/24 | Junee to Illabo 3-5 | Eastern sign-bearing frog (Crinia parasignifiera) recorded aurally. Bibron's Froglet (Pseudophryne bibronii) recorded aurally. Sudell's Frog (Neobatrachus sudelli) recorded aurally. | Absent |
| 23/08/24 | Demobilisation | Demobilised back home | |

Inland Rail A2I Sloane's Froglet Surveys

Incidental pest species found on sites: Nil

Incidental species found on sites: Nil

Follow Up

Nil



Inland Rail A2I Sloane's Froglet Surveys



Inland Rail A2I Sloane's Froglet Surveys





NGH Pty Ltd

NSW • ACT • QLD • VIC

ABN 31 124 444 622 ACN 124 444 622

E: ngh@nghconsulting.com.au

GOLD COAST

2B 34 Tallebudgera Creek Road Burleigh Heads QLD 4220

T. (07) 3129 7633

SYDNEY REGION

Unit 17, 21 Mary Street Surry Hills NSW 2010

T. (02) 8202 8333

BEGA

Suite 11, 89-91 Auckland Street (PO Box 470) Bega NSW 2550

T. (02) 6492 8333

MELBOURNE

Level 14, 10-16 Queen Street Melbourne VIC 3000

T: (03) 7031 9123

TOWNSVILLE

Level 4, 67-75 Denham Street Townsville QLD 4810

T. (07) 4410 9000

BRISBANE

T3, Level 7, 348 Edward Street Brisbane QLD 4000

T. (07) 3129 7633

NEWCASTLE - HUNTER & NORTH COAST

Level 1, 31-33 Beaumont Street Hamilton NSW 2303

T. (02) 4929 2301

WAGGA WAGGA - RIVERINA & WESTERN NSW

35 Kincaid Street (PO Box 5464) Wagga Wagga NSW 2650

T. (02) 6971 9696

CANBERRA

Unit 8, 27 Yallourn Street (PO Box 62) Fyshwick ACT 2609

T. (02) 6280 5053

SUNSHINE COAST

Building 1, 30 Chancellor Village Boulevard Sippy Downs QLD 4556

T: 13 54 93

WODONGA

Unit 2, 83 Hume Street (PO Box 506) Wodonga VIC 3690

T. (02) 6067 2533





APPENDIX E

ISC Rating



The below detailed compliance table contains relevant IS credits and where they are addressed in this plan or references external documents that fulfill the ISC credit criteria.

TABLE A1: ISC ECO-1 & ECO-2 COMPLIANCE TABLE

| ISC CREDIT | | WHERE ADDRESSED |
|--------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| ECOLOGICAL | VALUE – ECO-1 | · |
| LEVEL 1 | | |
| Benchmark | The ecological value of the infrastructure site is maintained. | Section 3.4 Section 6.9 Section 6.11 Environmental Work Method Statements (EWMS). Fauna Connectivity Strategy. Fauna Handling and Rescue Procedure. Sensitive Area Plans. Pre and post clearing reports. Unexpected Threatened Species Finds Procedure. |
| | 'An ecological management plan (or similar) must be developed and implemented that prioritises minimising ecological impacts, and is managed, reviewed or audited by a suitably qualified professional. | Section 3.3 Section 1.4.2 |
| LEVEL 2 & 3 | | |
| Benchmark | The ecological value of infrastructure site is enhanced by 0 to 20%. Fractions of Levels may be achieved on a sliding scale up to 20% for Level 3. | Section 6.7 Landscape Design Reports. Urban Design and Landscape Plan. Site-specific Rehabilitation Strategy. Inland Rail Landscape and Rehabilitation Framework Inland Rail Landscape and Rehabilitation Strategy. Inland Rail Landscape Specification. |
| | There are two methods for ecological assessment which are allowed under this credit. The first is a simple assessment using an 'Ecological Value Calculator'. This approach may be used where Ecology has low or medium Materiality. | Note second method using 'Ecological Impact Assessment' (EcIA) has adopted. |
| from v1.2 ISC Technical Manual | The second method is a more sophisticated approach using 'Ecological Impact Assessment' (EcIA). This method must be used where Ecology has medium, high or very high Materiality and/or to claim offsets. | EIS Biodiversity Development Assessment Report |
| | EcIA must be managed, reviewed or audited by a suitably qualified professional. | EIS Biodiversity Development Assessment Report. |



| ISC CREDIT | | WHERE ADDRESSED |
|--------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Must Statement from v1.2 ISC Technical Manual | It must be demonstrated that it is "probable" (at least a 50% chance) that the enhancement can be achieved. | Section 6.7 Urban Design and Landscape Plan. Site-specific Rehabilitation Strategy. Inland Rail Landscape and Rehabilitation Framework Inland Rail Landscape and Rehabilitation Strategy. Inland Rail Landscape Specification. |
| from v1.2 ISC Technical | Offsets used under this credit must be calculated and assessed, as a priority, in accordance with any existing regional policy that sets out specific measurement criteria. | EIS Biodiversity Development Assessment Report.Biodiversity Credit Report. |
| from v1.2 ISC | Evidence must be provided that demonstrates how ecological values have been maintained or enhanced, using quantifiable metrics where possible. These metrics must be specific to the features and values impacted and developed by a suitably qualified professional. | Section 6.7 Urban Design and Landscape Plan. Site-specific Rehabilitation Strategy. Inland Rail Landscape and Rehabilitation Framework Inland Rail Landscape and Rehabilitation Strategy. Inland Rail Landscape Specification. |
| from v1.2 ISC | If financial or indirect offsets are proposed, evidence must be provided that the offset provided will benefit the impacted matter/s. | IR Biodiversity Offset Strategy and evidence of credit retirement. |
| from v1.2 ISC Technical Manual | If land-based offsets are proposed, evidence must also be provided that shows what actions will be implemented on the offset site to achieve maintenance or enhancement, ensuring these are additional to baseline duty of care. | Appendix D. |
| from v1.2 ISC | Evidence must also be provided that demonstrates how the offset area will be protected and managed in perpetuity for conservation purposes. | Section 6.8 IR Biodiversity Offset Strategy and evidence of credit retirement. |
| from v1.2 ISC | Evidence must also be provided that demonstrates how the offset area will be protected and managed in perpetuity for conservation purposes. | Section 1.6 |
| from v1.2 ISC | If it is desired to exceed the requirements in any existing region policy or such processes do not exist, then: It must be demonstrated that the offsets are permanent and that management regimes are in place to ensure stated outcomes are achieved or maintained. | EIS Biodiversity Development Assessment Report. Biodiversity Credit Report. |
| from v1.2 ISC | The extent of the enhancement must be quantified by a SQP. It must be demonstrated that the ecological value of the entire site is maintained or | Section 7 IR Biodiversity Offset Strategy and evidence of credit retirement. |
| | enhanced. | |

LEVEL 1



| ISC CREDIT | | WHERE ADDRESSED |
|---------------------|---------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------|
| Benchmark | There is a low or moderate degree of existing | Section 5.2.4 |
| | habitat connectivity identified. | Fauna Connectivity Strategy. |
| Benchmark | The existing degree of habitat connectivity is | Section 6.8 |
| | enhanced (offsetting allowed). | Section 6.10 |
| | | Biodiversity Credit Report. |
| | | Fauna Connectivity Strategy. |
| | | Urban Design and Landscape Plan. |
| | | Detailed Design Drawings showing Flora and Fauna No Go Zones, clearance areas, and construction impact zones. |
| Must Statement | Offsets used under this credit must be calculated | Biodiversity Credit Report. |
| Technical | and assessed, as a priority, in accordance with any existing regional policy that sets out specific measurement criteria. | EIS Biodiversity Development Assessment Report |
| Must Statement | It must be demonstrated that the offsets are | IR Biodiversity Offset Strategy and evidence of |
| from v1.2 ISC | permanent and that management regimes are in | credit retirement |
| | place to ensure stated outcomes are achieved or | |
| Manual | maintained. | |
| | If financial or indirect offsets are proposed, | IR Biodiversity Offset Strategy and evidence of and it retirement. |
| | evidence must be provided that the offset provided will benefit the impacted matters. | credit retirement |
| Manual | will beliefft the impacted matters. | |
| Must Statement | t Evidence must be provided that shows how the | IR Biodiversity Offset Strategy and evidence of |
| from v1.2 ISC | offset achieves a maintenance or enhancement | credit retirement |
| | outcome using accepted metrics that are currently | |
| | in use in various jurisdictions or are developed by a SQP. | |
| | | ID Die diversity Officet Othertony and evidence of |
| | If land-based offsets are proposed, evidence must also be provided that shows what actions will be | IR Biodiversity Offset Strategy and evidence of credit retirement |
| | implemented on the offset site to achieve | or out roth of the |
| Manual | maintenance or enhancement. | |
| Must Statement | Evidence must also be provided that demonstrates | IR Biodiversity Offset Strategy and evidence of |
| from v1.2 ISC | how the offset area will be protected in perpetuity | credit retirement |
| Technical Manual | for conservation purposes. | |
| LEVEL 2 | | |
| | There is a low or moderate degree of existing | Section 4. |
| | habitat connectivity identified. | Section 4. |
| | AND | • Section 6.8 |
| | The existing degree of habitat connectivity is | Section 6.10 |
| | enhanced (offsetting allowed). | Biodiversity Credit Report. |
| | | Detailed Design Drawings showing Flora and |
| | | Fauna No Go Zones, clearance areas, |
| | | |
| | | construction impact zones, native vegetation and |
| | | |



| ISC CREDIT | | W | HERE ADDRESSED |
|-----------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | There is a high degree of existing habitat connectivity identified. AND The existing degree of habitat connectivity is maintained (offsetting allowed). | | Section 4. Section 5.2.4 Section 6.8 Section 6.10 Biodiversity Credit Report. Detailed Design Drawings showing Flora and Fauna No Go Zones, clearance areas, construction impact zones, native vegetation and environmental aspects. Environmental Impact Statement. Fauna Connectivity Strategy. Urban Design and Landscape Plan. |
| from v1.2 ISC | The degree of habitat connectivity before and after infrastructure development must be based on ecological assessment. | • | EIS Biodiversity Development Assessment Report. |
| | It must be demonstrated that it is "probable" (at least a 50% chance) that the enhancement can be achieved. | | Section 6.7 Urban Design and Landscape Plan. Site-specific Rehabilitation Strategy. Inland Rail Landscape and Rehabilitation Framework Inland Rail Landscape and Rehabilitation Strategy Inland Rail Landscape Specification. |
| Must Statement from v1.2 ISC Technical Manual | Voluntary offsetting beyond regulatory requirements may provide evidence towards enhancement. The extent of the enhancement must be quantified by a SQP. It must be demonstrated that the ecological value of the entire site is maintained or enhanced. | - | Section 7 Construction Biodiversity Monitoring Program. |
| LEVEL 3 | | | |
| Benchmark | There is a low or moderate degree of existing habitat connectivity identified. AND The existing degree of habitat connectivity is enhanced (with no offsetting) | • | Not targeting |
| | OR | | |
| | There is a high degree of existing habitat connectivity identified. AND The existing degree of habitat connectivity is maintained (with no offsetting). | | Not targeting |





APPENDIX F

PSR and **CEMF** Requirements



PSR and CEMF requirements are internal requirements beyond the Infrastructure Approval. These have been included for internal quality control purposes and do not form part of management plan.

TABLE A2: INTERNAL PSRS AND CEMF REQUIREMENTS APPLICABLE TO THIS PLAN

| NO. | REQUIREMENT | WHERE ADDRESSED |
|---------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| PSR Appendix B Section 5.4.10 | Without limiting the environmental management requirements in Annexure F, section 6.1.1, all D&C Works in watercourses shall comply with the NSW Department of Primary Industries Standards: Policy and Guidelines for Fish Friendly Waterway Crossings; they do Fish Need to Cross the Road? Fish Passage Requirements for Waterway | Section 6.3 |
| PSR Appendix C Section 6.1.3 | Crossings; and Policy and Guidelines for Fish Habitat Conservation and Management Update The key environmental risk areas which the Contractor shall consider in development of the Construction Environmental Management Plan include, but are not limited to: b) pest and weed seed management c) fauna management, including terrestrial and aquatic fauna connectivity d) flora management e) biosecurity matters, including fire ants (where required) (refer to 0-0000-900-EEC-00-ST-1000 Biosecurity Strategy, Appendix A); | b) Section 4.2 Section 6.4 c) Section 4.1 Section 5.2 Section 6.6 Section 6.9 Section 6.10 Section 6.11 d) Section 4.1 Section 5.2 Section 6.1 Section 6.7 e) Section 4.2 Section 6.4.1 |
| PSR Appendix C Section 8.6.8 | The Contractor shall maintain any existing fauna fencing for the duration of the Contractor's Activities. | Section 4.1.3 Section 6.11 |



| NO. | REQUIREMENT | WHERE ADDRESSED |
|-------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------|
| Table 3, A2P CEMF Specification Biodiversity | Contractor to confirm clearing footprint at least 80 days prior to being issued for construction and provide to ARTC | Section 6.1 |
| Table 3, A2P CEMF Specification Biodiversity | Vegetation survey to be completed | Section 6.1.1 |
| Table 3, A2P CEMF Specification Biodiversity | The construction corridor and areas declared as 'No Go Zones' shall be clearly protected/delineated. 'No Go Zones' may be identified through the installation of permanent or temporary fencing and appropriate signage, or an alternative solution agreed with ARTC. This will be included as a hold point in all clearing ITPs | Section 6.1 |
| Table 3, A2P CEMF Specification Biodiversity | Disturbance footprint/Construction Impact Zone to be delineated by a surveyor before works commence. This will be a hold point | Section 6.1 |
| Table 3, A2P CEMF Specification Biodiversity | A suitably qualified and experienced ecologist shall be available to the Contractor at all times and be on Site during high-risk activities (i.e. vegetation clearing) | Section 6.1.4 |
| Table 3, A2P CEMF Specification Biodiversity | A suitability qualified and experienced spotter catcher shall be present to survey and inspect prior, during and post vegetation clearing activities | Section 6.1.4 |
| Table 3, A2P CEMF Specification Biodiversity | Verification that the area cleared is correct and within the boundary and GIS data provided to ARTC | Section 6.1.5 |
| Table 3, A2P CEMF Specification Biodiversity | 'No Go Zones' are to be in project induction and toolbox with high-risk activities. | Section 7.2 |
| Table 3, A2P CEMF Specification Biodiversity | 'No Go Zones' identified on site environmental plans | Section 6.1 |
| Table 3, A2P CEMF Specification Biodiversity | Implement Site management procedures, such as wildlife rescue or equivalent, to respond to events when fauna enter construction worksites and provide to ARTC | Section 6.6 Appendix B: Fauna Handling and Rescue Procedure |



| NO. | REQUIREMENT | WHERE ADDRESSED |
|------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------|
| Table 3, A2P CEMF | A contact list of fauna handlers and local vet/wildlife organisations is to be developed and maintained that considers | Section 6.6 |
| Specification Biodiversity | their location and travel time with respect to active work areas | Appendix B: Fauna Handling and Rescue Procedure |
| Table 3, A2P CEMF | All personnel must drive to the conditions, speed limits and road rules. Any fauna strikes must be reported to ARTC as | Section 5.2.5 |
| Specification Biodiversity | soon as possible | Section 6.11 |
| | | Driver Code of Conduct |
| | | Fauna Handling Record Sheet |
| Table 3, A2P CEMF | All machinery/vehicle/materials/buildings/equipment arrive clean upon Site entry and have weed, and seed declaration or equivalent completed by suitably qualified person | Section 6.11 |
| Specification Biosecurity | | Vehicle hygiene register |
| Table 3, A2P CEMF Specification Biosecurity | Any movement restrictions (e.g. fire ant zone restrictions) will be assessed prior to undertaken the movement of high-risk material (e.g. soil, gravel, ballast) | Section 6.4.1 |
| Table 3, A2P CEMF | Vehicle hygiene register to be maintained | Section 6.11 |
| Specification Biosecurity | | Vehicle hygiene register |
| Table 3, A2P CEMF Specification Biosecurity | Pre-clearance disturbance survey including mapping of weeds and development of suitable controls to manage them | Section 6.1.3 |
| Table 3, A2P CEMF | Weekly inspection shall include weed and pest monitoring | Section 6.11 |
| Specification Biosecurity | | Weekly environmental inspection checklist |
| Table 3, A2P CEMF | Pest management contractor available at all times and provide treatment records to ARTC upon request | Section 6.4 |
| Specification General Construction | | Section 6.11 |

ALBURY TO ILLABO | A2I






| NO. | REQUIREMENT | WHERE ADDRESSED |
|------------------------------------|------------------------------------------------------------------------------------------------------|-----------------------------|
| Table 4, Environmental Hold Points | Flora and Fauna No Go Zones assessed and protected/delineated prior to commencing any relevant works | Section 6.1 |
| Table 4, Environmental Hold Points | Disturbance footprint/Construction Impact Zone to be delineated by a surveyor | Section 6.1 Section 6.11 |






APPENDIX G

Construction Biodiversity Monitoring Program









Document Control

| DOCUMENT TITLE: | Construction Biodiversity Monitoring Program – Stage C | | | |
|-----------------|--------------------------------------------------------------------|--|----------|----------------------|
| DOCUMENT OWNER: | Chris Standing – Environment, Approvals and Sustainability Manager | | | |
| PREPARED BY: | Steven Dando TITLE: Environmental Approvals Advisor | | | |
| SIGNATURE: | S.Dando | | DATE: | 23/09/2025 |
| REVIEWED BY: | Alison Kriegel TITLE: | | Environm | ental Approvals Lead |
| SIGNATURE: | Wism Kingel | | DATE: | 23/09/2025 |

Approved by

| NAME | TITLE | SIGNATURE | DATE |
|---------------|------------------|-----------|------------|
| Andy Williams | Project Director | Alle | 23/09/2025 |

Revision History

| REVISION | REVISION DATE | AMENDMENT | DATE TO CLIENT |
|----------|---------------|------------------------------|----------------|
| А | 17/09/2025 | Prepared to consider Stage C | 17/09/2025 |
| 0 | 23/09/2025 | For ER approval | 23/09/2025 |

Disclaimer: This document has been prepared by Martinus. Use of this document shall be subject to the terms of the relevant contract with Martinus. The electronic file of this current revision is the controlled copy. This file is stored on Martinus' server located at Head Office, Unit 1, 23-27 Waratah St, Kirrawee, NSW.

This document is the property of and contains proprietary information owned by Martinus. No permission is granted to publish, reproduce, transmit or disclose to another party, any information contained in this document, in whole or in part, without prior written permission from the issuing authority.

For the purpose of this document, Martinus refers to the Martinus Group of companies.

This document is uncontrolled when printed.



TABLE OF CONTENTS

| GLO | 9SSARY | 4 |
|--------------|-----------------------------------------|-----|
| 1 | INTRODUCTION | |
| 1.1 | Project overview | |
| 1.1.1 | • | |
| 1.1.2 | | |
| 1.2 | Scope of this Monitoring Program | |
| 1.3 | Endorsement and approval | |
| 1.4 | Consultation | |
| 1.5 | Responsibilities | |
| 1.6 | Purpose | |
| 1.7 | Environmental requirements | |
| 1.7.1 | Guidelines and standards | 8 |
| 1.7.2 | | |
| 1.7.3 | Updated Mitigation Measures | ç |
| 2 | BASELINE DATA | 4.0 |
| 2 .1 | Existing environment | |
| 2.1 2.1.1 | 3 | |
| 2.1.1 | , ,,, | |
| 2.1.3 | | |
| 2.1.4 | | |
| 2.1.5 | | |
| 2.2 | Additional baseline data to be obtained | |
| 2.2.1 | | |
| | , | |
| | MONITORING PROCEDURE | |
| 3.1 | Biodiversity monitoring | |
| 3.2 | Adaptive management | 16 |
| 4 | REPORTING | 18 |
| 4.1 | | |

A2I | ALBURY TO ILLABO

CONSTRUCTION BIODIVERSITY MONITORING PROGRAM - STAGE C



LIST OF TABLES

| Table 1: Conditions of approval relevant to this Monitoring Program | 8 |
|-----------------------------------------------------------------------------------------------------------------------|------|
| Table 2: Extent of White Box - Yellow Box - Blakely's Red Gum Grassy Woodland and Derived Native Grassland threatened | |
| ecological community within the study area | . 10 |
| Table 3: species with suitable habitat within the proposal site | |
| Table 4: Threatened fauna recorded in the study area | |
| Table 5: Biodiversity monitoring procedure | . 14 |



GLOSSARY

| TERM | DEFINITION |
|---------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| A2I | Albury to Illabo section of the Inland Rail project |
| ARTC | Australian Rail Track Corporation |
| BAM | Biodiversity Assessment Method |
| BC Act | Biodiversity Conservation Act 2016 (NSW) |
| BCS | Biodiversity, Conservation and Science Directorate of DCCEEW (former) |
| BDAR, Revised | Biodiversity Development Assessment Report that comprises Part 1 and Part 2 of the Revised Technical Paper 8: Biodiversity Development Assessment Report (WSP, February 2024) |
| СВМР | Construction Biodiversity Management Plan |
| CEMP | Construction Environmental Management Plan |
| CMP | Construction Monitoring Plan |
| СоА | Conditions of Approval |
| Construction | Includes work required to construct the CSSI as defined in the Project Description described in the documents listed in Condition A1 including commissioning trials of equipment and temporary use of any part of the CSSI but excluding Low Impact Work which is carried out or completed prior to approval of the CEMP. |
| CPHR | Conservation Programs, Heritage and Regulation Group of the NSW Department of Climate Change, Energy, the Environment and Water (formerly BCS) |
| CSSI | Critical State significant infrastructure |
| DAWE | Department of Agriculture, Water and Environment |
| DCCEEW | NSW Department of Climate Change, Energy, the Environment and Water |
| DCCEEW (Cth) | Commonwealth Department of Climate Change, Energy, the Environment and Water |
| DEC | Department of Environment and Conservation |
| DPHI | Department of Planning, Housing and Infrastructure |
| DPI | Department of Primary Industries |
| DPIE | Department of Planning, Industry and Environment |
| EAD | Environmental Assessment Documentation that includes: Inland Rail – Albury to Illabo Environmental Impact Statement (ARTC, August 2022); Albury to Illabo Response to Submissions (ARTC, November 2023); Albury to Illabo Preferred Infrastructure Report (ARTC, November 2023); |



| TERM | DEFINITION |
|-----------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | Albury to Illabo Preferred Infrastructure Report Response to Submissions (ARTC, February 2024); Inland Rail – Albury to Illabo (SSI-10055) Response to request for additional information – Air Quality Assessment (letter dated 1 May 2024); Part 1 - Revised Technical Paper 8: Biodiversity Development Assessment Report (WSP, February 2024); Part 2 - Revised Technical Paper 8: Biodiversity Development Assessment Report (WSP, February 2024); Kemp Street Bridge Enhancement Site Modification (June 2025); Albury to Illabo Kemp Street Bridge Enhancement Site Modification Clarification (July 2025); Albury to Illabo Kemp Street Bridge Modification Noise and Vibration Impact Assessment (August 2025). |
| EIS | Environmental Impact Statement |
| Environmental Representative (ER) | The Environmental Representative(s) for the CSSI approved by the Planning Secretary |
| EP&A Act | Environmental Planning and Assessment Act 1979 (NSW) |
| EPBC Act | Environment Protection and Biodiversity Conservation Act 1999 (Federal) |
| ESR | Environmental Site Representative |
| IBRA | Interim Biogeographic Regionalisation for Australia |
| KFH | Key Fish Habitat |
| Km | Kilometre |
| LGAs | Local government areas |
| NSW | New South Wales |
| OEH | Office of Environment and Heritage (former) |
| PCT | Plant Community Type |
| PIR | Preferred Infrastructure Report |
| RtS | Response to Submissions |
| SEARs | Secretary's Environmental Assessment Requirements |
| SMART | Specific, measurable, achievable, relevant and time-based |
| SSI | State significant infrastructure |
| This Monitoring Plan | CBMP – Stage C Appendix G: Construction Biodiversity Monitoring Program |
| UMM | Updated Mitigation Measure, as amended in Albury to Illabo Kemp Street Bridge Enhancement Site Modification (June 2025) |



1 INTRODUCTION

1.1 Project overview

Inland Rail is an approximate 1,600 kilometres (km) freight rail network that will connect Melbourne and Brisbane via regional Victoria, New South Wales (NSW) and Queensland. The Inland Rail route would involve using approximately 1,000 km of existing track (with enhancements and upgrades where necessary) and 600 km of new track, passing through 30 local government areas (LGAs). Inland Rail will accommodate double-stacked freight trains up to 1,800 metres (m) long and 6.5 m high.

The Australian Government has confirmed that Inland Rail is an important project to meet Australia's growing freight task, improve road safety and help decarbonise the economy. Inland Rail will enhance our national freight and supply chain capabilities, connecting existing freight routes through rail, roads and ports, and supporting Australian's growth. Inland Rail is being delivered by Australian Rail Track Corporation (ARTC).

Comprising 12 sections, a staged approach is being undertaken to deliver Inland Rail. Each of these projects can be delivered and operated independently with tie-in points to the existing railway. Work south of Parkes has been prioritised, which will enable Inland Rail to initially connect to existing rail networks between Melbourne, Sydney, Perth and Adelaide via Parkes and Narromine. The Parkes to Narromine and Narrabri to North Star Phase 1 sections are complete.

The Inland Rail project will enable enhancement works to structures and sections of track along 185 km of the existing operational standard-gauge railway in the Albury to Illabo (A2I) section of the Inland Rail program (the project). Enhancement works are required to provide the increased vertical and horizontal clearances required for double-stacked freight trains. Works would include track realignment, lowering and/or modification within the existing rail corridor, modification, removal or replacement of bridge structures (rail, road and/or pedestrian bridges), raising or replacing signal gantries, level-crossing modifications and other associated works.

A detailed project description is provided in Section 4 of the Construction Environmental Management Plan (CEMP).

1.1.1 Planning context

The Inland Rail – Albury to Illabo project (the project) is declared State significant infrastructure (SSI) and critical State significant infrastructure (CSSI) under Division 5.2 of the *Environmental Planning and Assessment Act 1979* (NSW) (EP&A Act). The project is permissible without development consent and is subject to assessment and approval by the NSW Minister for Planning and Public Spaces.

An environmental impact statement (EIS) was prepared to support ARTC's application for approval of the proposal in accordance with the requirements of the EP&A Act and the environmental assessment requirements of the Secretary of the (then) NSW Department of Planning, Industry and Environment (the SEARs) (now the Department of Planning, Housing and Infrastructure (DPHI)).

The EIS was placed on public exhibition from 17 August 2022 to 28 September 2022. During the exhibition period, interested stakeholders and members of the community were able to review the EIS online, participate in consultation and engagement activities held by ARTC, and make a written submission to the (then) Department of Planning and Environment for consideration in its assessment of the proposal.

In accordance with section 5.17(6)(b) of the EP&A Act, on 13 April 2023 the Planning Secretary directed ARTC to submit a Preferred Infrastructure Report (PIR) that provides further assessment of traffic and transport, noise and vibration, and air quality impacts. The PIR was also prepared to consider changes to the exhibited proposal that have arisen as a consequence of these further assessments and related submissions.

As a result of the potential for impacts on protected matters, the project was referred to the then Australian Government Minister for the Environment on 2 June 2020 (EPBC Referral No 2020/8670). On 29 June 2020, the Australian Government Department of Agriculture, Water and Environment (DAWE) notified that the proposal is a not controlled action, and hence approval under the EPBC Act is not required. In July 2022, the department changed its name to become the Department of Climate Change, Energy, the Environment and Water (DCCEEW).

A modification report (Kemp Street Bridge Enhancement Site Modification, Inland Rail June 2025) was prepared to revise the replacement road and pedestrian bridge arrangement over the railway line at the Kemp Street bridge enhancement site in Junee to now provide a single structure. The Modification was approved by the delegate of the NSW Minister for Planning and Public Spaces on 13 August 2025.

1.1.2 Statutory context and approval

The Inland Rail – Albury to Illabo project was assessed as part of the following documents:



- Inland Rail Albury to Illabo Environmental Impact Statement (ARTC, August 2022);
- Albury to Illabo Response to Submissions (ARTC, November 2023);
- Albury to Illabo Preferred Infrastructure Report (ARTC, November 2023);
- Albury to Illabo Preferred Infrastructure Report Response to Submissions (ARTC, February 2024);
- Inland Rail Albury to Illabo (SSI-10055) Response to request for additional information Air Quality Assessment (letter dated 1 May 2024);
- Part 1 Revised Technical Paper 8: Biodiversity Development Assessment Report (WSP, February 2024);
- Part 2 Revised Technical Paper 8: Biodiversity Development Assessment Report (WSP, February 2024);
- Kemp Street Bridge Enhancement Site Modification (June 2025);
- Albury to Illabo Kemp Street Bridge Enhancement Site Modification Clarification (July 2025);
- Albury to Illabo Kemp Street Bridge Modification Noise and Vibration Impact Assessment (August 2025).

Together these documents are referred to as the Environmental Assessment Documentation (EAD).

Part 1 and Part 2 of the Revised Technical Paper 8: Biodiversity Development Assessment Report (WSP, February 2024) are collectively referred to as the Revised Biodiversity Development Assessment Report (Revised BDAR).

The original approval for the project under the EP&A Act was granted by the Minister for Planning on 08 October 2024.

1.2 Scope of this Monitoring Program

The scope of this Construction Biodiversity Monitoring Program (this Monitoring Program) is to describe how Martinus Rail will monitor potential biodiversity impacts during construction of the project. This Program is an appendix of the Construction Biodiversity Management Plan – Stage C (CBMP).

SMART (Specific, Measurable, Achievable, Realistic and Timely) principles will be considered and applied during the preparation and ongoing implementation of this Monitoring Program.

This Monitoring Program is applicable to all activities during construction of the project, including all areas where physical works will occur or areas that may otherwise be impacted by the construction works. All Martinus Rail staff and subcontractors are required to comply with the requirements of this Monitoring Program and related environmental management plans, over the full duration of the construction program.

Operational biodiversity impacts and operational monitoring requirements do not fall within the scope of this Monitoring Program and therefore are not included within the processes contained herein.

1.3 Endorsement and approval

In accordance with CoA A22(d) and CoA A27(e), this Monitoring Program will be submitted to the ER for endorsement prior to submission to the Planning Secretary for approval.

Construction will not commence until the relevant CEMP(s) and Sub-plans have been endorsed by the ER and approved by the Planning Secretary (as applicable and as identified in the Construction Environmental Management Framework approved under CoA C16), in accordance with CoA C15.

This Monitoring Program, including any amendments, will be implemented throughout construction.

1.4 Consultation

In accordance with CoA C26, this Monitoring Program has been prepared in consultation with Conservation Programs, Heritage and Regulation (CPHR) (former Biodiversity, Conservation and Science Directorate (BCS)).

The consultation report prepared for the Stage B CBMP outlines the location in which stakeholders' responses have been addressed.

1.5 Responsibilities

Martinus Rail has appointed a project ecologist who is suitably qualified to oversee the construction of the project and to deploy suitably qualified and experienced personnel to be present during the undertaking of activities that may present a high risk to biodiversity matters such as clearing of native vegetation. This Monitoring Program, along the CBMP has been prepared in consultation with the project ecologist.

Martinus Rail's Construction Manager/Area Manager and the Environmental Site Representative (ESR) are responsible for ensuring that all legal and other requirements described in this Monitoring Program are met.



1.6 Purpose

The purpose of this Monitoring Program is to satisfy the requirement of CoA C26 and to support the Project in tracking performance against the objectives in Section 2.2 and targets in Section 2.3 of the CBMP.

1.7 Environmental requirements

1.7.1 Guidelines and standards

The main guidelines, specifications, and policy documents relevant to this Monitoring Program include:

- Environmental Management Plan Guideline Guideline for Infrastructure Projects (DPIE, April 2020);
- Department of Primary Industries 'Policy and Guidelines for Fish Habitat Conservation and Management (DPI, 2013);
- Hygiene protocol for the control of disease in frogs (DECCW, 2008);
- Australian Standard AS 4373 Pruning of Amenity Trees;
- Biodiversity Assessment Method (Department of Planning, Industry and Environment (DPIE), 2020a) (BAM);
- Threatened Biodiversity Survey and Assessment: Guidelines for Developments and Activities (Department of Environment and Conservation (DEC), 2004);
- NSW Guide to Surveying Threatened Plants (Office of Environment and Heritage (OEH), 2016);
- Species credit' threatened bats and their habitats (OEH, 2018);
- Australian Department of Agriculture, Water and the Environment's survey guidelines for threatened species under the EPBC Act;
- Matters of National Environmental Significance—significant impact guidelines 1.1 (Department of the Environment, 2013);
- Policy and guidelines for fish habitat conservation and management (Department of Primary Industries (DPI), 2013c);
- Why do fish need to cross the road? Fish passage requirements for waterway crossings (Fairfull and Witheridge, 2003);
- Guideline for controlled activities on waterfront land (DPI, 2012b);
- Inland Rail Sustainability Strategy (0-0000-900-ESS-00-RP-0003)
- Inland Rail Sustainability Requirements Albury to Parkes, sustainability requirements specified in 3-0000-210-ESS-00-SP-0001

1.7.2 Minister's Conditions of Approval

The requirements of the CoA relevant to the development of this Monitoring Program are shown in Table 1. A cross reference is also included to indicate where the CoA is addressed in this Monitoring Program or other project management document, as relevant.

TABLE 1: CONDITIONS OF APPROVAL RELEVANT TO THIS MONITORING PROGRAM

| NO. | REQUIREMENT | WHERE ADDRESSED | | |
|-----|--------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------|-------------|
| C26 | Programs must be prepared identified for each to compa | dition C16 the following Cond d in consultation with the release actual performance of co edicted in the documents list | evant government agencies | Section 1.4 |
| | | Required Construction Monitoring Programs | Relevant government agencies to be consulted for each Construction Monitoring Program | |
| | c) | Biodiversity | BCS (NSW DCCEEW) | |



| NO. | REQUIREMENT | WHERE ADDRESSED |
|-----|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|
| C27 | Each Construction Monitoring Program (CMP) must have consideration of SMART principles and provide: | - |
| | (a) details of baseline data available; | Section 2.1 |
| | (b) details of baseline data to be obtained and when; | Section 2.2 |
| | (c) details of all monitoring of the project to be undertaken; | Section 3.1 |
| | (d) the parameters of the project to be monitored; | Section 3.1 |
| | (e) the frequency of monitoring to be undertaken; | Section 3.1 |
| | (f) the location and justification of monitoring locations. | Section 3.1 |
| | (g) the reporting of monitoring results and analysis results against relevant criteria | Section 3.1 Section 4.1 |
| | (h) details of the methods that will be used to analyse the monitoring data; | Section 4.1 |
| | (i) procedures to identify and implement additional mitigation measures where the results of the monitoring indicate unacceptable project impacts; and | Section 3.1 Section 3.2 |
| | (j) any consultation to be undertaken in relation to the monitoring programs. | Section 1.4 |
| C34 | The results of the CMP(s) must be submitted to the Planning Secretary, and relevant regulatory agencies, for information in the form of a Construction Monitoring Report at the frequency identified in the relevant CMP. | Section 1.3 Section 4.1 |
| E29 | Prior to construction, at Billy Hughes Bridge and Uranquinty Creek, existing fauna movement corridors, pathways and connectivity for the Squirrel Glider at Billy Hughes Bridge and Uranquinty Creek must be determined by a suitably qualified and experienced expert in consultation with DCCEEW including evidence of existing fauna movement corridors, pathways and connectivity including analysis of existing studies or baseline monitoring. | Section 2.2.1 |

^{*}Uranquinty Creek refers to Sandy Creek which flows along the western extent of the Uranquinty township and intersects the Uranquinty Yard enhancement site.

1.7.3 Updated Mitigation Measures

The primary and secondary requirements of the Updated Mitigation Measures (UMMs)as amended in Albury to Illabo Kemp Street Bridge Enhancement Site Modification (June 2025) were reviewed and it was determined that no measures are directly relevant to the development of this Monitoring Program. The UMMs that are relevant to the development of the Stage C CBMP are detailed in Section 3.4 of the CBMP.



2 BASELINE DATA

Baseline data was gathered as part of the preparation of the project EAD. This data was collected during targeted field surveys undertaken across a range of seasons and years to map native and non-native vegetation and identify whether threatened flora and fauna species or communities listed under the NSW *Biodiversity Conservation Act 2016* (BC Act) and/or the Commonwealth *Environment Protection and Biodiversity Conservation Act 1999* (EPBC Act) are present.

Field surveys were undertaken in November 2020, February 2021, May 2021, October 2021, and July 2023, and included the following:

- native vegetation and targeted threatened flora surveys
- targeted threatened fauna surveys including:
 - o fauna habitat assessments
 - o opportunistic sightings of fauna and evidence of fauna activities (such as nests, scats, burrows, etc.
 - o targeted seasonal surveys of birds, bats, mammals, reptiles and amphibians.

No additional baseline data is required to be collected for Stage C of the Project for the purpose of this Monitoring Plan. Separate baseline fauna connectivity monitoring will be undertaken to support preparation of the Fauna Connectivity Strategy required by CoA E29, as identified in Section 2.2.1.

2.1 Existing environment

2.1.1 Plant Community Types and Threatened Ecological Communities

Native vegetation recorded within the study area is considered to meet the final determination of one threatened ecological community listed under the BC Act being:

White Box – Yellow Box – Blakely's Red Gum Grassy Woodland and Derived Native Grassland

White Box – Yellow Box – Blakely's Red Gum Grassy Woodland and Derived Native Grassland is listed as Critically Endangered under BC Act. A summary of the extent of White Box – Yellow Box – Blakely's Red Gum Grassy Woodland and Derived Native Grassland threatened ecological community within the study area is provided in Table 2.

TABLE 2: EXTENT OF WHITE BOX – YELLOW BOX – BLAKELY'S RED GUM GRASSY WOODLAND AND DERIVED NATIVE GRASSLAND THREATENED ECOLOGICAL COMMUNITY WITHIN THE STUDY AREA

| THREATENED ECOLOGICAL | VEGETATION TYPE AND ZONE | BC ACT | IBRA SUBREGION | | PROPOSAL SITE EXTENT |
|---------------------------------------------------|------------------------------|--------------------------|-----------------|------------------|-------------------------|
| COMMUNITY | | | LOWER SLOPES | INLAND SLOPES | (HECTARES) |
| White Box – Yellow Box – | PCT 277 - Moderate condition | | 0 | 0.5 | 0.50 |
| Blakely's Red Gum grassy | PCT277 – Poor condition | Critically Endangered | 0.14 | 1.29 | 1.43 |
| woodlands | PCT 277 – Derived condition | | 0 | 2.34 | 2.34 |
| Total extent of threatened ecological communities | | | | | |

2.1.2 Threatened or otherwise significant flora species

A total of nine threatened flora species were considered to have potential associated habitat within the study area and were the subject of targeted surveys.

No threatened flora species were recorded during targeted surveys.

2.1.3 Fauna Habitat

Section 5 of the Revised BDAR assessed the habitat suitability for threatened species in accordance with Chapter 5 of the BAM and has been prepared in accordance with Part 3 of the BAM 2020 Operational Manual – Stage 1 (EES 2020a). Likelihood of occurrence assessments were undertaken for all threatened species, populations and migratory species identified through database searches.



Fauna habitat assessments were undertaken to assess the likelihood of threatened species of animal (candidate species identified in desktop review) occurring within the study area.

Table 3 outlines the habitat features suitable for a species credit species within the proposal site (BAM s. 5.2.5). Detailed figures for threatened fauna recorded and candidate species polygons are presented in Appendix C of the CBMP.

TABLE 3: SPECIES WITH SUITABLE HABITAT WITHIN THE PROPOSAL SITE

| SCIENTIFIC NAME | COMMON NAME | BC ACT ¹ | SAII ² | ASSOCIATED NATIVE VEGETATION TYPES | IBRA SUBREGION | |
|--------------------------|------------------------------------|------------------------|-------------------|--------------------------------------------------------------------------------------|-----------------|------------------|
| | | | | | LOWER SLOPES | INLAND SLOPES |
| Crinia sloanei | Sloanes Froglet | V | No ³ | PCT 5 (poor) and PCT 277 (poor and native plantings) ⁴ | 0.03 | 0.23 |
| Keyacris scurra | Key's Matchstick Grasshopper | Е | No | PCT 5 (poor) and PCT 277 (poor, moderate, derived and native plantings) ⁴ | - | 0.21 |
| Polytelis swainsonii | Superb Parrot | V | No | PCT 5 (poor) and PCT 277 (poor and moderate) | 0.16 | 1.82 |
| Petaurus norfolcensis | Squirrel Glider | V | No | PCT 5 (poor) and PCT 277 (poor and moderate) | 0.16 | 1.82 |

⁽¹⁾ Threat status under the BC Act: V = Vulnerable, E = Endangered.

It was determined that the Sloane's Froglet potential species habitat will occur in the proposal site, where the mapped potential habitat (including 15 metre buffer) occurs in association with a native vegetation community (PCT) and is not dissected by a road, rail corridor or urban development. Targeted surveys were undertaken by NGH during July and/or August 2024 for Sloane's Froglet in all areas where that species was assumed present. Sloane's Froglet (*Crinia sloanei*) was not detected aurally or visually at any site. The survey is discussed further in Section 6.9 of the CBMP – Stage C.

The Matchstick Grasshopper species is predicted to occur within the Inland Slopes IBRA subregion. Targeted surveys for this species were completed in December 2022 and the species was not recorded. In areas that have not been surveyed due to access limitations this species was conservatively assumed to be present within potential habitats at the Junee to Illabo dual track clearances area in PCT 277 Blakely's Red Gum – Yellow Box grassy tall woodland (poor and moderate).

The Superb Parrot and Squirrel Glider potential species habitat has been mapped using a precautionary principal where all available habitat for this species has been used to map species polygons, being all PCT 5 and 277 patches with the exception of derived and native plantings.

2.1.4 Threatened fauna

In accordance with the BAM threatened species have been assessed as predicted or ecosystem credit species and species credit species. Threatened fauna surveys completed within the study area were carried out as described in Section 5.5.3 of the Revised BDAR.

A total of six threatened fauna species identified as predicted or ecosystem credit species and species credit species were recorded during surveys. These are presented in Table 4.

⁽²⁾ SAII = serious and irreversible impact.

⁽³⁾ Sloane's Froglet (Crinia sloanei) is a candidate SAII species however the Revised BDAR states the Project is not at risk of having a SAII on the species

⁽⁴⁾ The assessment relies on assumed presence for the Sloane's Froglet and Key's Matchstick Grasshopper



TABLE 4: THREATENED FAUNA RECORDED IN THE STUDY AREA

| SCIENTIFIC NAME | COMMON NAME | BC ACT | CREDIT TYPE | OUTCOME OF TARGETED SURVEYS |
|---------------------------|---------------------------|------------|------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Circus assimilis | Spotted Harrier | Vulnerable | Predicted ecosystem credit species | One individual was observed in grasslands adjacent to the study area at Marinna. Likely to occur seasonally in low numbers across open landscapes associated with study area. |
| | | | | Study area habitats not considered to represent important foraging habitat, but may provide trees for breeding purposes |
| Hieraaetus morphnoides | Little Eagle | Vulnerable | Dual credit species | Although potential breeding habitat was recorded during habitat assessments and one individual was recorded during the breeding season adjacent to Billy Hughes bridge, no breeding activity or nests trees were observed in the study area. Given that targeted survey did not locate breeding activity or nest trees, breeding habitat for the Little Eagle is unlikely to be affected by the proposal, and as such, this species was not considered further. |
| Petaurus norfolcensis | Squirrel Glider | Vulnerable | Candidate species credit | Species was recorded during field surveys within the study area. Study area provides habitat features (i.e. hollow-bearing trees) that the species is likely to use. The study area will be utilised for both foraging and breeding purposes. |
| Polytelis swainsonii | Superb Parrot | Vulnerable | Dual credit species | Species was recorded during field surveys within the study area. Study area provides habitat features (i.e. hollow-bearing trees) that the species is likely to use. The study area will be utilised for both foraging and breeding purposes. |
| Pteropus poliocephalus | Grey-headed Flying-fox | Vulnerable | Dual credit species | Species recorded foraging on blossom resources within study area vegetation. There are no known Flying-fox camps associated with the study area. |
| | | | | Due to the lack of the important breeding habitat features the species is not considered to be a candidate species. |
| Stagonopleura guttata | Diamond Firetail | Vulnerable | Predicted ecosystem credit species | Species recorded in the study area. May occasionally occur in the study area where more suitable habitat adjoins. The study area habitats are considered of generally poor quality to support this species over much of its length. |

⁽¹⁾ Grey-headed Flying-fox (*Pteropus poliocephalus*) is a dual credit species however for the purpose of the Project, the Revised BDAR states this is a 'predicted ecosystem credit species' due to the lack of the important breeding habitat features (breeding camps)

2.1.5 Aquatic habitat

The study area includes 26 watercourses and three waterbodies, of which 12 were ranked as medium to high priority watercourses and were subject to field survey and habitat assessment. Ranking of watercourses was based on Key Fish





Habitat (KFH) mapping (DPI, 2007a), threatened species distribution mapping (DPI, 2016) and Strahler stream order (Strahler, 1952).

Aquatic habitat assessment in the field found that except for the Murray River, all other watercourses were highly ephemeral with only four sites containing small, shallow remnant pools:

- Oddies Creek
- Eight Mile Creek
- Buckaringah Creek
- Jeralgambeth Creek

The remaining watercourses were completely dry within the proposal site at the time of survey. The Murray River (which is perennial and contained moderate flows) and Oddies Creek both contained habitat features such as woody debris, instream macrophytes, riparian vegetation and bank overhang. Eight Mile Creek contained instream macrophytes and Buckaringah Creek contained large woody debris. The remaining watercourses lacked important fish habitat features. First and second order drainage lines and tributaries that were visited usually lacked riparian or aquatic vegetation and were dry. All watercourses and riparian zones were significantly modified by agricultural land practices.

Targeted threatened fauna surveys were undertaken using bait traps in medium to high priority watercourses where water and/or remnant pools were present. Pelagic species and/or larger bodied fish species were not targeted in the Murray River and were assumed present and considered further in a likelihood of occurrence assessment.

Targeted surveys did not result in the capture of any threatened species and only the exotic Mosquitofish were captured.

2.2 Additional baseline data to be obtained

The baseline data obtained to inform the EAD is considered sufficient to fulfil the baseline monitoring requirements to inform this Monitoring Plan.

2.2.1 Fauna connectivity strategy

The Fauna Connectivity Strategy required by CoA E31 is being prepared separately to this CBMP. Any baseline monitoring requirements to inform the Fauna Connectivity will be determined in consultation with DCCEEW and a suitably qualified and experienced ecologist as per CoA E29. The survey methodology is being finalised in consultation with DCCEEW (BCS). Once finalised, baseline monitoring will be undertaken in accordance with the agreed upon survey methodology.



3 MONITORING PROCEDURE

3.1 Biodiversity monitoring

The biodiversity monitoring procedure to be implemented on the project is outlined in Table 5.

Any person, including Martinus Rail staff, undertaking biodiversity monitoring will be appropriately trained to the extent where required for the aspect in which they are monitoring for the purpose of the Project.

Biodiversity monitoring will be conducted within the Project construction boundary at all enhancement sites, with specific monitoring activities to focus on certain enhancement sites, as described in Table 5.

TABLE 5: BIODIVERSITY MONITORING PROCEDURE

| MONITORING DETAILS | LOCATION | FREQUENCY / DURATION | TEST PROCEDURE |
|----------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Pre-clearing inspection | All sites where clearing will occur | Within three (3) months of the commencement of the relevant clearing activity | Identification and verification of the quantum (in hectares) of clearing of all mapped plant community types, threatened ecological communities, threatened fauna habitat and threatened flora to inform the Project |
| Monitoring and supervision of vegetation clearing | All sites where clearing will occur | Within 24 hours of clearing During the second stage of two-stage clearing | clearing register and indicate any management measures to avoid or minimise impacts where relevant. Identify potential impacts to fauna habitat features (such as tree hollows, nests, potential microbat |
| Handling and rescue of fauna in accordance with the Fauna Handling Procedure | All enhancement sites | As discoveredFor the duration of construction | roosting) and quantify clearing of these features, fauna rescues, injuries and mortality rates. Track re-use, relocation and disposal of snags, hollows and |
| Post-clearing inspection | All sites where clearing has occurred | Following clearing activity and within three (3) months of completion of work | course woody debris. Monitor clearing of native vegetation to confirm actual impacts to biodiversity values to inform any final biodiversity offset requirements within the biodiversity offset package. Supervise clearing operations and removal of habitat trees during two-stage clearing approach per Section 6.1 of the CBMP. Reporting captured via: Project Clearing Register Preclearing report Clearing Permit Fauna Handling Record Sheet |
| Performance and effectiveness of exclusion zones when works are being undertaken | All enhancement sites with biodiversity exclusion zones in place, which may include: • Murray River Bridge (riparian zone) | Weekly (for sites where construction is occurring) For the duration of construction | Ongoing weekly inspections will be carried out throughout the duration of the construction of the Project to monitor environmental compliance and risk, and to identify any potential corrective actions. |



| MONITORING DETAILS | LOCATION | FREQUENCY / DURATION | TEST PROCEDURE |
|-------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | Billy Hughes bridge (Sloane's froglet and riparian zone) Table Top Yard (riparian zone) Henty Yard (riparian zone) Culcairn Yard (riparian zone) Uranquinty Yard (riparian zone) Pearson Street Bridge (riparian zone) Harefield Yard (riparian zone) Kemp Street Bridge (riparian zone) Kemp Street Bridge (riparian zone) Olympic Highway underbridge (riparian zone) Junee to Illabo (riparian zone) Areas within 100 metres of identified Superb Parrot nest trees during breeding season (September to November) as practicable any other enhancement sites where the requirement for a biodiversity exclusion zone is required. | | Reporting captured via: • Weekly environmental inspection checklist |
| Weed and pest (including fire ants) management | All enhancement sites | Weekly (for sites where construction is occurring) For the duration of construction | |
| Sloane's Froglet management (water quality and environmental control | Billy Hughes Bridge | Weekly (MR environment team for the duration of construction) Monthly (suitably qualified ecologist) | Ongoing weekly visual inspections will be carried out by the MR environment team throughout the duration of the construction of the Project, to be accompanied by a suitably qualified ecologist once a month to monitor environmental compliance and risk, and to identify any potential corrective actions. Reporting captured via: |



| MONITORING DETAILS | LOCATION | FREQUENCY / DURATION | TEST PROCEDURE |
|-------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | | | Weekly environmental inspection checklist |
| Weed monitoring | All enhancement sites | AnnuallyFor the duration of construction | Visual inspection of enhancement sites and review of weed monitoring notes in weekly environmental inspection checklists to inform annual weed monitoring report. Reporting captured via: Weed Monitoring Report |
| Rehabilitation inspections and monitoring | Enhancement sites where works may impact riparian zones within 40 metres of a watercourse: Murray River Bridge Billy Hughes bridge Table Top Yard Henty Yard Culcairn Yard Uranquinty Yard Pearson Street Bridge Harefield Yard Kemp Street Bridge Olympic Highway underbridge Junee to Illabo any other enhancement sites where the requirement for a biodiversity exclusion zone is required. | Quarterly following rehabilitation works For the remainder of construction | Visual inspection to determine the success of rehabilitation efforts for riparian land and watercourses. Reporting captured via: Erosion and Sediment Control Maps Sensitive Area Plans Environmental Work Method Statements Weekly Environmental Inspection Checklists Landscape Design Reports |
| Vehicle hygiene inspections | All enhancement sites | Inspection of every vehicle that enters the Project site for the first time For the duration of construction | Inspection for all new vehicles and plant entering site. Reporting captured via: Vehicle inspection forms. Vehicle hygiene register. |

3.2 Adaptive management

Biodiversity monitoring results obtained during the implementation of this Monitoring Program will be compared against the objectives identified in Section 2.2 and the targets identified in Section 2.3 of the CBMP as relevant.

Should an exceedance of the objective or predicted levels be identified that is directly attributable to the project, the ESR (or delegate) will undertake a site inspection and a review that will consider:

- Detailed analysis of the results by Martinus Rail personnel (including site inspection, as required) to determine
 possible causes for the exceedance. Construction activities occurring and/or specific equipment in use at the
 time of the exceedance may be considered;
- Advising relevant personnel of the exceedance;
- Identifying and agreeing on actions and/or additional mitigation measures to resolve or mitigate the exceedance;

A2I | ALBURY TO ILLABO





- Implementing actions to rectify or mitigate the exceedance;
- Identifying and implementing additional mitigation measures.

Where necessary, monitoring will be implemented to follow-up on any biodiversity related issues that arise during construction.

Mitigation measures and preventative/corrective actions will be developed in accordance with the procedure for dealing with non-compliance with environmental management measures outlined in Section 8 of the CEMP. Martinus Rail will verify and document the effectiveness of any management measures or preventative/corrective actions implemented to avoid further exceedances.



4 REPORTING

4.1 Quarterly Construction Biodiversity Monitoring Report

A quarterly Construction Monitoring Report will be prepared detailing the results of the monitoring undertaken in accordance with this Monitoring Program.

The Construction Monitoring Reports will be prepared once construction biodiversity monitoring commences during construction of Stage C of the Project.

The Construction Monitoring Reports will be submitted to the Planning Secretary and to relevant regulatory agencies (BCS) for information, in accordance with CoA C34. The report will be submitted within 60 days after the reporting period ends.

Reports will include, but not be limited to, the following information:

- The date(s) and time at which the monitoring was undertaken;
- The locations and description of monitoring undertaken;
- A summary of monitoring data;
- Comparison of monitoring results with the relevant objectives identified in Section 3 of this Monitoring Program and whether they have been met;
- Details of any alteration to the Monitoring Program;
- Summary of any complaints received regarding biodiversity.

Separate from the Construction Monitoring Report, additional records relating to biodiversity training, toolbox talks, monitoring results and audit results will be prepared, maintained, and stored in line with the CEMP. The complaints management and reporting procedure is described in the CEMP.









APPENDIX H

Threatened Species Identification



Table A3 details threatened flora and fauna species specified by the Revised BDAR which are known or predicted to occur in the Revised BDAR study area, and which have a moderate, high or known likelihood of occurrence. Details include scientific and common names, BC Act and EPBC Act listings, a written description and a reference image for each. Species descriptions and reference images are sourced from the NSW Office of Environment and Heritage (OEH) website from each respective species profile (unless otherwise stated), with contributors noted below each image. Location information is drawn from Appendix C-1 and C-2 of the Revised BDAR (WSP, 2024).

In the event that any of the below threatened entities are encountered in a new location (that was not assessed in the Revised BDAR) or an entity that was not offset (species for which a clearing limit is not set out in Table 7 of the CoA) is discovered, then the Unexpected Threatened Species Finds Procedure must be followed.

TABLE A3: THREATENED FLORA AND FAUNA INDIVIDUALS OR HABITAT KNOWN OR PREDICTED TO OCCUR IN THE STUDY AREA

| SCIENTIFIC NAME | COMMON NAME | BC ACT ¹ | EPBC ACT ² | SPECIES DESCRIPTION (OEH) | REFERENCE IMAGE (OEH) | LOCATION BY IBRA SUBREGION (WSP) ³ | | | |
|---------------------------|----------------------------------|---------------------|--------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|---------------------------------------------------|--|--|--|
| THREATENED | THREATENED FLORA SPECIES | | | | | | | | |
| Ammobium craspedioides | Yass Daisy | V | V | The Yass Daisy is a rosette-forming perennial. Leaves are spoon-shaped, to 12 cm long and 17 mm wide, hairy on top and white and woolly underneath. The spring flowerheads are hemispherical buttons, to 20 mm wide, and surrounded at the base by papery leaf-like structures (bracts). The solitary flowerheads are borne on unbranched stems to 60 cm tall; the stems are sparsely leafed, and edged with narrow "wings". Rosettes die off after fruiting. | Image by Bindi Vanzella | Inland slopes | | | |
| Amphibromus fluitans | River Swamp Wallaby- grass | V | V | A perennial grass to 0.8 m tall. Flowering stems tend to be somewhat sprawling, except for the flowering portion of the stalk, which is erect and up to 35 mm long. The leaf blade is 2 - 4.5 mm wide, rough to touch and deeply ribbed. The structure that breaks away from the flower-stalk (and contains the seed) is two-toothed, with a straight bristle arising about half way up its back. The species is virtually aquatic, often with only the flower heads above the water. | Image by Geoff Carr | All sites Recorded near Billy Hughes bridge | | | |



| SCIENTIFIC NAME | COMMON NAME | BC ACT ¹ | EPBC ACT ² | SPECIES DESCRIPTION (OEH) | REFERENCE IMAGE (OEH) | LOCATION BY IBRA SUBREGION (WSP) ³ |
|-------------------------|------------------------|---------------------|--------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|--------------------------------------------------|
| Prasophyllum petilum | Tarengo Leek Orchid | Е | E | Reaches to 35 cm tall. Can be distinguished from more common onion orchids that grow in its habitat by the pinkish-purple base to the leaf. Produces a solitary, tubular, fleshy, dull green leaf, growing to 35 cm tall. The flower-stem emerges in mid spring to early summer from a hole near the base of the leaf. The raceme, reaching to 12 cm tall, has about 20 fragrant flowers with pointed tepals. The flowers are usually a pale whitish-green, but can be pink or pale purple. Can be very cryptic when growing in small numbers and within tall grasses. | Image by John Briggs | Inland slopes |
| Swainsona recta | Small Purple- pea | Е | E | A slender, erect perennial herb growing to 30 cm tall. The leaves are divided into up to six pairs of 10 mm long, very narrow leaflets, each with a pointed tip. There is also a single leaflet at the end of each divided leaf. It bears one to several sprays of between 10 and 20 purple, pea-shaped flowers, between late September and early December. Flowers are followed by pods up to 10 mm long in summer. | Image by John Briggs | All sites |



| SCIENTIFIC NAME | COMMON NAME | BC ACT ¹ | EPBC ACT ² | SPECIES DESCRIPTION (OEH) | REFERENCE IMAGE (OEH) | LOCATION BY IBRA SUBREGION (WSP) ³ | | | |
|-------------------------|------------------------------------|---------------------|--------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|--------------------------------------------------|--|--|--|
| THREATENED | THREATENED FAUNA SPECIES | | | | | | | | |
| Crinia sloanei | Sloane's Froglet | Е | Е | A small ground-dwelling frog. Superficially resembles other frogs of the genus Crinia, but can be identified by physical characteristics and call. Far less variation in back colour pattern than other Crinia species, having a mustard yellow/greyish back with large patches of darker pigment over the body. The throat of males is greyish green. Call described as a short metallic 'chick chick chick chick'. | Image by David Hunter | All sites | | | |
| Keyacris scurra | Key's Matchstick Grasshopper | Е | Е | A small (females ~25 mm, males ~18mm), slender, wingless grasshopper characterised by its slanted face, splayed hind femora (longest segment of the hind leg) and sword-shaped antennae. Occurs in several colour forms, brown being most common. | Image by Brian Faulkner | Inland slopes | | | |
| Polytelis swainsonii | Superb Parrot | V | V | A distinctive medium-sized, bright grass-green parrot with a long, narrow tail and sharply back-angled wings in flight. Males have yellow foreheads and throats and a red crescent that separates the throat from the green breast and belly. Females are slightly duller green and have a dull, light blue wash in place of the males' red and yellow markings. | Images by Helen Fallow | All sites Recorded within study area | | | |



| SCIENTIFIC NAME | COMMON NAME | BC ACT ¹ | EPBC ACT ² | SPECIES DESCRIPTION (OEH) | REFERENCE IMAGE (OEH) | LOCATION BY IBRA SUBREGION (WSP) ³ |
|---------------------------|--------------------|---------------------|--------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|---------------------------------------------------------------------|
| Petaurus norfolcensis | Squirrel Glider | V, E | - | Head and body length of about 20 cm. Blue-grey to brown-grey fur above, white on the belly and the end third of the tail is black. A dark stripe from between the eyes to the mid-back and the tail is soft and bushy averaging about 27 cm in length. Up to twice the size of Sugar Gliders, are less vocal and their facial markings are more distinct and they nest in bowl-shaped, leaf lined nests in tree hollows. Species is 'Endangered' where it is located within the Wagga Wagga LGA. | Image by Figaro | All sites Recorded utilising native vegetation witin the study area |
| Circus assimilis | Spotted Harrier | V | - | A medium-sized, slender bird of prey having an owllike facial ruff that creates the appearance of a short, broad head, and long bare yellow legs. Upperparts are blue-grey with dark barring, and the wingtips are black. The face, innerwing patch, and underparts are chestnut. The long tail is boldly banded, with a wedge-shaped tip. Juveniles are mottled and streaked ginger and brown, with prominent ginger shoulders, fawn rump and banded tail. | Image by Dean Ingwersen | All sites Observed adjacent to Junee to Illabo clearances |
| Hieraaetus morphnoides | Little Eagle | V | - | A medium-sized bird of prey that occurs in two colour forms: either pale brown with an obscure underwing pattern, or dark brown on the upper parts and pale underneath, with a rusty head and a distinctive underwing pattern of rufous leading edge, pale 'M' marking and black-barred wingtips. Both forms have a black-streaked head with a slight crest, a pale shoulder band on the upperwings, a rather short and square-tipped barred tail, and feathered legs. | Image by Dean Ingwersen | All sites Observed adjacent to Junee to Illabo clearances |



| SCIENTIFIC NAME | COMMON NAME | BC ACT ¹ | EPBC ACT ² | SPECIES DESCRIPTION (OEH) | REFERENCE IMAGE (OEH) | LOCATION BY IBRA SUBREGION (WSP) ³ |
|---------------------------|---------------------------|---------------------|--------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|----------------------------------------------------------------|
| Pteropus poliocephalus | Grey-headed Flying-fox | V | V | The largest Australian bat, with a head and body length of 23 - 29 cm. It has dark grey fur on the body, lighter grey fur on the head and a russet collar encircling the neck. The wing membranes are black and the wingspan can be up to 1 m. It can be distinguished from other flying-foxes by the leg fur, which extends to the ankle. | Image by Shane Ruming | All sites May utilise blossom resources |
| Stagonopleura guttata | Diamond Firetail | V | V | A large (length 10 to 12 cm, weight 17 grams), striking finch with a bright red bill, and red eyes and rump. The white throat and lower breast are separated by a broad black breast-band that extends into the strongly white-spotted, black flanks. It has a grey back and head, and ashy-brown wings. The call is a plaintive, drawn-out, nasal 'twoo-wheee'. Flight is low and direct, with slight undulations. | Images by Helen Fallow | All sites Recorded at multiple locations within the study area |
| Anthochaera phrygia | Regent Honeyeater | CE | CE | A striking and distinctive, medium-sized (length 20 - 24 cm, weight 35 - 50 grams), black and yellow honeyeater with a sturdy, curved bill. Have a wingspan of 30 cm. Its head, neck, throat, upper breast and bill are black and the back and lower breast are pale lemon in colour with a black scalloped pattern. Its flight and tail feathers are edged with bright yellow. There is a characteristic patch of dark pink or cream-coloured facial-skin around the eye. Sexes are similar. The call is a soft metallic bell-like song. | Image by Chris Tzaros | All sites Mapped important habitat at Billy Hughes bridge |



| SCIENTIFIC NAME | COMMON NAME | BC ACT ¹ | EPBC ACT ² | SPECIES DESCRIPTION (OEH) | REFERENCE IMAGE (OEH) | LOCATION BY IBRA SUBREGION (WSP) ³ |
|---------------------------|----------------------------------|---------------------|--------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------|--------------------------------------------------------------------|
| Hirundapus caudacutus | White- throated Needletail | V | V | Large swift with approx. 50 cm wingspan and short, square tail. Predominantly dark, with white throat, forehead and undertail coverts. The name refers to the short spines that extend beyond the feathers of the tail. | Image by Vincent Wang (eBird) | Only likely to occur during seasonal movements |
| Lathamus discolor | Swift Parrot | E | CE | A small parrot about 25 cm long. It is bright green with red around the bill, throat and forehead. The red on its throat is edged with yellow. Its crown is blue-purple. There are bright red patches under the wings. Long (12 cm), thin tail, which is dark red. Flute-like chirruping or metallic "kik-kik-kik" call | Image by Neville Lazarus | All sites May utilise blossom resources |
| Phascolarctos cinereus | Koala | E | E | An arboreal marsupial with fur ranging from grey to brown above, and white below. It has large furry ears, a prominent black nose and no tail. Spends most of its time in trees and has long, sharp claws, adapted for climbing. Adult males weigh 6 - 12 kg and adult females weigh 5 - 8 kg. During breeding, males advertise with loud snarling coughs and bellows. | Image by Ross Bennett | All sites Species may occur irregularly where there are feed trees |



| SCIENTIFIC NAME | COMMON NAME | BC ACT ¹ | EPBC ACT ² | SPECIES DESCRIPTION (OEH) | REFERENCE IMAGE (OEH) | LOCATION BY IBRA SUBREGION (WSP) ³ |
|---------------------------------------|------------------------|---------------------|--------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------|--------------------------------------------------|
| Artamus cyanopterus cyanopterus | Dusky Wood- swallow | V | - | A medium-sized bird (16-19.5 cm, 35 g), with a longish tail. Mostly dark grey-brown, merging to blackish on the tail, with a small black-brown mask. Bluish bill with a black tip. Upper-wings are a dark blue-grey with a white leading edge. Conspicuous white corners on the tail. In flight the dark grey-brown under-body contrasts with the whitish under-wing. Sexes are alike. Calls consist of brassy chirps, chirups, a soft low 'vut vut' and a brisk 'peet peet'. | Image by Michael Rutkowski (eBird) | All sites |
| Callocephalon fimbriatum | Gang-gang Cockatoo | Е | Е | One of the more distinctive and charismatic members of Australia's avifauna. Primarily slate-grey, with the males easily identified by their scarlet head and wispy crest, while females have a grey head and crest and feathers edged with salmon pink on the underbelly. Range in length from 32 to 37 cm, with a wingspan of 62 to 76 cm. The call has been likened to a creaking gate or cork being pulled from a bottle. | Image by Zarni Bear | All sites |
| Certhionyx variegatus | Pied Honeyeater | V | - | A distinctive small, black and white honeyeater with white wing-bar, rump and tail-panels, abdomen and a bluish-grey wattle below the eye. The female is greyish-brown with a white abdomen, with a strong pattern of pale edging to feathers on the wing. The bill is long and curved and males possess a bare eye patch that is pale blue in colour. Females and young males have a less conspicuous bare eye patch than mature males. | Image by Graeme Chapman | All sites; Known to occur in Albury |



| SCIENTIFIC NAME | COMMON NAME | BC ACT ¹ | EPBC ACT ² | SPECIES DESCRIPTION (OEH) | REFERENCE IMAGE (OEH) | LOCATION BY IBRA SUBREGION (WSP) ³ |
|-------------------------------------|--------------------------------|---------------------|--------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|-----------------------------------------------------------------------------|
| Epthianura albifrons | White-fronted Chat | V | - | An endemic Australian passerine bird, 12 cm in length and weighing approximately 13 g. It has a short slender bill, long spindly legs, a short square-tipped tail and rounded wings. The male's plumage is more striking than the females; juvenile plumage is most similar to the female. A distinctive 'tang, tang' is used as a contact call. | Image by Australian museum | All sites May utilitse unmanaged ground cover for nesting |
| Falco subniger | Black Falcon | V | - | A large (45-55 cm in length), very dark falcon with pale grey cere, eye-rings and feet. It is uniformly dark brown to sooty black, with a pale throat and an indistinct black streak below each eye. Some individuals have faint, narrow barring under the wings and tail. | Image by Michael Fuhrer (eBird) | All sites May utilise trees for perching or breeding. |
| Glossopsitta porphyroceph ala | Purple- crowned Lorikeet | V | - | A small (17-18.5cm) parrot. Upper parts are bright green, with a wash of bronze across the nape and mantle, while underparts are greenish-yellow with a pale blue belly. The crown is purple, appearing black in the field while the ear coverts and forehead are orange-yellow. The bend of the wing is narrowly edged bright blue while the underwing coverts are bright red. The call is a high-pitched slightly metallic 'tziet, tziet, tziet'. | Image by Chris Tzaros | All sites May utilise blossom resources (particularly in the Albury region) |



| SCIENTIFIC NAME | COMMON NAME | BC ACT ¹ | EPBC ACT ² | SPECIES DESCRIPTION (OEH) | REFERENCE IMAGE (OEH) | LOCATION BY IBRA SUBREGION (WSP) ³ |
|---------------------------|----------------------------|---------------------|--------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------|-----------------------------------------------------------------|
| Glossopsitta pusilla | Little Lorikeet | V | - | A small (16-19 cm; 40 g) bright green parrot, with a red face surrounding its black bill and extending to the eye. The undertail is olive-yellow with a partly concealed red base, and the underwing coverts are bright green. The mantle is imbued with light brown. The call in flight is diagnostically different from other lorikeets, being a shrill and rolling screech: 'zit-zit' or 'zzet'. Although difficult to observe while foraging high in treetops, a flock's constantly chattering contact calls give it away. Flight is fast, direct and through or above the canopy. | Image by John Barkla (birdlife Australia) | All sites May utilise blossom resources |
| Haliaeetus leucogaster | White-bellied Sea-Eagle | V | Ма | A large eagle that has long broad wings and a short, wedge-shaped tail. It measures 75–85 cm in length, and has a wingspan of 180–220 cm. Predominantly white and grey. The head, breast and belly, and the feathering on the legs, are white. The back and upper surfaces of the wings are grey, and the undersides are greyish-black with a smaller area of white along the leading edge. The tail is grey at the base, and has a white tip. The large, hooked bill is grey with a darker tip, and the eye is dark brown. The legs and feet are cream-white, with long black talons. | | All sites Recorded at Murray River, Wagga Wagga and Henty |



| SCIENTIFIC NAME | COMMON NAME | BC ACT ¹ | EPBC ACT ² | SPECIES DESCRIPTION (OEH) | REFERENCE IMAGE (OEH) | LOCATION BY IBRA SUBREGION (WSP) ³ |
|-----------------------|-----------------------|---------------------|--------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------|----------------------------------------------------------------------------|
| Lophoictinia isura | Square-tailed Kite | V | - | A reddish, medium-sized (length 50-56 cm, wingspan 130-145 cm), long-winged raptor. Males weigh approximately 500 g while females weigh 650 g. White face with thick black streaks on the crown and finer streaks elsewhere. The saddle, rump and central upper tail coverts are blackish with grey-brown barring. The underparts are predominantly grey-brown with black tips on the grey, square-tipped tail and wing edges. Sexes are alike. Long fingered, upswept wings with a large white patch at the base of the barred 'fingers' show in flight. | Image by Steve Sass | All sites |
| Merops ornatus | Rainbow Bee-eater | - | М | A medium-sized bird, and the only species of bee- eater in Australia. The males measure 25 cm in length and the females 22 cm. Both length measurements include the central tail-streamers, which project 2 - 6 cm beyond the rest of the tail in the male and 1 - 2 cm in the female. The wingspan is 34 cm in the male and 31 cm in the female (DCCEEW, courtesy of Higgins 1999). | Image by Geoff Walan (Australian Museum) | Recorded foraging within study area |
| Petroica phoenicea | Flame Robin | V | - | A small Australian robin (length 14 cm). The male has a dark grey head and upperparts, a small white forehead patch, white wing stripes and white tailedges, a bright orange-red throat, breast and upperbelly. The lower belly is white. The female is brown, darker above, and has a whitish throat and lower belly. The main call is a thin, pretty, piping descending song. | Images by Leo Berzins | All sites Likely to occur seasonally in woodland and open country habitats |



| SCIENTIFIC NAME | COMMON NAME | BC ACT ¹ | EPBC ACT ² | SPECIES DESCRIPTION (OEH) | REFERENCE IMAGE (OEH) | LOCATION BY IBRA SUBREGION (WSP) ³ |
|-------------------------------------------|-----------------------------|---------------------|--------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------|-------------------------------------------------------------------------|
| Pomatostomu s temporalis temporalis | Grey- crowned Babbler | V | - | The largest of the four Australian babblers (length 30 cm). Its distinctive bill is scimitar-shaped, long and heavy. The broad white eyebrow and a pale grey crown-stripe are other distinguishing characters. A dark band passes from the bill through the eye, separating the pale throat and brow to giving a 'masked' look. It has dark greyish-brown upperparts and is paler brown on the underparts, grading to a whitish throat. In flight shows white tips to the tail feathers, and orange-buff patches in the wings. Loud, often repeated 'ya-hoo' call which is a duet between the male and female. | Image by Graeme Chapman | All sites May utilise adjacent habitats (Box-Gum Woodlands) for nesting |
| Stictonetta naevosa | Freckled duck | V | - | A dark, greyish-brown bird with a large head that is peaked at the rear, and a distinctive narrow, slightly up-turned bill. Their dark brownish-black plumage is evenly freckled all over with white or buff. During the winter-spring breeding season, the male's bill becomes crimson at the base. | Image by Michael Murphy | Murray River bridge |
| Petroica boodang | Scarlet Robin | V | - | A small Australian robin (length 13 cm). The male has a black head and upperparts, with a conspicuous white forehead patch, white wing stripes, a bright scarlet-red chest and a white belly. The female is pale brown, darker above, has a dull reddish breast and whitish throat and has white wing and tail markings. Immature males resemble females. The main call of Scarlet Robin is a soft, warbling trill. | Images by Dean Ingwerson (Male) and Helen Fallow (female) | All sites May occur on a seasonal basis |



| SCIENTIFIC NAME | COMMON NAME | BC ACT ¹ | EPBC ACT ² | SPECIES DESCRIPTION (OEH) | REFERENCE IMAGE (OEH) | LOCATION BY IBRA SUBREGION (WSP) ³ |
|--------------------------------------------|------------------------------------------------------------------|---------------------|--------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------|--------------------------------------------------------------------|
| Falsistrellus tasmaniensis | Eastern False Pipistrelle | V | - | Relatively large with a head-body length of about 65 mm. It weighs up to 28 grams. It is dark to reddish-brown above and paler grey on its underside. It has long slender ears set well back on the head and some sparse hair on the nose. | Image by Linda Broome | Inland slopes May occur seasonally |
| Miniopterus orianae oceanensis | Large Bentwing-bat (formerly Eastern bent- wing bat) | V | - | Has chocolate to reddish-brown fur on its back and slightly lighter coloured fur on its belly. It has a short snout and a high 'domed' head with short round ears. The wing membranes attach to the ankle, not to the base of the toe. The last bone of the third finger is much longer than the other finger-bones giving the "bent wing" appearance. It weighs up to 20 grams, has a head and body length of about 6 cm and a wingspan of 30 - 35 cm. | Image by NSW DEC | Inland slopes Recorded at multiple locations within the study area |
| Myotis Macropus (Myotis adversus) | Southern Myotis | V | - | Has disproportionately large feet; more than 8 mm long, with widely-spaced toes which are distinctly hairy and with long, curved claws. It has dark-grey to reddish brown fur above and is paler below. It weighs up to 15 grams and has a wingspan of about 28 cm. | Image by R & A Williams (Australian Museum) | All sites May occur seasonally |



| SCIENTIFIC NAME | COMMON NAME | BC ACT ¹ | EPBC ACT ² | SPECIES DESCRIPTION (OEH) | REFERENCE IMAGE (OEH) | LOCATION BY IBRA SUBREGION (WSP) ³ |
|-----------------------------|------------------------------------------|---------------------|--------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|--------------------------------------------------------------------------------------|
| Saccolaimus flaviventris | Yellow- bellied Sheathtail- bat | V | - | A very distinctive, large, insectivorous bat up to 87 mm long. It has long, narrow wings, a glossy, jet-black back, and a white to yellow belly extending to the shoulders and just behind the ear. Characteristically, it has a flattened head and a sharply-pointed muzzle. The tail is covered with an extremely elastic sheath that allows variation in the tail-membrane area. Males have a prominent throat pouch; females have a patch of bare skin in the same place. | Image by NSW DCCEEW | All sites May occur on a seasonal basis |
| Scoteanax rueppellii | Greater Broad-nosed Bat | V | - | A large powerful bat, up to 95 mm long, with a broad head and a short square muzzle. It is dark reddishbrown to mid-brown above and slightly paler below. It is distinguished from other broad-nosed bats by its greater size. | Image by Michael Pennay | May occur on a seasonal basis |
| Vespadelus baverstocki | Inland Forest Bat | V | - | Generally sandy-brown above, with the underparts being paler. Identification is difficult, with overlap in size and fur colouration with some species occurring in the same area. | Image by Lindy Lumsden | Recorded adjacent to The Rock Yard clearances May occur on a seasonal basis |

⁽¹⁾ BC Act: V = Vulnerable, E = Endangered, CE = Critically Endangered

Doc No: 6-0052-210-PMA-00-PL-0029_0

⁽²⁾ EPBC Act: V = Vulnerable, E = Endangered, CE = Critically Endangered, M = Migratory, Ma =Marine

⁽³⁾ IBRA subregions: Inland Slopes consists of Murray River bridge, Albury Station pedestrian bridge, Albury Yard clearances, Riverina Highway bridge, Billy Hughes bridge, Table Top Yard clearances, The Rock Yard clearances, Uranquinty Yard clearances, Pearson Street bridge, Cassidy Parade pedestrian bridge, Edmondson Street bridge, Wagga Wagga Station pedestrian bridge, Wagga Wagga Yard clearances, Kemp Street bridge, Junee pedestrian bridge, Junee Yard clearances, Olympic Highway underbridge, Junee to Illabo clearances. Lower Slopes consists of Billy Hughes bridge, Culcairn pedestrian bridge, Culcairn Yard clearances, Henty Yard clearances, Yerong Creek Yard clearances, Bomen Yard clearances, Harefield Yard clearances.



